



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2021-22/ 3702

दिनांक 11-5-2021

ई- निविदा-सूचना सं० 03/2021-22

नगर निगम बीकानेर की ओर से विभिन्न कार्यों के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "एऐ", "ऐ" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेब साईट **www.bikanermc.org** Web site **www.SPPP.raj.nic.in** से व **http://eproc.rajabasthan.gov.in** पर देखा जा सकता है।

निविदा की कुल लागत :-25.48 लाख

॥
आयुक्त

नगर निगम, बीकानेर

दिनांक 11-5-2021

क्रमांक/निर्माण/2020-21/ 3703

प्रतिलिपि :-

1. श्रीमान् निदेशक, जनसम्पर्क एवं प्रकाशन विभाग, राजस्थान संवाद जयपुर को प्रेषित कर लेख है कि उपरोक्त निविदा का प्रकाशन कम से कम स्पेस में राज्य सरकार की प्रकाशन नीति के अनुरूप एक मुख्य क्षेत्रीय दैनिक समाचार पत्र, एक राज्य स्तरी समाचार पत्र बीकानेर संस्करण में प्रकाशन करावें।

॥
आयुक्त

नगर निगम, बीकानेर



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2021-22/ 3702

दिनांक

ई- निविदा-सूचना सं० 03/2021-22

नगर निगम बीकानेर की ओर से निम्नलिखित कार्यो के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "ऐऐ", "ऐ" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेबसाईट www.bikanermc.org Website www.SPMP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

निविदा कार्य :	1	वार्ड नं० 78 में पाडा चौक से सुलेमानी मंदरसा से होत हुए मुस्लिम मुसाफिर खाने मैन रोड तक सीवर लाईन का कार्य।	16.49 लाख
	2	मीट मार्केट में मरम्मत का कार्य।	8.99 लाख
निविदा की कुल लागत	:	25.48 लाख	
ऑनलाईन निविदा फार्म मिलने की तिथि	:	13/05/2021 09:30 बजे से 25/05/2021 18:00 बजे तक	
ऑनलाईन निविदा फार्म जमा कराने की तारीख	:	13/05/2021 09:30 बजे से 25/05/2021 18:00 बजे तक	
ऑनलाईन निविदा खोलने की तिथि	:	28/05/2021 को 17.00 बजे	

इच्छुक संवेदको को अपने डिजिटल हस्ताक्षर के माध्यम से वेब साईट <http://eproc.rajasthan.gov.in> पर रजिस्टर्ड होना आवश्यक है।

क्रमांक/निर्माण/2021-22/ 3704-05
प्रतिलिपि :-


1. श्रीमान् महापौर महोदया, नगर निगम, बीकानेर।
2. सुरक्षित पत्रावली।

आयुक्त
नगर निगम, बीकानेर
दिनांक 11-5-2021

आयुक्त
नगर निगम, बीकानेर

ई-निविदा-सूचना सं0 03/2021-22

निविदा कार्य :	1	वार्ड नं0 78 में पाडा चौक से सुलेमानी मदरसा से होत हुए मुस्लिम मुसाफिर खाने मैन रोड तक सीवर लाईन का कार्य।	16.49 लाख
	2	मीट मार्केट में मरम्मत का कार्य।	8.99 लाख
निविदा की कुल लागत	:	25.48 लाख	
ऑनलाईन निविदा फार्म मिलने की तिथि	:	...13/05/2021... 09.30 बजे से ...25/05/2021... 18:00 बजे तक	
ऑनलाईन निविदा फार्म जमा कराने की तारीख	:	...13/05/2021... 09.30 बजे से ...25/05/2021... 18:00 बजे तक	
ऑनलाईन निविदा खोलने की तिथि	:	...28/05/2021... को 17.00 बजे	


 आयुक्त
 नगर निगम, बीकानेर



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2021-22/ 3704-05

दिनांक 11/05/2021

ई- निविदा-सूचना सं0 03/2021-22

नगर निगम बीकानेर की ओर से निम्नलिखित कार्यों के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "एए", "ए" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेबसाईट www.bikanermc.org Website www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

जिला	कार्य/पैकेज का नाम	अनुमानित लागत (लाखों में)	कार्य की अवधि
बीकानेर	वार्ड नं0 78 में पाडा चौक से सुलेमानी मदरसा से होत हुए मुस्लिम मुसाफिर खाने मैन रोड तक सीवर लाईन का कार्य।	16.49	02 माह
बीकानेर	मीट मार्केट में मरम्मत का कार्य।	8.99	02 माह

निविदा प्रपत्रों को वेब साईट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदक निविदा को इलेक्ट्रॉनिक फारमेट में वेबसाईट <http://eproc.rajasthan.gov.in> पर अपलोड करावें।

नोट :- स्थानीय निकाय विभाग जयपुर के अन्तर्गत में रजिस्टर्ड फर्म एवं नगर निगम बीकानेर संभाग में रजिस्टर्ड एवं अन्य विभागों के ए एवं एए क्लास में पंजीकृत संवेदक निविदा में भाग ले सकते हैं।

आयुक्त
नगर निगम, बीकानेर

निविदा शर्तें

1. नगर निगम बीकानेर एवं स्थानीय निकाय विभाग जयपुर के अन्तर्गत उपर्युक्त श्रेणी में रजिस्टर्ड फर्म अन्य विभागों के "एए" अथवा "ए" श्रेणी के संवेदक निविदा में भाग ले सकते हैं।
2. निविदा प्रपत्रों हेतु डाउनलोड की अवधि 13/05/2021 09.30 बजे से 25/05/2021 18:00 बजे तक होगी।
3. (अ) निविदा प्रपत्र फॉरमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर 13/05/2021 09.30 बजे से 25/05/2021 18:00 बजे तक जमा करवाये जा सकते हैं एवं प्राप्त निविदाएं, इलैक्ट्रॉनिक फॉरमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर अधिशाषी अभियंता, नगर निगम, बीकानेर निर्माण अनुभाग में 28/05/2021 को 17:00 बजे बाद खोली जावेगी।
4. यदि किसी कारणवश उस दिन अवकाश रहता है तो अगले दिन उसी समय व उसी स्थान पर निविदाएं खोली जायेगी।
(अ) निविदा प्रक्रिया ऑन लाईन होगी।
(ब) इलैक्ट्रॉनिक निविदा प्रक्रिया में प्रीबीड मीटिंग का प्रावधान नहीं है।
5. अधिशाषी अभियंता, नगर निगम, बीकानेर निर्माण अनुभाग कार्यालय में संवेदक द्वारा 13/05/2021 09.30 बजे से 25/05/2021 18:00 बजे तक किसी भी कार्य दिवस में निविदा प्रपत्र को देखा जा सकता है। निविदा प्रपत्रों में निविदाकर्ता के लिये योग्यता सूचना तथा निविदाकर्ता की पात्रता, प्लान, स्पेसिफिकेशन, ड्राईंग विभिन्न कार्यों की मात्रा एवं दरों का विवरण, नियम, शर्तें एवं अन्य विवरण वर्णित हैं।
6. निविदा खोलने की दिनांक से 90 दिवस तक निविदा स्वीकृति हेतु मान्य रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है तो उसकी धरोहर राशि जब्त कर ली जावेगी।
7. किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार सक्षम अधिकारी के पास सुरक्षित हैं आरपीडब्ल्यू ए-100 की समस्त शर्तें मान्य होगी।
8. 10 लाख या अधिक लागत के कार्यों की Defect Liability Period 05 वर्ष का होगा।
9. निविदा शुल्क निम्नानुसार निर्धारित है :-


कार्य की अनुमानित राशि (लाखों में)	शुल्क
नाम	आयुक्त, नगर निगम, बीकानेर।
10 लाख तक	500 / -
10 लाख से अधिक	1000 / -

10. प्रासेसिंग फीस निम्नानुसार निर्धारित है :-

कार्य की अनुमानित राशि (लाखों में)	शुल्क
नाम	Managing Director, RISL, Jaipur
50 लाख तक	500 / -
50 लाख से अधिक	1000 / -

11. निविदा शुल्क, प्रासेसिंग फीस के भुगतान की प्रक्रिया ऑनलाईन ही होगी।
12. वित्त(सामान्य वित्तीय एवं लेखा नियम) विभाग के परिपत्र क्रमांक एफ.2(1)वित्त/ जीएण्डटी-एसपीएफसी/2017 जयपुर दिनांक 23.12.2020 के क्रम में बिड सिक्यूरिटी के स्थान पर बिड सिक्यूरिटी के सम्बंध में घोषणा पत्र (Declaration) प्राप्त करने का प्रावधान किया गया है। अतः संवेदको/फर्मों द्वारा बिड सिक्यूरिटी के स्थान पर 50/- रुपये के राजस्थान राज्य के स्टाम्प पर संलग्न घोषणा पत्र निविदा में अपलोड करना अनिवार्य है। जिसे निगम कार्यालय में निविदा स्वीकृत पश्चात् जमा करवाया जाना आवश्यक होगा।
13. निविदा हेतु ऑनलाईन भुगतान नगर निगम की वेबसाइट www.bikanermc.org पर PAY ONLINE ऑप्शन पर होगा।

14. ऑनलाईन भुगतान हेतु संवेदक को नगर निगम की वेबसाईट www.bikanermc.org पर **PAY ONLINE** पर भुगतान किये जाने के पश्चात् भुगतान रसीद, फर्म के रजिस्ट्रेशन की प्रति एवं फर्म का जी0एस0टी0 प्रमाण पत्र को ऑनलाईन साईट <http://eproc.rajasthan.gov.in> पर अपलोड करना अनिवार्य होगा।
15. Bidder द्वारा ऑनलाईन निविदा शुल्क, प्रासेसिंग शुल्क राशि **PAY ONLINE** के साथ-साथ नगर निगम के खाता धारक आयुक्त नगर निगम बीकानेर, खाता संख्या :- **2011226629965742 IFSC Code AUBL0002266, AU Small Finance Bank.** पर RTGS के माध्यम से जमा करवायी जा सकती है एवं आर0टी0जी0एस0 की रसीद ऑनलाईन अपलोड करना अनिवार्य होगा।
16. ऑनलाईन पेमेंट एवं आर0टी0जी0एस0 भुगतान के अतिरिक्त किसी अन्य तरीके के भुगतान करने वाली निविदा पर विचार नहीं किया जावेगा।
17. निविदा शुल्क, प्रासेसिंग शुल्क **Non Refundable** होगा।
18. निर्धारित शुल्क से कम भुगतान करने वाली निविदा पर विचार नहीं किया जावेगा।
19. किसी टंकणीय त्रुटि के कारण का के जी अनुसूची की विभिन्न इकाई की दरे सम्बंधित एस0ओ0आर0/बी0एस0आर0 की दरे मानी जावेगी।
20. निविदा प्रपत्र 02 कवर में होगा। यदि संवेदक द्वारा निविदा प्रपत्र अनुसार निविदा अपलोड करते समय वांछित प्रपत्र संलग्न नहीं किये जाते हैं तो उस निविदा पर विचार नहीं किया जावेगा।
21. ई- टेन्डरिंग के लिये निविदादाता हेतु निर्देश :-
 अ - इन निविदाओं में इच्छुक निविदादाता निविदा प्रपत्रों का इन्टरनेट साईट <http://eproc.rajasthan.gov.in> से डाउनलोड कर सकते हैं।
 ब - निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://eproc.rajasthan.gov.in> पर रजिस्टर करवाना होगा। ऑनलाईन निविदा में भाग लेने के लिये डिजिटल सर्टिफिकेट टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी सी ए द्वारा स्वीकृत एजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल सर्टिफिकेट लेने की आवश्यकता नहीं है।
 स- निविदादाताओं को निविदा प्रपत्र इलेक्ट्रॉनिक फॉर्मेट में उपरोक्त वेबसाईट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव डिजिटल साईन के साथ नहीं होंगे, उनके प्रस्ताव स्वीकार नहीं किये जायेंगे। कोई भी प्रस्ताव अकेले भौतिक फर्म में स्वीकार्य नहीं होगा।
 द- ऑन लाईन निविदाएं निर्धारित दिनांक एवं समय पर उपरोक्त क्रम संख्या - 3 के अनुसार खोली जायेगी।
 य - इलेक्ट्रॉनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे कि निविदा प्रपत्रों से संबंधित सभी आवश्यक दस्तावेजों की स्कैन कॉपी निविदा प्रपत्रों के साथ अटैच कर दी गयी है।
 र - कोई भी टेंडर इलेक्ट्रॉनिक जमा कराने में किसी कारण विलम्ब हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
 ल - टेंडर के प्रपत्रों में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑनलाईन दर्ज करें।


 आयुक्त
 नगर निगम, बीकानेर

क्रमांक : एफ.2(1)वित्त/जीएण्डटी-एसपीएफसी/2017


जयपुर, दिनांक : 23-12-2020

परिपत्र

वित्त विभाग की अधिसूचना क्रमांक एफ. 2(1)वित्त/जीएण्डटी - एसपीएफसी/2017 दिनांक 18.12.2020 द्वारा आरटीपीपी नियम, 2013 के नियम 42(2) में संशोधन करते हुए आमंत्रित की जाने वाली आगामी बोलियों के संदर्भ में दिनांक 31.12.2021 तक बिड सिक्यूरिटी राशि प्राप्त नहीं करने एवं इसके स्थान पर बिड सिक्यूरिटी के संबंध में घोषणा पत्र (Declaration) प्राप्त करने का प्रावधान किया गया है।


चूंकि उक्त नियमों में बिड सिक्यूरिटी राशि के स्थान पर बिड सिक्यूरिटी के संबंध में घोषणा पत्र (Declaration) प्राप्त करने का नवीन प्रावधान किया गया है। अतः समस्त उपापन संस्थाओं के उपयोगार्थ बिड सिक्यूरिटी के संबंध में लिए जाने वाले घोषणा पत्र (Declaration) का मानक प्रारूप संलग्न प्रेषित है। राजस्थान स्टाम्प अधिनियम, 1998 की धारा 3 सपठित अनुसूची के अनुच्छेद 4 के अनुसार घोषणा पत्र (Declaration) पर 50/- रुपये स्टाम्प ड्यूटी देय है तथा इस स्टाम्प ड्यूटी की राशि पर नियमानुसार 30 प्रतिशत सरचार्ज देय है। अतः समस्त उपापन संस्थाओं को निर्देशित किया जाता है कि बिड सिक्यूरिटी के संबंध में प्रस्तुत किए जाने वाले घोषणा पत्र (Declaration) पर उक्तानुसार राजस्थान राज्य में स्टाम्प ड्यूटी एवं सरचार्ज का भुगतान सुनिश्चित करावें।

संलग्न- उपरोक्तानुसार


(विमल कुमार गुप्ता)
संयुक्त शासन सचिव

प्रतिलिपि निम्नांकित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित है:-

1. सचिव, राज्यपाल/प्रमुख सचिव, मुख्यमंत्री/विशिष्ट सहायक समस्त मंत्रीगण/राज्य मंत्रीगण।
2. उप सचिव, मुख्य सचिव/निजी सचिव, समस्त अति. मुख्य सचिव/प्रमुख शासन सचिव/शासन सचिव/विशिष्ट शासन सचिव।
3. सचिव, राजस्थान विधानसभा, राजस्थान, जयपुर।
4. सचिव, लोकयुक्त सचिवालय, राजस्थान, जयपुर।
5. सचिव, राजस्थान लोक सेवा आयोग, अजमेर।
6. रजिस्ट्रार, राजस्थान उच्च न्यायालय जोधपुर/जयपुर।
7. प्रधान महालेखाकार ए एण्ड ई राजस्थान जयपुर।
8. प्रधान महालेखाकार ऑडिट राजस्थान जयपुर।
9. समस्त संयुक्त शासन सचिव/उप शासन सचिव/सचिवालय के समस्त अनुभाग/विभाग।
10. समस्त विभागाध्यक्ष/जिला कलेक्टर/संभागीय आयुक्त।
11. रजिस्ट्रार, राजस्थान सिविल सेवा अपील अधिकरण, जयपुर।
12. समस्त वित्तीय सलाहकार/मुख्य लेखाधिकारी।
13. समस्त कोषाधिकारी।
14. समस्त उपापन संस्थाएं।
15. तकनीकी निदेशक वित्त विभाग को भेजकर लेख है परिपत्र को वित्त विभाग की वेबसाइट पर प्रकाशित करवाने की व्यवस्था करावें।
16. रक्षित पत्रावली।


23/12/2020
संयुक्त शासन सचिव

Form of Bid-Securing Declaration

Date :
Bid No. :
Alternative No. :

To :

We, the undersigned, declare that:

We understand that, according to your conditions, bids must be supported by a Bid-Securing Declaration. We accept that we are required to pay the bid security amount specified in the Term and Condition of Bid, in the following cases, namely :-

- (a) when we withdraw or modify our bid after opening of bids;
- (b) when we do not execute the agreement, if any, after placement of supply/work order within the specified period;
- (c) when we fail to commence the supply of the goods or service or execute work as per supply/work order within the time specified;
- (d) when we do not deposit the performance security within specified period after the supply/work order is placed; and
- (e) if we breach any provision of code of integrity prescribed for bidding specified in the Act and Chapter VI of these rules.

In addition to above, the State Government shall debar us from participating in any procurement process undertaken for a period not exceeding three years in case where the entire bid security or any part thereof is required to be forfeited by procuring entity.

We understand this Bid Securing Declaration shall expire if :-

- (i) we are not the successful Bidder;
- (ii) the execution of agreement for procurement and performance security is furnished by us in case we are successful bidder;
- (iii) thirty days after the expiration of our Bid.
- (iv) the cancellation of the procurement process; or
- (v) the withdrawal of bid prior to the deadline for presenting bids, unless the bidding documents stipulate that no such withdrawal is permitted.

Signed : _____

Name : _____


In the capacity of : _____

Duly authorized to sign the bid for and on behalf of :

Dated on day of

Corporate Seal _____

[Note: In case of a Joint Venture, the Bid Securing Declaration must be signed in name of all partners of the Joint Venture that is submitting the bid.]





NIT No. 03 Work No. 01

Municipal Corporation, Bikaner.

Name of Work :- वार्ड नं० 78 में पाडा चौक से सुलेमानी मदरसा से होत हुए मुस्लिम मुसाफिर खाने में रोड़ तक सीवर लाईन का कार्य।

Name of Contractor :-

Date of Sales : 13.05.2021 to 25.05.2021		Date of Opening : 28.05.2021	
Tender Cost Rs 1649000/-		Earnest Money Rs. Stamp	
		Tender Fess :1000/-	
Earnest Money Cheque Draft No. :		Date :	
Earnest Money M.C.B. Receipt No. :		Date :	
Earnest Fees M.C.B. Receipt No. :		Date :	

"G" Schdule

S. No.	BSR Code	Item	Qty.	Unit	Rate	Amount
1.	SOR 2017 17.1.1.1	Earth work for Sewer line and Manhole in excavation in foundation, trenches manholes, road side chambers etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level including allowances for any additional excavation beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth up to 1.5 m	500.00	Cum	197.00	98500.00
2.	BSR 1.27.1&1.2 7.2/ B-7	Pumping out water caused by springs, tidal or river seepage, broken water main or drains and the like with pumping set of following H.P. including P.O.L./ Power consumption etc. complete. 5 to 9 H.P. .	150.00	Hour	151.00	22650.00
3.	SOR 2017 17.8.1 17.8.2	Dismantling of flexible pavements for sewer line and manholes and disposal of dismantled materials up to a lead of 50 metres as directed by Engineer including allowances for any additional dismantling beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task. Granular courses	80.00	Cum	247.00	19760.00
4.	1.2 1.1.2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	200.00	Cum	132.00	26400.00
5.	14.1.2	Brick masonry work with First class FPS bricks (min. 10.5 Mpa) in cement mortar with mechanical mixer in substructure/ super structure at all levels complete as per clause 1300 and 2200 of MoRT&H specification including all material, labour, scaffolding etc but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	40.00	Cum	4150.00	166000.00
6.	14.5.2	Plastering with cement mortar (1:3) on Brick/stone work in substructure/ super structure at any height complete as per clause 1312 of MoRT&H specification including all material, labour, scaffolding etc. 20 mm plaster on stone work	400.00	Sqm	188.00	75200.00
7.	21.1 21.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	55.00	Cum	4700.00	258500.00

8.	26.8	30mm red sand stone sun-shade (chisel-dressed) supported on red sand stone brackets, fixed in walls with cement mortar 1:4 (1 cement : 4 coarse sand) including finishing complete.	40.00	Sqm	1060.00	42400.00
9.	SOR 2017 17.19.1	Providing at site, lowering & laying in trenches, aligning & jointing of RCC pipes NP3 class (with s/s ends) IS: 458 - 1988 (amended up to date) marked and pipes from 300 mm upto 2000 mm manufactured through vertical casting process all levels with Rubber gaskets (EPDM/SBR) for sewer lines as per IS: 5382 (including cost of Rubber gaskets lubricants) as per drawing, sectional hydro testing of the sewer pipe line (including cost and conveyance of water to site for testing) etc., complete as directed by Engineer. 200 mm internal diameter	400.00	Mtr.	521.00	208400.00
10.	SOR 2017 17.28.1	Providing granular bedding having width = outer dia of pipe (Bc) + 500mm, thickness below pipe = 0.25Bc or 100mm (whichever is higher) and haunching = 0.5Bc, with graded hard crusher broken stone of 100% passing through 20mm sieve, 20 to 50 % passing through 10mm sieve and 100 % retain on 6.3mm sieve, laying in layers of thickness 10/15cm including ramming, consolidation etc complete for all type of pipes of following sizes as per drawing and or as directed by Engineer. 200 mm internal diameter	400.00	Mtr	133.00	53200.00
11.	4.13	Earth filling with available surplus soil excavated from foundations and taken only from outside of building plinth in layers not exceeding 20cm in depth, consolidating each deposited layer including ramming and watering and consolidation with lead up to 50 m and lift upto 1.5 m.	100.00	Cum	98.00	9751.00
12.	17.65	Providing and making connection to the manhole/ road side chamber/ property chamber by cutting hole in wall, making good the same with brick work/ stone masonry work in cement mortar 1:4, plaster in cement mortar 1:3, encasement of pipe at manhole with 75mm thick M15 grade concrete etc complete as directed by Engineer.	25.00	Each	707.00	17675.00
13.	17.72.1	Supplying & fixing 560mm dia SFRC manhole frame & cover as per IS : 12592-2002 in existing manholes including grouting the frame in PCC M-15 complete in all respect as directed by the Engineer. HD 20	20.00	Each	2400.00	48000.00
14.	17.34 17.34.1	Providing and constructing of SEWER-BRICK masonry circular manholes of "Type-A" with internal dia 0.90m and depth upto 1.65m having 230mm thick sewer brick masonry wall in cement sand mortar 1:4, including concreting PCC M-10 grade (1:4:8) for 225mm thick foundation including curing compaction and form work etc complete, PCC M15 for benching and channel portion, RCC M20 for 200mm thick cover slab including reinforcement, PCC M20 for fixing the manhole frame and cover using stone aggregate 20mm nominal size, 20mm thick inside and outside plaster in C. M. 1:3, inside plaster finished with floating coat of neat cement, vata in CM1:1 around pipe entering and leaving the manhole and also at the junction of masonry and concrete slab, providing and fixing of SFRC foot steps of approved make at every 0.30m height fixed in CM 1:3, supplying and fixing heavy duty SFRC manhole frame and cover as per IS 12592 (Part I and II) having clear opening of 560mm, including refilling of Jhiri, including curing, watering, ramming, hydro testing of manhole, conveyance & cost of water, and dewatering complete as directed by the Engineer. Note:- Excavation of earth work and road cutting for manhole will be measured and paid separately. Manhole "Type-A" of depth 0.90 m	25.00	Each	11500.00	287500.00
15.	17.34.2	Providing and constructing extra depth of manhole "Type-A" for depth beyond 0.90 m and upto 1.65 m with SEWER-BRICK masonry including 20mm plaster inside and outside as per drawing and direction of Engineer.	10.00	Mtr.	5800.00	58000.00
16.	.26 29.26.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1000.00	Kg.	87.50	87500.00
17.	17.58	Providing orange colour safety foot rest of minimum 6 mm thick plastic encapsulated as per IS : 10910, on 12 mm dia steel bar conforming to IS: 1786, having minimum cross section as 23 mmx25mm and over all minimum length 263 mm and width as 165 mm with minimum 112 mm space between protruded legs having 2 mm tread on top surface by ribbing or chequering besides necessary and adequate anchoring projections on tail length on 138 mm as per standard drawing and suitable to with stand the bend test and chemical resistance test as per specifications and having manufacture's permanent identification mark to be visible even after fixing, including fixing in manholes while casting in RCC manhole	10.00	Each	339.00	3390.00

		and with 30x20x15 cm cement concrete block 1:3:6 in brick/RR stone manhole complete as per design.				
18.	4.25	Providing Barricading for Trenches using 80 - 100 mm dia Wooden Ballies as vertical post, atleast 1.5m above ground level and atleast 30-45 cm below ground level at a spacing of 3 m. Two rows of PVC Tape (preferably red in colour) strip barricading horizontal strip securely tied by the vertical members. Vertical members shall be painted in red and white colour. Rate is inclusive removal and cleaning of site complete in all respect.	400.00	Mtr.	76.50	30600.00
19.	9.3	Providing and laying lean cement concrete 1:4:8 in Sub- base over prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	48.00	Cum	2300.00	111550.00
20.	17.25.1	Providing at site, lowering & laying in trenches, aligning & jointing of PVC-U pipes (SN 8) as per IS 15328 (amended up to date) and as per specifications with rubber rings with socket and spigot joint, (EPDM/SBR) for all depths for pipe length as per drawing and specification including hydraulic field testing (including the cost and conveyance of water to site for testing) and commissioning etc complete as directed by Engineer. 110 mm Nominal Dia	100.00	Mtr.	244.00	24400.00
Grand Total						1649376.00
SAY :-						16.49 Lacs

I/We Tendering above work @ above/below "G" Schedule.

Signature of Tendering Contractor



Municipal Corporation, Bikaner.

Name of Work :- मीट मार्केट में मरम्मत का कार्य।

Name of Contractor :-

Date of Sales : 13.05.2021 to 25.05.2021	Date of Opening : 28.05.2021
Tender Cost Rs 899000/-	Earnest Money Rs. Stamp
Earnest Money Cheque Draft No. :	Date :
Earnest Money M.C.B. Receipt No. :	Date :
Earnest Fees M.C.B. Receipt No. :	Date :

"G" Schdule

S. No.	BSR Code	Item	Qty.	Unit	Rate	Amount
1.	33.1.2	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50metres lead : With cement mortar 1:4 (1 cement : 4 coarse sand)	368.00	Sqm	234.00	86112.00
2.	33.4.1	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground. For door/ window/ clerestory window.	291.00	Sqm	514.00	149574.00
3.	32.50 32.50.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	115.20	Sqm	69.00	7948.80
4.	32.33.1	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	400.00	Sqm	55.50	22200.00
5.	2.4.2	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer.	15.00	Cum	427.00	6405.00
6.	9.3	Providing and laying lean cement concrete 1:4:8 in Sub- base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	20.00	Cum	2300.00	46000.00
7.	9.11	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications	75.00	Sqm	641.00	48075.00
8.	24.1.2	Brick work with FPS bricks of class designation 75 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	6.049	Cum	3760.00	22744.24

9.	.1.2	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	30.00	Cum	4310.00	129300.00
10.	32.3.3	Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:6 (1 cement : 6 fine/coarse sand)	200.00	Sqm	192.00	38400.00
11.	33.29	Distemping with dry distemper of approved brand and manufacture (two or more coats) and of required shade on new work, over and including priming coat of whitening to give an even shade.	150.00	Sqm	65.50	9825.00
12.	30.24.1	Kota stone slab flooring 25mm thick over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : Area of each slab 900 to 2000 sqcm	80.00	Sqm	1020.00	81600.00
13.	.26 29.26.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	500.00	Kg.	87.50	43750.00
14.	21.1 21.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	10.00	Cum	4700.00	47000.00
15.	30.16.1	Precast terrazzo tiles 22mm thick with graded marble chips of size upto 12mm laid in floors, and landings, jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing complete with precast tiles on 20mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) : Light shade using white cement.	50.00	Sqm	769.00	38450.00
16.	31.53.4	Stone slab roofing on ground floor with fine grained stone slab 90mm average thickness from approved quarry including filling of joints slab in cement sand mortar 1:4 with ceiling pointing in cement sand mortar 1 : 3 complete as per specification for span: Above 3.00 metre and up to 3.30 metre	27.00	Sqm	1190.00	32130.00
17.	28.7.3.1	Providing and fixing wood panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled and glazed shutter 25 mm to 40 mm thick Wire gauge GI wire gauge 24 gauge 14 mesh of IS 1568-1970 marked 85 gauge of dia 0.56 mm	50.00	Sqm	750.00	37500.00
18.	28.32.1	Providing and fixing 30mm thick wire gauge shutters using galvanised M.S. wire gauge of average width of aperture 1.4mm with wire of dia. 0.63 mm for doors, windows and clerestory windows including ISI marked Stainless Steel butt hinges with necessary screws : Second class teak wood.	20.00	Sqm	2600.00	52000.00
Grand Total						899014.04
Say						8.99 Lacs

I/We Tendering above work @ above/below "G" Schedule.

Signature of Tendering Contractor