



15

बीकानेर नगर निगम

बीकानेर (राजस्थान) फैंक्स :- 0151-2226906, फोन नं :- 0151-2226902, 0151-2226905

E-mail: nagarnigambikaner@gmail.com, Web Site www.bikanermc.org

क्रमांक / निर्माण / 2023-24 / 28480 - 481

दिनांक:- 22/09/2023

निविदा सूचना सं०...196/2023-24

नगर निगम बीकानेर की ओर से निम्नलिखित कार्य (कुल 01 कार्य) के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "एए", "ए" श्रेणी में पंजीकृत संवेदकों एवं नगर निगम में उपयुक्त श्रेणी में पंजीकृत निविदादाताओं (स्थाई रजिस्ट्रेशन नियमानुसार रिव्यू होना आवश्यक) से निर्धारित प्रपत्र में ऑफ लाईन निविदा आमंत्रित की जाती है। निविदा से संबंधित विवरण वेब साइट www.bikanermc.org एवं Website www.SPPP.raj.nic.in पर देखा जा सकता है। निर्धारित शुल्क जमा करवाकर निर्माण शाखा, नगर निगम बीकानेर से प्राप्त की जाकर दिनांक 24/09/23 को दोपहर 1:00 बजे तक विक्रय की जाकर एवं उसी दिवस 3:00 बजे प्राप्त की जाकर सायं 3:30 बजे उपस्थित संवेदकों एवं उनके प्रतिनिधि के समक्ष खोली जावेगी। डाउनलोड किये जाने की स्थिति में सुरक्षा राशि के साथ निविदा शुल्क भी जमा/डी.डी. इत्यादि संलग्न किये जाना अनिवार्य होगा। यदि निविदा विक्रय/प्राप्ति तिथि को राजकीय अवकाश होगा तो आगामी कार्य दिवस को निविदा प्राप्त एवं विक्रय की जावेगी।

क्र. सं.	कार्य का नाम	अनुमानित लागत (लाखों में)	निविदा शुल्क	अमानत राशि	कार्य अवधि
1	वार्ड नं.10 में हरीश सैनी के घर से हरि शर्मा के घर तक रंगीन ब्लॉक एवं सी.सी. सड़क का कार्य।	4.11	500	2% or 1/2%	2 माह

शर्तें

- निविदा की समस्त शर्तें कार्य दिवस में निर्माण शाखा में देखी जा सकती हैं।
- निविदा विक्रय तिथि को कम्प्यूटर से काटी गई रसीद प्रस्तुत करने के बाद ही निविदा कॉपी जारी की जायेगी।
- दर तीन माह के लिये मान्य होंगी।
- एक लिफाफे में ही निविदा डालनी होगी जिस पर कार्य का नाम, निविदा क्रमांक अंकित करने होंगे।
- नये नियमों के तहत पंजीयन रिन्यू/स्थाई पंजीकृत संवेदकों को ही निविदा प्रति दी जावेगी।
- निविदा बिना किसी कारण बताये निरस्त करने का अधिकार अद्योहस्ताक्षर करता के पास रहेगा।
- RTPP एक्ट 2012 नियम 2013 के समस्त प्रावधान लागू होंगे। RTPP एक्ट 2013 के नियम 75A के अनुसार कार्य में दर 15 प्रतिशत से अधिक नीची आने पर बिड की 85 प्रतिशत राशि में से भरी गई बिड के अन्तर राशि की 50 प्रतिशत की राशि अतिरिक्त पी०जी० के रूप में अनुबंध से पूर्व जमा कराना आवश्यक होगी।

आशुक्त
नगर निगम बीकानेर।

क्रमांक / निर्माण / 2023-24 / 28480 - 81

दिनांक:- 22/09/2023

प्रतिलिपि:-

- श्रीमान् जिला कलक्टर, बीकानेर।
- महापौर महोदया, नगर निगम, बीकानेर।
- श्रीमान् निदेशक, जनसम्पर्क एवं प्रकाशन विभाग, राजस्थान संवाद जयपुर को प्रेषित कर लेख है कि उपरोक्त निविदा का प्रकाशन कम से कम स्पेस में राज्य सरकार की प्रकाशन नीति के अनुरूप एक मुख्य क्षेत्रीय दैनिक समाचार पत्र एक मुख्य राज्य स्तरी दैनिक समाचार पत्र बीकानेर संस्करण में प्रकाशन करायें।

आशुक्त
नगर निगम बीकानेर।



NIT.No....196/23-24 Work No..01

Municipal Corporation, Bikaner.

Name of Work :- वार्ड नं० 10 में हरीश सैनी के घर से हरि शर्मा के घर तक रंगीन ब्लॉक एवं सी0सी0 सड़क का कार्य।

Name of Contractor :-

Date of Sales : As per NIT	Date of Opening : As per NIT
Tender Cost Rs 411000/-	Earnest Money Rs. 2% or 1/2%
Earnest Money Cheque Draft No. :	Date :
Earnest Money M.C.B. Receipt No. : -	Date :
Earnest Fees M.C.B. Receipt No. :	Date :

"G" Schdule

S. No.	Item Code	Item	Qty.	Unit	Rate	Amount
1.	4.2.2	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In Ordinary Rock	116.10	Cum	324.50	37674.45
2.	1.1.2	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Sand, bazri, ballast, kaankar for lead 5KM	116.10	Cum	196.76	22843.84
3.	9.3	Providing and laying lean cement concrete 1:4:8 in Sub- base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion	25.80	Cum	2775.00	71595.00
4.	9.11	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications.	69.00	Sqm	737.00	50853.00
5.	24.1.1	Brick work with FPS bricks of class designation 75 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand).	6.50	Cum	5160.00	33540.00
6.	21.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of contring and shuttering - All work upto plinth level : 1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	29.35	Cum	5810.00	170523.50
7.	17.77	Raising precast circular manhole cover and frame by taking out existing precast frame and cover, providing and fixing precast SPRC circular spacer of height 100/125/150mm, re-fixing existing manhole cover frame and cover with cement sand mortar (1:3), including making good the damage, complete as directed by Engineer.	06.00	Each	1828.00	10968.00
8.	17.80.1	Supplying & fixing 560mm dia SPRC manhole frame & cover as per IS : 12592-2002 in existing manholes including grouting the frame in PCC M-15 complete in all respect as directed by the Engineer. IID 20	5.00	Each	2685.00	13425.00
total						3839999.55
Say						38.40 Lacs

Executive Engineer
Municipal Corporation
Bikaner

I/We Tendering above work @ above/below "G" Schedule.

Signature of Tendering Contractor

E:/e/raja P/All 2023-234 G Schdule 2023-24