



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905

E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2023-24/29810

दिनांक07/10/23.....

ई- निविदा-सूचना सं० 238 / 2023-24

नगर निगम बीकानेर की ओर से विभिन्न कार्यों (कुल 03 कार्य) के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "एए", "ए" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेबसाइट www.bikanermc.org Website www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

निविदा की अनुमानित लागत :- 72.12 लाख

7

9

आयुक्त

नगर निगम, बीकानेर

दिनांक 07/10/23.....

क्रमांक/निर्माण/2023-24/29810-11

प्रतिलिपि :-

1. श्रीमान् निदेशक, जनसम्पर्क एवं प्रकाशन विभाग, राजस्थान संवाद जयपुर को प्रेषित कर लेख है कि उपरोक्त निविदा का प्रकाशन कम से कम स्पेस में राज्य सरकार की प्रकाशन नीति के अनुरूप एक मुख्य क्षेत्रीय दैनिक समाचार पत्र, एक मुख्य राज्य स्तरी दैनिक समाचार पत्र बीकानेर संस्करण में प्रकाशन करावें।

आयुक्त

नगर निगम, बीकानेर



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2023-24/29812

दिनांक 07/10/23

ई- निविदा-सूचना सं० 238/2023-24

नगर निगम बीकानेर की ओर से निम्नलिखित कार्यों के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "ऐपे", "ऐ" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती हैं। निविदा से सम्बन्धित विवरण वेबसाइट www.bikanermc.org Website www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

निविदा कार्य :	1	लालगुफा रोड़ पर स्थित हंसावत भोजक श्मशान भूमि में दीवार मरम्मत, फर्श मरम्मत एवं टीनशेड का कार्य। 5.92 लाख
	2	वार्ड नं० 62में गफूर बस्ती ईशाक मैनसर वाले के मकान से बाबूलाल गिडलासर वाले के कारखान तक, नवनपुरी मठ के मंदिर से सददाम के घर तक, जैन स्कूल के पीछे (सर्विस सेन्टर) की गलियों में, गोपेश्वर बस्ती महादेव मंदिर के सामने गली गायत्री पुरोहित से कलवानी के घर तक, गोपेश्वर बस्ती गंगाशहर रोड़ गणेश प्रजापत के घर से जुगल प्रजापत के घर तक सी०सी० सडक निर्माण कार्य, लाल गुफा रोड़ मस्जिद वाली गली में रंगीन सी०सी० कलर ब्लॉक का कार्य, व विभिन्न स्थानों पर पेचवर्क, नाली रिपेयर व क्रोस का कार्य। 38.46 लाख
	3	वार्ड नं० 62 में पिंजारा समाज कब्रिस्तान में सी०सी० कलर ब्लॉक लगाने का कार्य व पानी कुण्डी व तारबंदी का कार्य 27.74 लाख
निविदा की अनुमानित लागत	:	72.12 लाख
ऑनलाईन निविदा फार्म मिलने की तिथि	:	09/10/23 09.30 बजे से 18/10/23 18:00 बजे तक
ऑनलाईन निविदा फार्म जमा कराने की तारीख	:	09/10/23 09.30 बजे से 18/10/23 18:00 बजे तक
ऑनलाईन निविदा खोलने की तिथि	:	19/10/23 को 17.00 बजे

इच्छुक संवेदको को अपने डिजिटल हस्ताक्षर के माध्यम से वेब साईट <http://eproc.rajasthan.gov.in> पर रजिस्टर्ड होना आवश्यक है।

क्रमांक/निर्माण/2023-24/29812-13

प्रतिलिपि :-


1. श्रीमान् महापौर महोदया, नगर निगम, बीकानेर।
2. सुरक्षित पत्रावली।

आयुक्त
नगर निगम, बीकानेर
दिनांक 07/10/23

आयुक्त
नगर निगम, बीकानेर

ई- निविदा-सूचना सं० 235 / 2023-24

निविदा कार्य :	1	लालगुफा रोड़ पर स्थित हंसावत भोजक श्मशान भूमि में दीवार मरम्मत, फर्श मरम्मत एवं टीनशेड का कार्य। 5.92 लाख
	2	वार्ड नं० 62में गफूर बस्ती ईशाक मेंनसर वाले के मकान से बाबूलाल गिढलासर वाले के कारखान तक, नवनपुरी मठ के मंदिर से सददाम के घर तक, जैन स्कूल के पीछे (सर्विस सेन्टर) की गलियों में, गोपेश्वर बस्ती महादेव मंदिर के सामने गली गायत्री पुरोहित से कलवानी के घर तक, गोपेश्वर बस्ती गंगाशहर रोड़ गणेश प्रजापत के घर से जुगल प्रजापत के घर तक सी०सी० सडतक निर्माण कार्य, लाल गुफा रोड़ मस्जिद वाली गली में रंगीन सी०सी० कलर ब्लॉक का कार्य, व विभिन्न स्थानों पर पेचवर्क, नाली रिपेयर व क्रोस का कार्य। 38.46 लाख
	3	वार्ड नं० 62 में पिंजारा समाज कब्रिस्तान में सी०सी० कलर ब्लॉक लगाने का कार्य व पानी कुण्डी व तारबंदी का कार्य 27.74 लाख
निविदा की अनुमानित लागत	:	72.12 लाख
ऑनलाईन निविदा फार्म मिलने की तिथि	:	09/10/23 09:30 बजे से 18/10/23 18:00 बजे तक
ऑनलाईन निविदा फार्म जमा कराने की तारीख	:	09/10/23 09:30 बजे से 18/10/23 18:00 बजे तक
ऑनलाईन निविदा खोलने की तिथि	:	19/10/23 को 17:00 बजे


 आयुक्त
 नगर निगम, बीकानेर

बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फैक्स :- 0151-2226906, फोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2022-23/ 29812 - 13

दिनांक 07/10/23

ई- निविदा-सूचना सं० 238/2032-24

नगर निगम बीकानेर की ओर से निम्नलिखित कार्यों के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "ऐऐ", "ऐ" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेबसाइट www.bikanermc.org Website www.SPMP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

जिला	कार्य/पैकेज का नाम	अनुमानित लागत (लाखों में)	कार्य की अवधि
बीकानेर	लालगुफा रोड पर स्थित हंसावत भोजक श्मशान भूमि में दीवार मरम्मत, फर्श मरम्मत एवं टीनशेड का कार्य।	5.92	2 माह
बीकानेर	वार्ड नं० 62में गफूर बस्ती ईशाक मैनसर वाले के मकान से बाबूलाल गिढलासर वाले के कारखान तक, नवनपुरी मठ के मंदिर से सददाम के घर तक, जैन स्कूल के पीछे (सर्विस सेन्टर) की गलियों में, गोपेश्वर बस्ती महादेव मंदिर के सामने गली गायत्री पुरोहित से कलवानी के घर तक, गोपेश्वर बस्ती गंगाशहर रोड गणेश प्रजापत के घर से जुगल प्रजापत के घर तक सी०सी० सड़क निर्माण कार्य, लाल गुफा रोड मस्जिद वाली गली में रंगीन सी०सी० कलर ब्लॉक का कार्य, व विभिन्न स्थानों पर पेचवर्क, नाली रिपेयर व क्रोस का कार्य।	38.46	4 माह
बीकानेर	वार्ड नं० 62 में पिंजारा समाज कब्रिस्तान में सी०सी० कलर ब्लॉक लगाने का कार्य व पानी कुण्डी व तारबंदी का कार्य	27.74	4 माह

निविदा प्रपत्रों को वेब साइट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदक निविदा को इलेक्ट्रॉनिक फारमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर अपलोड करावें।

नोट :- स्थानीय निकाय विभाग जयपुर के अन्तर्गत उपर्युक्त श्रेणी में रजिस्टर्ड फर्म एवं नगर निगम बीकानेर संभाग में रजिस्टर्ड "डी" क्लास फर्म 15.00 लाख तक के कार्य एवं "सी" क्लास फर्म 50.00 लाख तक के कार्य एवं "बी" क्लास फर्म 1/2 प्रतिशत धरोहर राशि जमा करवाने पर एवं अन्य विभागों के "ऐऐ" अथवा "ऐ" श्रेणी के संवेदक 2 प्रतिशत धरोहर राशि जमा करवाकर निविदा में भाग ले सकते हैं।

आयुक्त
नगर निगम, बीकानेर

निविदा शर्तें

1. स्थानीय निकाय विभाग जयपुर के अन्तर्गत उपर्युक्त श्रेणी में रजिस्टर्ड (स्थायी रजिस्ट्रेशन नियमानुसार 02 वर्ष पश्चात् रिव्यू होना आवश्यक) फर्म एवं नगर निगम बीकानेर संभाग में रजिस्टर्ड "डी" क्लास फर्म 15.00 लाख तक के कार्य एवं "सी" क्लास फर्म 50.00 लाख तक के कार्य एवं "बी" क्लास फर्म 1/2 प्रतिशत धरोहर राशि जमा करवाने पर एवं अन्य विभागों के "एए" अथवा "ए" श्रेणी के संवेदक 2 प्रतिशत धरोहर राशि जमा करवाकर निविदा में भाग ले सकते हैं।
2. निविदा प्रपत्रों हेतु डाउनलोड की अवधि 09/10/23 09:30 बजे से 18/10/23 18:00 बजे तक होगी।
3. (अ) निविदा प्रपत्र फॉरमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर 09/10/23 09:30 बजे से 18/10/23 18:00 बजे तक जमा करवाये जा सकते हैं एवं प्राप्त निविदाएं, इलैक्ट्रॉनिक फॉरमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर अधिशाषी अभियंता, नगर निगम, बीकानेर निर्माण अनुभाग में 09/10/23 को 17:00 बजे बाद खोली जावेगी।
4. यदि किसी कारणवश उस दिन अवकाश रहता है तो अगले दिन उसी समय व उसी स्थान पर निविदाएं खोली जायेगी।
- (अ) निविदा प्रक्रिया ऑन लाईन होगी।
- (ब) इलैक्ट्रॉनिक निविदा प्रक्रिया में प्रीवीड मीटिंग का प्रावधान नहीं है।
5. अधिशाषी अभियंता, नगर निगम, बीकानेर निर्माण अनुभाग कार्यालय में संवेदक द्वारा 09.30 बजे से 18:00 बजे तक किसी भी कार्य दिवस में निविदा प्रपत्र को देखा जा सकता है। निविदा प्रपत्रों में निविदाकर्ता के लिये योग्यता सूचना तथा निविदाकर्ता की पात्रता, प्लान, स्पेसिफिकेशन, ड्राईंग विभिन्न कार्यों की मात्रा एवं दरों का विवरण, नियम, शर्तें एवं अन्य विवरण वर्णित है।
6. निविदा खोलने की दिनांक से 90 दिवस तक निविदा स्वीकृति हेतु मान्य रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है तो उसकी धरोहर राशि जप्त कर ली जावेगी।
7. किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार सक्षम अधिकारी के पास सुरक्षित है आरपीडब्ल्यू ए-100 की समस्त शर्तें मान्य होगी।
8. 10 लाख या अधिक लागत के कार्यों की Defect Liability Period 05 वर्ष का होगा।
9. RTPP एक्ट 2012, नियम 2013 के समस्त प्रावधान लागू होंगे। RTPP 2013 के नियम 75A के अनुसार कार्य में दर 15 प्रतिशत से अधिक नीची आने पर बिड की 85 प्रतिशत राशि में से भरी गई बिड के अन्तर राशि का 50 प्रतिशत की राशि अतिरिक्त पी0जी0 के रूप में अनुबंध से पूर्व जमा कराना आवश्यक होगा।
10. निविदा शुल्क निम्नानुसार निर्धारित है :-

कार्य की अनुमानित राशि (लाखों में)	शुल्क
नाम	आयुक्त, नगर निगम, बीकानेर।
10 लाख तक	500/-
10 लाख से अधिक	1000/-


11. प्रासेसिंग फीस निम्नानुसार निर्धारित है :-

कार्य की अनुमानित राशि (लाखों में)	शुल्क
नाम	Managing Director, RISL, Jaipur
50 लाख तक	500/-
50 लाख से अधिक	1000/-

12. निविदा शुल्क, प्रासेसिंग फीस एवं धरोहर राशि के भुगतान की प्रक्रिया ऑनलाईन ही होगी।

13. निविदा हेतु ऑनलाईन भुगतान नगर निगम की वेबसाइट www.bikanermc.org पर PAY ONLINE ऑप्शन पर होगा।

14. ऑनलाईन भुगतान हेतु संवेदक को नगर निगम की वेबसाईट www.bikanermc.org पर PAY ONLINE पर भुगतान किये जाने के पश्चात् भुगतान रसीद, फर्म के रजिस्ट्रेशन की प्रति एवं फर्म का जी0एस0टी0 प्रमाण पत्र को ऑनलाईन साईट <http://eproc.rajasthan.gov.in> पर अपलोड करना अनिवार्य होगा।
15. निविदादाता द्वारा निविदा दस्तावेज मय कार्य का "G" Schdule की प्रति को हस्ताक्षर मय नाम, तकनीकी निविदा के साथ अपलोड किया जाना अनिवार्य है अन्यथा हस्ताक्षरित निविदा दस्तावेज के अभाव में निविदा पर विचार नहीं किया जावेगा।
16. ऑनलाईन पेमेंट भुगतान के अतिरिक्त किसी अन्य तरीके के भुगतान करने वाली निविदा पर विचार नहीं किया जावेगा।
17. निविदा शुल्क, प्रोसेसिंग शुल्क Non Refundable होगा।
18. निर्धारित शुल्क से कम भुगतान करने वाली निविदा पर विचार नहीं किया जावेगा।
19. किसी टंकणीय त्रुटि के कारण का के जी अनुसूची की विभिन्न इकाई की दरे सम्बंधित एस0ओ0आर0/जी0एस0आर0 की दरें मानी जावेगी।
20. निविदा प्रपत्र 02 कवर में होगा। यदि संवेदक द्वारा निविदा प्रपत्र अनुसार निविदा अपलोड करते समय वांछित प्रपत्र संलग्न नहीं किये जाते हैं तो उस निविदा पर विचार नहीं किया जावेगा।
21. निविदादाता को श्रम नियमों का पालन करना होगा। श्रमिकों के बीमा (इश्योरेन्स) एवं पी0एफ0 जमा आदि करवाने की जिम्मेवारी सफल निविदादाता की होगी। ई0पी0एफ0 एवं ईएसआई जमा राशि के चालान श्रमिकों के नाम सहित प्रस्तुत करने पर ही रनिंग व अंतिम बिल का भुगतान किया जावेगा।
22. ई- टेन्डरिंग के लिये निविदादाता हेतु निर्देश :-
 अ - इन निविदाओं में इच्छुक निविदादाता निविदा प्रपत्रों का इन्टरनेट साईट <http://eproc.rajasthan.gov.in> से डाउनलोड कर सकते हैं।
 ब - निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://eproc.rajasthan.gov.in> पर रजिस्टर करवाना होगा। ऑनलाईन निविदा में भाग लेने के लिये डिजिटल सर्टिफिकेट टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी सी ए द्वारा स्वीकृत एजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल सर्टिफिकेट लेने की आवश्यकता नहीं है।
 स- निविदादाताओं को निविदा प्रपत्र इलेक्ट्रॉनिक फॉर्मेट में उपरोक्त वेबसाईट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव डिजिटल साईन के साथ नहीं होंगे, उनके प्रस्ताव स्वीकार नहीं किये जायेंगे। कोई भी प्रस्ताव अकेले भौतिक फर्म में स्वीकार्य नहीं होगा।
 द- ऑन लाईन निविदाएं निर्धारित दिनांक एवं समय पर उपरोक्त क्रम संख्या - 3 के अनुसार खोली जायेगी।
 य - इलेक्ट्रॉनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे कि निविदा प्रपत्रों से संबंधित सभी आवश्यक दस्तावेजों की स्कैन कॉपी निविदा प्रपत्रों के साथ अटैच कर दी गयी है।
 र - कोई भी टेंडर इलेक्ट्रॉनिक जमा कराने में किसी कारण विलम्ब हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
 ल - टेंडर के प्रपत्रों में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑनलाईन दर्ज करें।


 आयुक्त
 नगर निगम, बीकानेर



NIT No. 238/23-24 Work No. 01

Municipal Corporation , Bikaner.

Name of Work :- लालगुफा रोड पर स्थित हंसावत भोजक श्मशान भूमि में दीवार मरम्मत, फर्श मरम्मत एवं टीनशेड का कार्य।

Name of Contractor :-

Date of Sales : As per NIT		Date of Opening : As per NIT	
Tender Cost Rs 2900000/-		Earnest Money Rs. 2% or 1/2%	
Tender Fess :1000/-			
Earnest Money Cheque Draft No. :		Date :	
Earnest Money M.C.B. Receipt No. :		Date :	
Earnest Fees M.C.B. Receipt No. :		Date :	

"G" Schdule

S. No.	Item Code	Item	Qty.	Unit	Rate	Amount
1.	3.1.1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	13.17	Cum	419.00	5518.23
2.	3.2.2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and upto 40 mm	75.00	Sqm	67.20	5040.00
3.	10.1.1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m	17.10	Cum	210.50	3599.55
4.	21.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:5:10 (1 Cement : 5 fine/ coarse sand : 10 graded stone aggregate 40 mm nominal size)	10.85	Cum	4075.00	44213.75
5.	21.1 21.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	03.00	Cum	5810.00	17430.00
6.	24.1.1	Brick work with FPS bricks of class designation 75 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand).	8.23	Cum	5160.00	42466.80
7.	23.1.2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.68	Cum	6200.00	10416.00
8.	22.1.1	Centring and shuttering with plywood or steel sheet upto two stories or height upto 7.5 metre above plinth level including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	9.50	Sqm	220.00	2090.00
9.	23.19 23.19.6	Reinforcement for R.C.C. work at all levels including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars.	400.00	Kg.	64.20	25680.00
10.	24.5.1	Brick work with FPS bricks of class designation 75 in superstructure above plinth level upto two stories in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	12.12	Cum	5970.00	72356.40
11.	32.3.2	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water,	145.00	Sqm	283.50	41107.50

		curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)				
12.	30.3.1	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded 20mm nominal size stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick	4.37	Sqm	384.50	1680.27
13.	30.25	Kota stone slab flooring 25mm thick over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : Area of each slab 900 to 2000 sqcm	75.00	SqM	1299.00	97425.00
14.	31.1.3	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	75.00	Sqm	843.00	63225.00
15.	.26 29.26.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	300.00	Kg.	117.50	35250.00
16.	32.33.1	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	150.00	Sqm	85.40	12810.00
17.	27.18.1	Providing and fixing 1st quality ceramic glazed vitrified tiles of colour standard white, grey, ivory, fume, red brown, light green, light blue, and other light shades with water absorbtion less than or equal to 0.08% confirming to IS : 13753 & IS : 15622 in floor, steps etc laid on bed on neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (excluding the the cost of cement plaster on wall and pillar) Size 600mm x 600mm	45.00	Sqm	1529.00	68805.00
18.	39.48	Supplying, erecting and fixing in position specified precast RCC bench made of RCC grade M-30 consisting of 2 Nos. "L" shaped base support of thickness 100 mm back height 1000mm, front height 450 mm, base width 420mm and 5 Nos. RCC planks of size of 1500x100 x 50 mm and 1 Nos RCC planks of 150x200x50mm including joining all parts with galvanised nuts and bolts of suitable size. All bolts to be sealed after assembly with nice finish and appearance and level complete in all respect as per direction of engineer in charge. Every bench should have a manufacture's logo of appropriate size Engraved at suitable place.	05.00	Each	8500.00	5518.23
total						591113.50
Say						5.91 Lacs

I/We Tendering above work @ above/below "G" Schedule.

Signature of Tendering Contractor



Municipal Corporation , Bikaner.

Name of Work :- वार्ड नं० 62 में गफूर बस्ती ईशाक मेंसर वाले के मकान से बाबूलाल गिदलासर वाले के कारखाने तक, नवनपुरी मठ के मंदिर से सददाम के घर तक, जैन स्कूल के पीछे की गलियों में, गोपेश्वर बस्ती महादेव मंदिर के सामने वाली गली गायत्री पुरोहित से कलवानी के घर तक, गोपेश्वर बस्ती गंगाशहर रोड़ गणेश प्रजापत के घर से जुगल प्रजापत के घर तक सी०सी० सड़क निर्माण कार्य, लाल गुफा रोड़ मस्जिद वाली गली में रंगीन सी०सी० ब्लॉक का कार्य व विभिन्न स्थानों पर पेचवर्क, नाली रिपेयर व क्रॉस का कार्य।

Name of Contractor :-

Date of Sales : As per NIT	Date of Opening : As per NIT
Tender Cost Rs 3846000/-	Earnest Money Rs. 2% or 1/2%
Earnest Money Cheque Draft No. :	Tender Fess :1000/-
Earnest Money M.C.B. Receipt No. :	Date :
Earnest Fees M.C.B. Receipt No. :	Date :

"G" Schdule

S. No.	Item Code	Item	Qty.	Unit	Rate	Amount
1.	2.4.2	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer.	228.14	Cum	620.00	141446.80
2.	4.2.1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil	309.33	Cum	214.50	66351.29
3.	4.10.1.1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc.	118.88	Cum	210.50	25024.24
4.	1.1.2	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Sand, bazri, ballast, kankar for lead 5KM	649.35	Cum	196.76	127766.11
5.	21.1 21.1.6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size).	28.00	Cum	4675.00	130900.00
6.	9.3	Providing and laying lean cement concrete 1:4:8 in Sub- base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification	364.30	Cum	2775.00	733432.50

		including all material, labour, machinery, lighting, guarding and aintenance of diversion.				
7.	9.6.1	Providing and laying un-reinforced, plain cement concrete mix with Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints etc including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20	221.91	Cum	5420.00	1202752.20
8.	8.3	Providing and applying tack coat on the prepared surface with bitumen emulsion as per IS: 8887 and approved quality @ 0.2 kg/sqm with the help of spray set fitted on bitumen Container (boiler) after cleaning the surface with brooms or soft brushes and finally dusting with old gunny bags and compressed air to receive bituminous treatment complete as per clause 502 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	800.00	Sqm	9.90	7920.00
9.	8.1	Providing and applying primer coat over prepared surface of granular base with bitumen emulsion as per IS : 8887 and approved quality @ 0.6 kg/sqm with the help of spray set fitted on bitumen Container (boiler) after cleaning the surface including removing of binding material and other foreign matter with wire brushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and compressed air to receive bituminous treatment complete as per clause 502 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	800.00	Sqm	27.70	22160.00
10.	8.9	Providing laying and consolidation Semi Dense Bituminous Concrete, as per Design Mix (approved by Engineer), on prepared surface with specified graded crushed aggregates as per table 500- 15 for wearing coarse including loading of material with F.E. loader, hot mixing of stone aggregate, filler and bitumen (including cost of anti-stripping compound wherever required) heating and mixing in in computerised hot mix plant, transporting the mixed material by tippers to paver and laying with paver finisher fitted with electronic sensor control to the required level and grade, compacting by power rollers and vibratory rollers or 150 to 250 KN \ pneumatic tyred roller with TP = 0.7 Mpa, to achieve the desired density (approximately 2.3 tonne/cum) complete as per clause 508 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion but excluding primer/tack coat. 35-40 mm compacted thickness (Grade-1) using Bitumen VG-30	32.00	Cum	7190.00	230080.00
11.	9.11	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications.	62.50	Sqm	737.00	46062.50
12.	.1.2	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)]	54.50	Cum	5530.00	301385.00
13.	32.3.2	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	438.00	Sqm	283.50	124173.00
14.	30.3.1	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded 20mm nominal size stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick	69.00	Sqm	384.50	26530.50
15.	21.7	Providing and laying damp-proof course with cement concrete grade M-15 (1 : 2 : 4) mortar prepared with 1% solution of	138.00	Sqm	405.50	55959.00

		water-proof compound complete as per specification .				
16.	26.8	30mm red sand stone sun-shade (chisel-dressed) supported on red sand stone brackets, fixed in walls with cement mortar 1:4 (1 cement : 4 coarse sand) including finishing complete.	60.00	Sqm	1409.00	84540.00
17.	.26 29.26.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1500.00	Kg.	117.50	176250.00
18.	21.1 21.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	59.10	Cum	5810.00	343371.00
total						3846104.13
Say						38.46 Lacs

I/We Tendering above work @ above/below "G" Schedule.

Signature of Tendering Contractor



NIT No. 238/23-24 Work No. 03

Municipal Corporation , Bikaner.

Name of Work :- वार्ड नं० 62 में पिंजारा समाज कब्रिस्तान में सी0सी0 कलर ब्लॉक लगाने का कार्य व पानी कुण्डी व तारबंदी का कार्य।

Name of Contractor :-

Date of Sales : As per NIT		Date of Opening : As per NIT	
Tender Cost Rs 3846000/-		Earnest Money Rs. 2% or 1/2%	
Tender Fess :1000/-			
Earnest Money Cheque Draft No. :		Date :	
Earnest Money M.C.B. Receipt No. :		Date :	
Earnest Fees M.C.B. Receipt No. :		Date :	

"G" Schdule

S. No.	Item Code	Item	Qty.	Unit	Rate	Amount
1.	4.2.1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil	491.05	Cum	214.50	105330.23
2.	4.10.1.1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc.	47.92	Cum	210.50	10087.16
3.	1.1.2	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Sand, bazri, ballast, kankar for lead 5KM	538.97	Cum	196.76	106047.74
4.	21.1.7	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	175.38	Cum	4340.00	761149.20
5.	9.11	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications.	1403.00	Sqm	737.00	1034011.00
6.	21.1 21.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	56.55	Cum	5810.00	328555.50
7.	21.1 21.1.6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size).	2.74	Cum	4675.00	12809.50
8.	.1.2	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)]	19.07	Cum	5530.00	105457.10

9.	32.3.2	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	86.00	Sqm	283.50	24381.00
10.	31.61.2	Stone slab roofing on ground floor with fine grained stone slab 90mm average thickness from approved quarry including filling of joints slab in cement sand mortar 1:4 with ceiling pointing in cement sand mortar 1 : 3 complete as per specification for span: Above 2.00 metre and up to 2.50 metre	13.69	Sqm	1225.00	16770.25
11.	.26 29.26.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	150.00	Kg.	117.50	17625.00
12.	34.44	Providing and placing in position hand pump of approved quality for 40 mm diameter G.I. pipe complete with all accessories.	01.00	Each	1009.00	1009.00
13.	34.50.1	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	02.00	Each	584.00	1168.00
14.	30.3.1	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded 20mm nominal size stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick	09.00	Sqm	384.50	3460.50
15.	10.16.1	Supplying and fixing of GI chain link fencing of required width in mesh including strengthening with 2 mm dia GI wire/ G.I. staples/ G.I.U-nails/ nuts bolts with 2.4 m angle iron posts 50 mm x 50 mm x 6 mm placed every 3 metres center to center founded in M15 grade cement concrete 30cmx30cmx60cm, 0.6 metre below ground level, every 15th post, last but one end post and corner post shall be struted on both sides and end post on one side only etc complete as required and as per direction of Engineer-in-charge. Mesh size 50mm x 50mm made of GI wire 3.15mm dia	342.00	Sqm	721.00	246582.00
total						2774444.17
Say						27.74 Lacs

I/We Tendering above work @ above/below "G" Schedule.

Signature of Tendering Contractor