



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2021-22/ 4112-4114

दिनांक 12-7-2021

ई- निविदा-सूचना सं0 19/2021-22

नगर निगम बीकानेर की ओर से विभिन्न कार्यों (कुल 03 कार्य) के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "एए", "ए" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेब साईट www.bikanermc.org Web site www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।
निविदा की कुल लागत :-80.66 लाख

1
11
आयुक्त

नगर निगम, बीकानेर


दिनांक 12-7-2021

क्रमांक/निर्माण/2021-22/ 4112-4114
प्रतिलिपि :-

1. श्रीगान् निदेशक, जनसम्पर्क एवं प्रकाशन विभाग, राजस्थान संवाद जयपुर को प्रेषित कर लेख है कि उपरोक्त निविदा का प्रकाशन कम से कम स्पेस में राज्य सरकार की प्रकाशन नीति के अनुरूप एक मुख्य क्षेत्रीय दैनिक समाचार पत्र, एक मुख्य राज्य स्तरी दैनिक समाचार पत्र में प्रकाशन करावें।

11
आयुक्त

नगर निगम, बीकानेर



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2021-22/4112-4114

दिनांक 12-7-2021

ई- निविदा-सूचना सं0 19/2021-22

नगर निगम बीकानेर की ओर से निम्नलिखित कार्यों के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "एए", "ए" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेबसाईट www.bikanermc.org Website www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

निविदा कार्य :	1	वार्ड नं0 41 में पार्क मरम्मत का कार्य सेक्टर नं0 02 मनीष सोनी के सामने सेक्टर नं0 01/148 के सामने, ग्रीन इंडिया पार्क सेक्टर नं0 02 मूर्ति वाला पार्क, मुक्ताप्रसाद नगर बीकानेर। 43.19 लाख
	2	वार्ड नं0 07 में (भीनासर) गोपाल जी गाली के घर से भगवान जी पंचारिया, हंसराज रेगर के घर से पेट्रोल पम्प नोखा रोड़ तक डामर सड़क निर्माण कार्य व शिवा बस्ती में मेघराम जी ब्राह्मण के घर से जोगेन्द्र के घर तक, लक्ष्मण गेदर से जोगेन्द्र के घर तक, राकेश नाई के घर से ओम जी सुथार के घर तक, जोगेन्द्र के घर से मोहनलाल पारख के घर तक नाली क्रोस निर्माण कार्य। 27.79 लाख
	3	वार्ड नं0 66 में बालाजी मिष्टान से शौकत जी के मकान तक सी0सी0 सड़क निर्माण कार्य। 9.68 लाख
निविदा की कुल लागत	:	80.66 लाख
ऑनलाईन निविदा फार्म मिलने की तिथि	:	16/07/2021 09.30 बजे से 28/07/2021 18:00 बजे तक
ऑनलाईन निविदा फार्म जमा कराने की तारीख	:	16/07/2021 09.30 बजे से 28/07/2021 18:00 बजे तक
ऑनलाईन निविदा खोलने की तिथि	:	29/07/2021 को 17.00 बजे

इच्छुक संवेदको को अपने डिजिटल हस्ताक्षर के माध्यम से वेब साईट <http://eproc.rajasthan.gov.in> पर रजिस्टर्ड होना आवश्यक है।

क्रमांक/निर्माण/2021-22/4112-4114
प्रतिलिपि :-


1. श्रीगान् महापौर महोदया, नगर निगम, बीकानेर।
2. सुरक्षित पत्रावली।


आयुक्त
नगर निगम, बीकानेर
दिनांक 12-7-2021

आयुक्त
नगर निगम, बीकानेर

ई-निविदा-सूचना सं0 19/2021-22

निविदा कार्य :	1	वार्ड नं0 41 में पार्क मरम्मत का कार्य सेक्टर नं0 02 मनीष सोनी के सामने सेक्टर नं0 01/148 के सामने, ग्रीन इंडिया पार्क सेक्टर नं0 02 मूर्ति वाला पार्क, मुक्ताप्रसाद नगर बीकानेर। 43.19 लाख
	2	वार्ड नं0 07 में (भीनासर) गोपाल जी माली के घर से भगवान जी पंचारिया, हंसराज रेगर के घर से पेट्रोल पम्प नोखा रोड़ तक डामर सड़क निर्माण कार्य व शिवा बस्ती में मेघराम जी ब्राह्मण के घर से जोगेन्द्र के घर तक, लक्ष्मण गेदर से जोगेन्द्र के घर तक, राकेश नाई के घर से ओम जी सुथार के घर तक, जोगेन्द्र के घर से मोहनलाल पारख के घर तक नाली क्रॉस निर्माण कार्य। 27.79 लाख
	3	वार्ड नं0 66 में बालाजी मिष्ठान से शौकत जी के मकान तक सी0सी0 सड़क निर्माण कार्य। 9.68 लाख
निविदा की कुल लागत	:	80.66 लाख
ऑनलाईन निविदा फार्म मिलने की तिथि	:	16/07/2021 09.30 बजे से 28/07/2021 18:00 बजे तक
ऑनलाईन निविदा फार्म जमा कराने की तारीख	:	16/07/2021 09.30 बजे से 28/07/2021 18:00 बजे तक
ऑनलाईन निविदा खोलने की तिथि	:	29/07/2021 को 17.00 बजे


 आयुक्त
 नगर निगम, बीकानेर



(वेबसाइट पर अपलोड हेतु)

बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक / निर्माण / 2021-22 / 4112-4114

दिनांक 12-7-2021

ई- निविदा-सूचना सं० 19/2021-22

नगर निगम बीकानेर की ओर से निम्नलिखित कार्यों के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "एए", "ए" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेबसाइट www.bikanermc.org Website www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

जिला	कार्य/पैकेज का नाम	अनुमानित लागत (लाखों में)	कार्य की अवधि
बीकानेर	वार्ड नं० 41 में पार्क मरम्मत का कार्य सेक्टर नं० 02 मनीष सोनी के सामने सेक्टर नं० 01/148 के सामने, ग्रीन इंडिया पार्क सेक्टर नं० 02 मूर्ति वाला पार्क, मुक्ताप्रसाद नगर बीकानेर।	43.19	4 माह
बीकानेर	वार्ड नं० 07 में (भीनासर) गोपाल जी माली के घर से भगवान जी पंचारिया, हंसराज रेगर के घर से पेट्रोल पम्प नोखा रोड़ तक डामर सड़क निर्माण कार्य व शिवा बस्ती में मेघराम जी ब्राह्मण के घर से जोगेन्द्र के घर तक, लक्ष्मण गेदर से जोगेन्द्र के घर तक, राकेश नाई के घर से ओम जी सुथार के घर तक, जोगेन्द्र के घर से मोहनलाल पारख के घर तक नाली क्रोस निर्माण कार्य।	27.79	4 माह
बीकानेर	वार्ड नं० 66 में बालाजी मिष्ठान से शौकत जी के मकान तक सी०सी० सड़क निर्माण कार्य।	9.68	2 माह

निविदा प्रपत्रों को वेब साइट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदक निविदा को इलेक्ट्रॉनिक फारमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर अपलोड करावें।

नोट :- स्थानीय निकाय विभाग जयपुर के अन्तर्गत में रजिस्टर्ड फर्म एवं नगर निगम बीकानेर संभाग में रजिस्टर्ड एवं अन्य विभागों के ऐ एवं एए क्लास में पंजीकृत संवेदक निविदा में भाग ले सकते हैं।


आयुक्त
नगर निगम, बीकानेर

निविदा शर्तें

1. नगर निगम बीकानेर एवं स्थानीय निकाय विभाग जयपुर के अन्तर्गत उपर्युक्त श्रेणी में रजिस्टर्ड फर्म अन्य विभागों के "एए" अथवा "ए" श्रेणी के संवेदक निविदा में भाग ले सकते हैं।
2. निविदा प्रपत्रों हेतु डाउनलोड की अवधि 16/07/2021 09.30 बजे से 28/07/2021 18:00 बजे तक होगी।
3. (अ) निविदा प्रपत्र फॉरमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर 16/07/2021 09.30 बजे से 28/07/2021 18:00 बजे तक जमा करवाये जा सकते हैं एवं प्राप्त निविदाएं, इलैक्ट्रॉनिक फॉरमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर अधिशाषी अभियंता, नगर निगम, बीकानेर निर्माण अनुभाग में 29/07/2021 को 17:00 बजे बाद खोली जावेगी।
4. यदि किसी कारणवश उस दिन अवकाश रहता है तो अगले दिन उसी समय व उसी स्थान पर निविदाएं खोली जायेगी।
(अ) निविदा प्रक्रिया ऑन लाईन होगी।
(ब) इलैक्ट्रॉनिक निविदा प्रक्रिया में प्रीबीड मीटिंग का प्रावधान नहीं है।
5. अधिशाषी अभियंता, नगर निगम, बीकानेर निर्माण अनुभाग कार्यालय में संवेदक द्वारा 16/07/2021 09.30 बजे से 28/07/2021 18:00 बजे तक किसी भी कार्य दिवस में निविदा प्रपत्र को देखा जा सकता है। निविदा प्रपत्रों में निविदाकर्ता के लिये योग्यता सूचना तथा निविदाकर्ता की पात्रता, प्लान, स्पेसिफिकेशन, ड्राईंग विभिन्न कार्यों की मात्रा एवं दरों का विवरण, नियम, शर्तें एवं अन्य विवरण वर्णित है।
6. निविदा खोलने की दिनांक से 90 दिवस तक निविदा स्वीकृति हेतु मान्य रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है तो उसकी धरोहर राशि जब्त कर ली जावेगी।
7. किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार सक्षम अधिकारी के पास सुरक्षित है आरपीडब्ल्यू ए-100 की समस्त शर्तें मान्य होगी।
8. 10 लाख या अधिक लागत के कार्यों की Defect Liability Period 05 वर्ष का होगा।
9. निविदा शुल्क निम्नानुसार निर्धारित है :-


कार्य की अनुमानित राशि (लाखों में)	शुल्क
नाम	आयुक्त, नगर निगम, बीकानेर।
10 लाख तक	500 / -
10 लाख से अधिक	1000 / -

10. प्रासेसिंग फीस निम्नानुसार निर्धारित है :-

कार्य की अनुमानित राशि (लाखों में)	शुल्क
नाम	Managing Director, RISL, Jaipur
50 लाख तक	500 / -
50 लाख से अधिक	1000 / -

11. निविदा शुल्क, प्रासेसिंग फीस के भुगतान की प्रक्रिया ऑनलाईन ही होगी।
12. वित्त(सामान्य वित्तीय एवं लेखा नियम) विभाग के परिपत्र क्रमांक एफ.2(1)वित्त/ जीएण्डटी-एसपीएफसी/2017 जयपुर दिनांक 23.12.2020 के क्रम में बिड सिक्यूरिटी के स्थान पर बिड सिक्यूरिटी के सम्बंध में घोषणा पत्र (Declaration) प्राप्त करने का प्रावधान किया गया है। अतः संवेदको/फर्मों द्वारा बिड सिक्यूरिटी के स्थान पर 50/- रुपये के राजस्थान राज्य के स्टाम्प पर संलग्न घोषणा पत्र निविदा में अपलोड करना अनिवार्य है। जिसे निगम कार्यालय में निविदा स्वीकृत पश्चात् जमा करवाया जाना आवश्यक होगा।

13. निविदा हेतु ऑनलाईन भुगतान नगर निगम की वेबसाईट www.bikanermc.org पर **PAY ONLINE** ऑप्शन पर होगा।
14. ऑनलाईन भुगतान हेतु संवेदक को नगर निगम की वेबसाईट www.bikanermc.org पर **PAY ONLINE** पर भुगतान किये जाने के पश्चात् भुगतान रसीद, फर्म के रजिस्ट्रेशन की प्रति एवं फर्म का जी0एस0टी0 प्रमाण पत्र को ऑनलाईन साईट <http://eproc.rajasthan.gov.in> पर अपलोड करना अनिवार्य होगा।
15. ऑनलाईन पेमेंट भुगतान के अतिरिक्त किसी अन्य तरीके के भुगतान करने वाली निविदा पर विचार नहीं किया जावेगा।
16. निविदा शुल्क, प्रोसेसिंग शुल्क Non Refundable होगा।
17. निर्धारित शुल्क से कम भुगतान करने वाली निविदा पर विचार नहीं किया जावेगा।
18. किसी टंकणीय त्रुटि के कारण कार्ड के जी अनुसूची की विभिन्न इकाई की दरे सम्बंधित एस0ओ0आर0/बी0एस0आर0 की दरे मानी जावेगी।
19. निविदा प्रपत्र 02 कवर में होगा। यदि संवेदक द्वारा निविदा प्रपत्र अनुसार निविदा अपलोड करते समय वांछित प्रपत्र संलग्न नहीं किये जाते हैं तो उस निविदा पर विचार नहीं किया जावेगा।
20. ई- टेन्डरिंग के लिये निविदादाता हेतु निर्देश :-
- अ - इन निविदाओं में इच्छुक निविदादाता निविदा प्रपत्रों का इन्टरनेट साईट <http://eproc.rajasthan.gov.in> से डाउनलोड कर सकते हैं।
- ब - निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://eproc.rajasthan.gov.in> पर रजिस्टर करवाना होगा। ऑनलाईन निविदा में भाग लेने के लिये डिजिटल सर्टिफिकेट टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी सी ए द्वारा स्वीकृत ऐजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल सर्टिफिकेट लेने की आवश्यकता नहीं है।
- स- निविदादाताओं को निविदा प्रपत्र इलेक्ट्रॉनिक फॉर्मेट में उपरोक्त वेबसाईट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव डिजिटल साईन के साथ नहीं होंगे, उनके प्रस्ताव स्वीकार नहीं किये जायेंगे। कोई भी प्रस्ताव अकेले भौतिक फर्म में स्वीकार्य नहीं होगा।
- द- ऑन लाईन निविदाएं निर्धारित दिनांक एवं समय पर उपरोक्त क्रम संख्या - 3 के अनुसार खोली जायेगी।
- य - इलेक्ट्रॉनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे कि निविदा प्रपत्रों से संबंधित सभी आवश्यक दस्तावेजों की स्कैन कॉपी निविदा प्रपत्रों के साथ अटैच कर दी गयी है।
- र - कोई भी टेंडर इलेक्ट्रॉनिक जमा कराने में किसी कारण विलम्ब हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
- ल - टेंडर के प्रपत्रों में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑनलाईन दर्ज करें।


आयुक्त
नगर निगम, बीकानेर

Form of Bid-Securing Declaration

Date :

Bid No. :

Alternative No. :

To :

We, the undersigned, declare that:

We understand that, according to your conditions, bids must be supported by a Bid-Securing Declaration.

We accept that we are required to pay the bid security amount specified in the Term and Condition of Bid, in the following cases, namely :-

- (a) when we withdraw or modify our bid after opening of bids;
- (b) when we do not execute the agreement, if any, after placement of supply/work order within the specified period;
- (c) when we fail to commence the supply of the goods or service or execute work as per supply/work order within the time specified;
- (d) when we do not deposit the performance security within specified period after the supply/work order is placed; and
- (e) if we breach any provision of code of integrity prescribed for bidding specified in the Act and Chapter VI of these rules.

In addition to above, the State Government shall debar us from participating in any procurement process undertaken for a period not exceeding three years in case where the entire bid security or any part thereof is required to be forfeited by procuring entity.

We understand this Bid Securing Declaration shall expire if :-

- (i) we are not the successful Bidder;
- (ii) the execution of agreement for procurement and performance security is furnished by us in case we are successful bidder;
- (iii) thirty days after the expiration of our Bid.
- (iv) the cancellation of the procurement process; or
- (v) the withdrawal of bid prior to the deadline for presenting bids, unless the bidding documents stipulate that no such withdrawal is permitted.

Signed :-----

Name :-----

In the capacity of :-----

Duly authorized to sign the bid for and on behalf of :

Dated on day of

Corporate Seal -----

[Note: In case of a Joint Venture, the Bid Securing Declaration must be signed in name of all partners of the Joint Venture that is submitting the bid.]



NIT No. 19 Work No. 01

Municipal Corporation, Bikaner.

Name of Work :- पार्क मरम्मत कार्य सेक्टर नं० ०२ मनीष सोनी के सामने सेक्टर १/१४८ के सामने, ग्रीन इंडिया पार्क सेक्टर नं० ०१ सेक्टर नं० ०२ मूर्ति वाला पार्क, मुक्ताप्रसाद नगर, बीकानेर।

Name of Contractor :-

Date of Sales :	Date of Opening :
Tender Cost Rs 4319000/-	Earnest Money Rs. Stamp
Earnest Money Cheque Draft No. :	Tender Fess :1000/-
Date :	
Earnest Money M.C.B. Receipt No. :	Date :
Date :	
Earnest Fees M.C.B. Receipt No. :	Date :

"G" Schdule

S. No.	BSR Code	Item	Qty.	Unit	Rate	Amount
1.	SOR 2017 3.1.1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-incharge. In cement Mortar	120.06	Cum	284.00	34097.04
2.	3.34	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	5.04	Sqm	21.00	105.84
3.	1.2 1.1.2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	1080.06	Cum	132.00	142567.92
4.	14.1.2	Brick masonry work with First class FPS bricks (min. 10.5 Mpa) in cement mortar with mechanical mixer in substructure/ super structure at all levels complete as per clause 1300 and 2200 of MoRT&H specification including all material, labour, scaffolding etc but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	206.63	Cum	4150.00	857514.50
5.	32.3.3	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:6 (1 cement : 6 fine/ coarse sand)	2482.00	Sqm	192.00	476544.00
6.	9.3	Providing and laying lean cement concrete 1:4:8 in Sub- base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	167.60	Cum	2300.00	385480.00
7.	9.11	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimun compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications	1676.00	Sqm	641.00	1074316.00
8.	.26 29.26.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder,	9000.00	Kg.	87.50	787500.00

		railings, brackets, gates and similar works.				
9.	32.50 32.50.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	800.00	Sqm	69.00	55200.00
10.	4.13	Earth filling with available surplus soil excavated from foundations and taken only from outside of building plinth in layers not exceeding 20cm in depth, consolidating each deposited layer including ramming and watering and consolidation with lead up to 50 m and lift upto 1.5 m.	960.00	Cum	98.00	94080.00
11.	32.33.1	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	2500.00	Sqm	55.50	138750.00
12.	23.19 23.19.6	Reinforcement for R.C.C. work at all levels including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars.	2760.00	Kg.	51.50	142140.00
13.	23.1.2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	26.45	Cum	4960.00	131192.00
Grand Total						4319487.30
Say						43.19 Lacs

I/We Tendering above work @ above/below "G" Schedule.

Signature of Tendering Contractor



NIT No. 19 Work No. 02

Municipal Corporation , Bikaner.

Name of Work :- वार्ड नं० ०७ में (भीनासर) गोपाल जी माली के घर से भगवान जी पंचारिया, हंसराज रेगर के घर से पेट्रोल पम्प नोखा रोड़ तक डामर सड़क निर्माण कार्य व शिवा बस्ती में मेघराम जी ब्राह्मण के घर से जोगेन्द्र के घर तक, लक्ष्मण गेदर से जोगेन्द्र के घर तक, राकेश नाई के घर से ओम जी सुथार के घर तक, जोगेन्द्र के घर से मोहनलाल पारख के घर तक नाली क्रोस निर्माण कार्य।

Name of Contractor :-

Date of Sales :	Date of Opening :
Tender Cost Rs 2779000/-	Earnest Money Rs. Stamp
Earnest Money Cheque Draft No. :	Tender Fess :1000/-
Earnest Money M.C.B. Receipt No. :	Date :
Earnest Fees M.C.B. Receipt No. :	Date :

"G" Schdule

S.No.	Item Code	Item	Qty.	Unit	Rate	Amount
1.	.10.1.1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m.	76.89	Cum	164.00	12609.96
2.	4.2 4.2.1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil c.	1249.80	Cum	145.00	181221.00
3.	1.2 1.1.2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	1326.69	Cum	132.00	175123.08
4.	9.3	Providing and laying lean cement concrete 1:4:8 in Sub- base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	18.57	Cum	2300.00	42711.00
5.	.1.2	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	27.27	Cum	4310.00	117533.70

6.	32.3.2	Cement plastering including T&P, scaffolding, material and complete lappour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	223.44	Sqm	210.00	46922.40
7.	21.8	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	104.88	Sqm	259.00	27163.92
8.	30.3.1	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded 20mm nominal size stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick	52.44	Sqm	292.00	15312.48
9.	26.8	30mm red sand stone sun-shade (chisel-dressed) supported on red sand stone brackets, fixed in walls with cement mortar 1:4 (1 cement : 4 coarse sand) including finishing complete.	20.88	Sqm	1060.00	22132.80
10.	29.26.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	500.00	Kg	87.50	43750.00
11.	21.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	11.96	Cum	4700.00	56212.00
12.	7.3.1	Providing, laying and spreading of granular sub-base by providing coarse graded Material (Table 400-2), spreading in uniform layers with motor grader on prepared surface, mixing BY MIX IN PLACE METHOD with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per MoRT&H specification clause - 401 including all material, labour, machinery, lighting, guarding and maintenance of diversion. Grading I Material.	624.90	Cum	984.00	614901.60
13.	7.6	Providing laying, spreading and compacting stone aggregates of specific sizes as per Table 400-7 to Water Bound Macadam specification including spreading in uniform thickness; hand packing, rolling with power roller 8-10 tonnes, in stages to proper grade and camber, applying and brooming requisite type of screening (Table 400-8) binding materials to fill up the interstices of coarse aggregates, watering (with water browser) and compacting to required density, making necessary earthen bund to protect edges as per clause 404 of MoRT&H specification including all material,labour, machinery, lighting, guarding and maintenance of diversion Complete. Crusher broken - Grade-II (63-45mm)	312.45	Cum	1320.00	412434.00
14.	7.5.4	Providing laying, spreading and compacting stone aggregates of specific sizes as per Table 400-7 to Water Bound Macadam specification including spreading in uniform thickness; hand packing, rolling with power roller 8-10 tonnes, in stages to proper grade and camber, applying and brooming requisite type of screening (Table 400-8) binding materials to fill up the interstices of coarse aggregates, watering (with water browser) and compacting to required density, making necessary earthen bund to protect edges as per clause 404 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion Complete Crusher broken - Grade-III (53-22.4mm).	312.45	Cum	1400.00	437430.00
15.	8.1	Providing and applying primer coat over prepared surface of granular base with bitumen emulsion as per IS : 8887 and approved quality @ 0.6 kg/sqm with the	2748.50	Sqm	20.00	54970.00

		help of spray set fitted on bitumen Container (boiler) after cleaning the surface including removing of binding material and other foreign matter with wire brushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and compressed air to receive bituminous treatment complete as per clause 502 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.				
16.	8.3	Providing and applying tack coat on the prepared surface with bitumen emulsion as per IS: 8887 and approved quality @ 0.2 kg/sqm with the help of spray set fitted on bitumen Container (boiler) after cleaning the surface with brooms or soft brushes and finally dusting with old gunny bags and compressed air to receive bituminous treatment complete as per clause 502 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	2748.50	Sqm	7.00	19239.50
17.	8.12.1	Providing and laying open graded premix carpet 20mm thick (compacted), on prepared surface in a single course as wearing course, composed of specified graded crushed stone aggregate as per Table 500-23, premixed with bituminous binder @ 14.60 kg/ 10sqm (including cost of anti-stripping compound wherever required), including loading of material with F.E. loader, hot mixing of stone aggregate and bitumen in computerised hot mix plant, transporting the mixed material by tippers to paver and laying with paver finisher fitted with electronic sensor control to the required level and grade, compacting smooth wheeled roller 8-10 tonne capacity and finishing to required level to achieve the desired density as per clause 511 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion but excluding cost of tack coat/ seal coat.	2748.50	Sqm	94.00	258359.00
18.	8.15.1	Providing and applying premixed seal coat Type "B" comprising of thin application of fine aggregate 0.06 cum/ 10 sqm premix with bitumen binder @ 6.8 Kg/ 10 Sqm (including cost of anti-stripping compound wherever required) laying with paver finisher with electronic sensor control and rolling with power roller 8-10 tonne complete as per clause 513 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. With Bitumen VG-grade 30 sqm.	2748.50	Sqm	38.00	104443.00
19.	19.1.2	Providing, lowering, laying in trenches, aligning, fixing in position and jointing socketed rubber gasket type ISI marked uPVC pipes of Class III (6 Kg/sqcm) suitable for potable water with rubber ring joints (as per IS 4985-2000) of following outer dia with all accessories (excluding specials) complete including all material, labour, hydraulic testing and commissioning as per Technical Specifications and as per direction of Engineer. 110 mm dia.	600.00	Mtr.	273.00	136500.00
Total						2778969.44
Say						27.79 Lacs

I/We Tendering above work @ above/below "G" Schedule.

Signature of Tendering Contractor



NIT No. 19 Work No. 03

Municipal Corporation, Bikaner.**Name of Work :-** वार्ड नं० 66 बालाजी मिष्ठान से शौकत जी के मकान तक सी0सी0 सड़क निर्माण कार्य।**Name of Contractor :-**

Date of Sales :	Date of Opening :
Tender Cost Rs 968000/-	Earnest Money Rs. Stamp
Earnest Money Cheque Draft No. :	Tender Fess :500/-
Earnest Money M.C.B. Receipt No. :	Date :
Earnest Fees M.C.B. Receipt No. :	Date :

"G" Schdule

S.No.	Item Code	Item	Qty.	Unit	Rate	Amount
1.	2.4.2	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer.	214.38	Cum	427.00	91540.26
2.	1.2 1.1.2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	214.38	Cum	132.00	28298.16
3.	9.3	Providing and laying lean cement concrete 1:4:8 in Sub- base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	90.00	Cum	2300.00	207000.00
4.	21.1 21.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	135.00	Cum	4700.00	634500.00
Total						968338.42
Say						9.68 Lacs

I/We Tendering above work @ above/below "G" Schedule.**Signature of Tendering Contractor**