

(समाचार पत्रों में प्रकाशन हेतु)

बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2021-22/ 8368-8370

दिनांक 27/12/2021

ई- निविदा-सूचना सं० 75/2021-22


नगर निगम बीकानेर की ओर से विभिन्न कार्यों (कुल 12 कार्य) के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "ऐऐ", "ऐ" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेब साईट www.bikanermc.org Web site www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।
निविदा की कुल लागत :- 65.27 लाख

क्रमांक/निर्माण/2021-22/ 8368-70
प्रतिलिपि :-

1. श्रीमान् निदेशक, जनसम्पर्क एवं प्रकाशन विभाग, राजस्थान संवाद जयपुर को प्रेषित कर लेख है कि उपरोक्त निविदा का प्रकाशन कम से कम स्पेस में राज्य सरकार की प्रकाशन नीति के अनुरूप एक मुख्य क्षेत्रीय दैनिक समाचार पत्र, एक मुख्य राज्य स्तरी दैनिक समाचार पत्र में प्रकाशन करावें।

अध्यक्ष
नगर निगम, बीकानेर
दिनांक 27/12/21

अध्यक्ष
नगर निगम, बीकानेर



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2021-22/ 8368-8370

दिनांक 27/12/21

ई- निविदा-सूचना सं0 75/2021-22

नगर निगम बीकानेर की ओर से निम्नलिखित कार्यों के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "ऐऐ", "ऐ" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेबसाइट www.bikanermc.org Website www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

निविदा कार्य :	1	चतोलाई श्मशान भूमि में टीनशेड, बरामदा, पानी की टंकी का कार्य। 7.13 लाख
	2	वैद्य मधाराम कॉलोनी मेघवाल श्मशान भूमि में पानी की टंकी, टीनशेड, गेट इत्यादि का कार्य। 5.00 लाख
	3	सर्वोदय बस्ती में मेघवाल श्मशान भूमि में चार दीवारी मरम्मत का कार्य। 5.21 लाख
	4	पंवार सांखला श्मशान में भ्रमण पथ, टीन शेड एवं कलर ब्लॉक का कार्य वार्ड नं0 24 6.31 लाख
	5	वार्ड नं0 24 श्मशान (राजीव नगर) में हॉल, टीन शेड, कलर ब्लॉक का कार्य। 5.90 लाख
	6	रामावत श्मशान भूमि में चार दीवारी, टीन शेड, गेट का कार्य वार्ड नं0 24 11.38 लाख
	7	बंगला नगर में सेन समाज श्मशान भूमि में टीन शेड, पानी की टंकी का कार्य। 2.19 लाख
	8	बंगला नगर में भार्गव समाज श्मशान भूमि में टीन शेड, पानी की टंकी का कार्य। 2.04 लाख
	9	वार्ड नं0 23, जाटों की श्मशान भूमि करमीसर में चार दीवारी, गेट एवं टीन शेड का कार्य। 11.62 लाख
	10	सर्वोदय बस्ती वार्ड नं0 18 में नायक श्मशान भूमि में टीन शेड एवं फुटपाथ का कार्य। 3.26 लाख
	11	लाल गुफा रोड़ पर स्थित हंसावत भोजक श्मशान भूमि में दीवार मरम्मत, फर्श मरम्मत का कार्य। 1.45 लाख

	12	शाकद्वीपीय ब्राह्मण समाज, हरोलाई मन्दिर के पास श्मशान भूमि में विकास कार्य। 3.78 लाख
निविदा की कुल लागत	:	65.27 लाख
ऑनलाईन निविदा फार्म मिलने की तिथि	:	27.12.2021 09.30 बजे से 06.01.2022 18:00 बजे तक
ऑनलाईन निविदा फार्म जमा कराने की तारीख	:	27.12.2021 09.30 बजे से 06.01.2022 18:00 बजे तक
ऑनलाईन निविदा खोलने की तिथि	:	07.01.2022 को 17.00 बजे

इच्छुक संवेदको को अपने डिजिटल हस्ताक्षर के माध्यम से वेब साईट <http://eproc.rajasthan.gov.in> पर रजिस्टर्ड होना आवश्यक है।

क्रमांक/निर्माण/2021-22/ 8368-8370
प्रतिलिपि :-

1. श्रीमान् महापौर महोदया, नगर निगम, बीकानेर।
2. सुरक्षित पत्रावली।

आयुक्त
नगर निगम, बीकानेर
दिनांक 27/12/21


आयुक्त
नगर निगम, बीकानेर

ई-निविदा-सूचना सं0 75/2021-22

निविदा कार्य :	1	चतोलाई श्मशान भूमि में टीनशेड, बरामदा, पानी की टंकी का कार्य। 7.13 लाख
	2	वैद्य मघाराम कॉलोनी मेघवाल श्मशान भूमि में पानी की टंकी, टीनशेड, गेट इत्यादि का कार्य। 5.00 लाख
	3	सर्वोदय बस्ती में मेघवाल श्मशान भूमि में चार दीवारी मरम्मत का कार्य। 5.21 लाख
	4	पंवार सांखला श्मशान में भ्रमण पथ, टीन शेड एवं कलर ब्लॉक का कार्य वार्ड नं0 24 6.31 लाख
	5	वार्ड नं0 24 श्मशान (राजीव नगर) में हॉल, टीन शेड, कलर ब्लॉक का कार्य। 5.90 लाख
	6	रामावत श्मशान भूमि में चार दीवारी, टीन शेड, गेट का कार्य वार्ड नं0 24 11.38 लाख
	7	बंगला नगर में सेन समाज श्मशान भूमि में टीन शेड, पानी की टंकी का कार्य। 2.19 लाख
	8	बंगला नगर में भार्गव समाज श्मशान भूमि में टीन शेड, पानी की टंकी का कार्य। 2.04 लाख
	9	वार्ड नं0 23, जाटों की श्मशान भूमि करमीसर में चार दीवारी, गेट एवं टीन शेड का कार्य। 11.62 लाख
	10	सर्वोदय बस्ती वार्ड नं0 18 में नायक श्मशान भूमि में टीन शेड एवं फुटपाथ का कार्य। 3.26 लाख
	11	लाल गुफा रोड़ पर स्थित हंसावत भोजक श्मशान भूमि में दीवार मरम्मत, फर्श मरम्मत का कार्य। 1.45 लाख
	12	शाकद्वीपीय ब्राह्मण समाज, हरोलाई मन्दिर के पास श्मशान भूमि में विकास कार्य। 3.78 लाख
निविदा की कुल लागत	:	65.27 लाख
ऑनलाईन निविदा फार्म मिलने की तिथि	:	27.12.2021 09.30 बजे से 06.01.2022 18:00 बजे तक
ऑनलाईन निविदा फार्म जमा कराने की तारीख	:	27.12.2021 09.30 बजे से 06.01.2022 18:00 बजे तक
ऑनलाईन निविदा खोलने की तिथि	:	07.01.2022 को 17.00 बजे


 आयुक्त

नगर निगम, बीकानेर



बीकानेर नगर निगम

नगर निगम मार्ग, बीकानेर (राजस्थान) फ़ैक्स :- 0151-2226906, फ़ोन :- 0151-2226902, 0151-2226905
E-Mail Address :- nagarnigambikaner@gmail.com, Web Site :- www.bikanermc.org

क्रमांक/निर्माण/2021-22/ 8368-8370

दिनांक 27/12/21

ई- निविदा-सूचना सं0 75/2021-22

नगर निगम बीकानेर की ओर से निम्नलिखित कार्यों के लिये केन्द्र व राज्य सरकार के अभियांत्रिकी विभागों में "ऐऐ", "ऐ" श्रेणी में पंजीकृत संवेदको एवं नगर निगम में उपर्युक्त श्रेणी में पंजीकृत निविदादाताओं से निर्धारित प्रपत्र में ई-प्रोक्यूमेंट प्रक्रिया से ऑन लाईन निविदाएं आमंत्रित की जाती है। निविदा से सम्बन्धित विवरण वेबसाईट www.bikanermc.org Website www.SPPP.raj.nic.in से व <http://eproc.rajasthan.gov.in> पर देखा जा सकता है।

जिला	कार्य/पैकेज का नाम	अनुमानित लागत (लाखों में)	कार्य की अवधि
बीकानेर	चतोलाई श्मशान भूमि में टीनशेड, बरामदा, पानी की टंकी का कार्य।	7.13	2 माह
बीकानेर	वैद्य मधाराम कॉलोनी मेघवाल श्मशान भूमि में पानी की टंकी, टीनशेड, गेट इत्यादि का कार्य।	5.00	2 माह
बीकानेर	सर्वोदय बस्ती में मेघवाल श्मशान भूमि में चार दीवारी मरम्मत का कार्य।	5.21	2 माह
बीकानेर	पंवार सांखला श्मशान में भ्रमण पथ, टीन शेड एवं कलर ब्लॉक का कार्य वार्ड नं0 24	6.31	2 माह
बीकानेर	वार्ड नं0 24 श्मशान (राजीव नगर) में हॉल, टीन शेड, कलर ब्लॉक का कार्य।	5.90	2 माह
बीकानेर	रामावत श्मशान भूमि में चार दीवारी, टीन शेड, गेट का कार्य वार्ड नं0 24	11.38	2 माह
बीकानेर	बंगला नगर में सेन समाज श्मशान भूमि में टीन शेड, पानी की टंकी का कार्य।	2.19	1 माह
बीकानेर	बंगला नगर में भार्गव समाज श्मशान भूमि में टीन शेड, पानी की टंकी का कार्य।	2.04	1 माह
बीकानेर	वार्ड नं0 23, जाटों की श्मशान भूमि करमीसर में चार दीवारी, गेट एवं टीन शेड का कार्य।	11.62	2 माह
बीकानेर	सर्वोदय बस्ती वार्ड नं0 18 में नायक श्मशान भूमि में टीन शेड एवं फुटपाथ का कार्य।	3.26	1 माह
बीकानेर	लाल गुफा रोड पर स्थित हंसावत भोजक श्मशान भूमि में दीवार मरम्मत, फर्श मरम्मत का कार्य।	1.45	1 माह
बीकानेर	शाकद्वीपीय ब्राह्मण समाज, हरोलाई मन्दिर के पास श्मशान भूमि में विकास कार्य।	3.78	1 माह

निविदा प्रपत्रों को वेब साईट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदक निविदा को इलेक्ट्रॉनिक फारमेट में वेबसाईट <http://eproc.rajasthan.gov.in> पर अपलोड करावें।

नोट :- स्थानीय निकाय विभाग जयपुर के अन्तर्गत में रजिस्टर्ड फर्म एवं नगर निगम बीकानेर संभाग में रजिस्टर्ड एवं अन्य विभागों के ऐ ऐ एवं ऐऐ क्लास में पंजीकृत संवेदक निविदा में भाग ले सकते हैं।

आयुक्त
नगर निगम, बीकानेर

निविदा शर्तें

1. नगर निगम बीकानेर एवं स्थानीय निकाय विभाग जयपुर के अन्तर्गत उपर्युक्त श्रेणी में रजिस्टर्ड फर्म अन्य विभागों के "एए" अथवा "ए" श्रेणी के संवेदक निविदा में भाग ले सकते हैं।
2. निविदा प्रपत्रों हेतु डाउनलोड की अवधि 27.12.2021 09.30 बजे से 06.01.2022 18:00 बजे तक होगी।
3. (अ) निविदा प्रपत्र फॉरमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर 27.12.2021 09.30 बजे से 06.01.2022 18:00 बजे तक जमा करवाये जा सकते हैं एवं प्राप्त निविदाएं, इलैक्ट्रॉनिक फॉरमेट में वेबसाइट <http://eproc.rajasthan.gov.in> पर अधिशाषी अभियंता, नगर निगम, बीकानेर निर्माण अनुभाग में 07.01.2022 को 17:00 बजे बाद खोली जावेगी।
4. यदि किसी कारणवश उस दिन अवकाश रहता है तो अगले दिन उसी समय व उसी स्थान पर निविदाएं खोली जायेगी।
(अ) निविदा प्रक्रिया ऑन लाईन होगी।
(ब) इलैक्ट्रॉनिक निविदा प्रक्रिया में प्रीबीड मीटिंग का प्रावधान नहीं है।
5. अधिशाषी अभियंता, नगर निगम, बीकानेर निर्माण अनुभाग कार्यालय में संवेदक द्वारा 27.12.2021 09.30 बजे से 06.01.2022 18:00 बजे तक किसी भी कार्य दिवस में निविदा प्रपत्र को देखा जा सकता है। निविदा प्रपत्रों में निविदाकर्ता के लिये योग्यता सूचना तथा निविदाकर्ता की पात्रता, प्लान, स्पेसिफिकेशन, ड्राईंग विभिन्न कार्यों की मात्रा एवं दरों का विवरण, नियम, शर्तें एवं अन्य विवरण वर्णित है।
6. निविदा खोलने की दिनांक से 90 दिवस तक निविदा स्वीकृति हेतु मान्य रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है तो उसकी धरोहर राशि जब्त कर ली जावेगी।
7. किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार सक्षम अधिकारी के पास सुरक्षित है आरपीडब्ल्यू ए-100 की समस्त शर्तें मान्य होगी।
8. 10 लाख या अधिक लागत के कार्यों की Defect Liability Period 05 वर्ष का होगा।
9. RTTP एकट 2012, नियम 2013 के समस्त प्रावधान लागू होंगे। RTTP 2013 के नियम 75A के अनुसार कार्य में दर 15 प्रतिशत से अधिक नीची आने पर बिड की 85 प्रतिशत राशि में से भरी गई बिड के अन्तर राशि का 50 प्रतिशत की राशि अतिरिक्त पी0जी0 के रूप में अनुबंध से पूर्व जमा कराना आवश्यक होगा।
10. निविदा शुल्क निम्नानुसार निर्धारित है :-

कार्य की अनुमानित राशि (लाखों में)	शुल्क
नाम	आयुक्त, नगर निगम, बीकानेर।
10 लाख तक	500 / -
10 लाख से अधिक	1000 / -

11. प्रासेसिंग फीस निम्नानुसार निर्धारित है :-

कार्य की अनुमानित राशि (लाखों में)	शुल्क
नाम	Managing Director, RISL, Jaipur
50 लाख तक	500 / -
50 लाख से अधिक	1000 / -

12. निविदा शुल्क, प्रासेसिंग फीस के भुगतान की प्रक्रिया ऑनलाईन ही होगी।
13. वित्त(सामान्य वित्तीय एवं लेखा नियम) विभाग के परिपत्र क्रमांक एफ.2(1)वित्त/ जीएण्डटी-एसपीएफसी/2017 जयपुर दिनांक 23.12.2020 के क्रम में बिड सिक्यूरिटी के स्थान पर बिड सिक्यूरिटी के सम्बंध में घोषणा पत्र (Declaration) प्राप्त करने का प्रावधान किया गया है। अतः संवेदको/फर्मों द्वारा बिड सिक्यूरिटी के स्थान पर 50/- रुपये के राजस्थान राज्य के स्टाम्प पर संलग्न घोषणा पत्र निविदा में अपलोड करना अनिवार्य है। जिसे निगम कार्यालय में निविदा स्वीकृत पश्चात् जमा करवाया जाना आवश्यक होगा।
14. निविदा हेतु ऑनलाईन भुगतान नगर निगम की वेबसाइट www.bikanermc.org पर PAY ONLINE ऑप्शन पर होगा।

15. ऑनलाईन भुगतान हेतु संवेदक को नगर निगम की वेबसाईट www.bikanermc.org पर **PAY ONLINE** पर भुगतान किये जाने के पश्चात् भुगतान रसीद, फर्म के रजिस्ट्रेशन की प्रति एवं फर्म का जी0एस0टी0 प्रमाण पत्र को ऑनलाईन साईट <http://eproc.rajasthan.gov.in> पर अपलोड करना अनिवार्य होगा।
16. निविदादाता द्वारा निविदा दस्तावेज मय कार्य का "G" Schdule की प्रति को हस्ताक्षर मय नाम, तकनीकी निविदा के साथ अपलोड किया जाना अनिवार्य है अन्यथा हस्ताक्षरित निविदा दस्तावेज के अभाव में निविदा पर विचार नहीं किया जावेगा।
17. ऑनलाईन पेमेंट भुगतान के अतिरिक्त किसी अन्य तरीके के भुगतान करने वाली निविदा पर विचार नहीं किया जावेगा।
18. निविदा शुल्क, प्रोसेसिंग शुल्क Non Refundable होगा।
19. निर्धारित शुल्क से कम भुगतान करने वाली निविदा पर विचार नहीं किया जावेगा।
20. किसी टंकणीय त्रुटि के कारण कार्ड के जी अनुसूची की विभिन्न इकाई की दरे सम्बंधित एस0ओ0आर0/बी0एस0आर0 की दरें मानी जावेगी।
21. निविदा प्रपत्र 02 कवर में होगा। यदि संवेदक द्वारा निविदा प्रपत्र अनुसार निविदा अपलोड करते समय वांछित प्रपत्र संलग्न नहीं किये जाते हैं तो उस निविदा पर विचार नहीं किया जावेगा।
22. ई- टेन्डरिंग के लिये निविदादाता हेतु निर्देश :-
 - अ - इन निविदाओं में इच्छुक निविदादाता निविदा प्रपत्रों का इन्टरनेट साईट <http://eproc.rajasthan.gov.in> से डाउनलोड कर सकते हैं।
 - ब - निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://eproc.rajasthan.gov.in> पर रजिस्टर करवाना होगा। ऑनलाईन निविदा में भाग लेने के लिये डिजिटल सर्टिफिकेट टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी सी ए द्वारा स्वीकृत एजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल सर्टिफिकेट लेने की आवश्यकता नहीं है।
 - स- निविदादाताओं को निविदा प्रपत्र इलेक्ट्रॉनिक फॉर्मेट में उपरोक्त वेबसाईट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव डिजिटल साईन के साथ नहीं होंगे, उनके प्रस्ताव स्वीकार नहीं किये जायेंगे। कोई भी प्रस्ताव अकेले भौतिक फर्म में स्वीकार्य नहीं होगा।
 - द- ऑन लाईन निविदाएं निर्धारित दिनांक एवं समय पर उपरोक्त क्रम संख्या - 3 के अनुसार खोली जायेगी।
 - य - इलेक्ट्रॉनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे कि निविदा प्रपत्रों से संबंधित सभी आवश्यक दस्तावेजों की स्केन कॉपी निविदा प्रपत्रों के साथ अटैच कर दी गयी है।
 - र - कोई भी टेंडर इलेक्ट्रॉनिक जमा कराने में किसी कारण विलम्ब हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
 - ल - टेंडर के प्रपत्रों में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑनलाईन दर्ज करें।


अभ्युक्त
नगर निगम, बीकानेर

Form of Bid-Securing Declaration

Date :

Bid No. :

Alternative No. :

To :

We, the undersigned, declare that:

We understand that, according to your conditions, bids must be supported by a Bid-Securing Declaration.

We accept that we are required to pay the bid security amount specified in the Term and Condition of Bid, in the following cases, namely :-

- (a) when we withdraw or modify our bid after opening of bids;
- (b) when we do not execute the agreement, if any, after placement of supply/work order within the specified period;
- (c) when we fail to commence the supply of the goods or service or execute work as per supply/work order within the time specified;
- (d) when we do not deposit the performance security within specified period after the supply/work order is placed; and
- (e) if we breach any provision of code of integrity prescribed for bidding specified in the Act and Chapter VI of these rules.

In addition to above, the State Government shall debar us from participating in any procurement process undertaken for a period not exceeding three years in case where the entire bid security or any part thereof is required to be forfeited by procuring entity.

We understand this Bid Securing Declaration shall expire if :-

- (i) we are not the successful Bidder;
- (ii) the execution of agreement for procurement and performance security is furnished by us in case we are successful bidder;
- (iii) thirty days after the expiration of our Bid.
- (iv) the cancellation of the procurement process; or
- (v) the withdrawal of bid prior to the deadline for presenting bids, unless the bidding documents stipulate that no such withdrawal is permitted.

Signed :-----

Name :-----

In the capacity of :-----

Duly authorized to sign the bid for and on behalf of :

Dated on day of

Corporate Seal -----

[Note: In case of a Joint Venture, the Bid Securing Declaration must be signed in name of all partners of the Joint Venture that is submitting the bid.]

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: चतोलाई श्मशान भूमि में टीनशेड, बरामदा, पानी की टंकी का कार्य।

Contract No: E NIT No 75/2021-22/01

Name of the Bidder/ Bidding Firm / Company :						
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	60.00	Cum	4310.00	258600.00	INR Two Lakh Fifty Eight Thousand Six Hundred Only
2	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	200.00	Sqm	210.00	42000.00	INR Forty Two Thousand Only

3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	5.00	Cum	4700.00	23500.00	INR Twenty Three Thousand Five Hundred Only
4	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	40.00	Sqm	706.00	28240.00	INR Twenty Eight Thousand Two Hundred & Forty Only
5	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	4000.00	Kg.	87.50	350000.00	INR Three Lakh Fifty Thousand Only
6	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Ltr.	6.50	6500.00	INR Six Thousand Five Hundred Only
7	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 15 mm nominal bore.	10.00	Each	377.00	3770.00	INR Three Thousand Seven Hundred & Seventy Only
Total in Figures					712610.00	INR Seven Lakh Twelve Thousand Six Hundred & Ten Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

Validate Print Help

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: वैद्य मघाराम कॉलोनी मेघवाल समाज श्मशान भूमि में पानी की टंकी, टीनशेड, गेट इत्यादि का कार्य।

Contract No: E NIT No 75/2021-22/02

Name of the Bidder/ Bidding Firm / Company :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil c.	20.00	Cum	145.00	2900.00	INR Two Thousand Nine Hundred Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	20.00	Cum	132.00	2640.00	INR Two Thousand Six Hundred & Forty Only
3	Brick work with FPS bricks of class designation 75 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	10.00	Cum	3760.00	37600.00	INR Thirty Seven Thousand Six Hundred Only

4	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	20.00	Cum	4310.00	86200.00	INR Eighty Six Thousand Two Hundred Only
5	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	100.00	Sqm	210.00	21000.00	INR Twenty One Thousand Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	10.00	Cum	4700.00	47000.00	INR Forty Seven Thousand Only
7	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved	35.00	Sqm	706.00	24710.00	INR Twenty Four Thousand Seven Hundred & Ten Only
8	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	3000.00	Kg.	87.50	262500.00	INR Two Lakh Sixty Two Thousand Five Hundred Only
9	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Per Ltr	6.50	6500.00	INR Six Thousand Five Hundred Only

10	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :	2.00	Each	3450.00	6900.00	INR Six Thousand Nine Hundred Only
11	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 15 mm nominal bore.	5.00	Each	377.00	1885.00	INR One Thousand Eight Hundred & Eighty Five Only
Total in Figures					499835.00	INR Four Lakh Ninety Nine Thousand Eight Hundred & Thirty Five Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

Validate Print Help

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: सर्वोदय बस्ती में मेघवाल श्मशान भूमि में चार दीवारी मरम्मत का कार्य।

Contract No: E NIT No 75/2021-22/03

Name of the Bidder/ Bidding Firm / Company :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	250.00	Sqm	21.00	5250.00	INR Five Thousand Two Hundred & Fifty Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	250.00	Cum	132.00	33000.00	INR Thirty Three Thousand Only
3	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	75.00	Cum	4310.00	323250.00	INR Three Lakh Twenty Three Thousand Two Hundred & Fifty Only

4	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	600.00	Sqm	210.00	126000.00	INR One Lakh Twenty Six Thousand Only
5	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	600.00	Sqm	55.50	33300.00	INR Thirty Three Thousand Three Hundred Only
Total in Figures					520800.00	INR Five Lakh Twenty Thousand Eight Hundred Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: पंवार सांखला श्मशान में भ्रमण पथ, टीन शेड एवं कलर ब्लॉक का कार्य वार्ड नं0 24

Contract No: E NIT No 75/2021-22/04

Name of the Bidder/ Bidding Firm / Company :						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil c.	20.00	Cum	145.00	2900.00	INR Two Thousand Nine Hundred Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	20.00	Cum	132.00	2640.00	INR Two Thousand Six Hundred & Forty Only

3	Providing and laying lean cement concrete 1:4:8 in Sub-base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	15.00	Cum	2300.00	34500.00	INR Thirty Four Thousand Five Hundred Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	2.00	Cum	4700.00	9400.00	INR Nine Thousand Four Hundred Only
5	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications	80.00	Sqm	641.00	51280.00	INR Fifty One Thousand Two Hundred & Eighty Only
6	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	96.00	Cum	4310.00	413760.00	INR Four Lakh Thirteen Thousand Seven Hundred & Sixty Only
7	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	220.00	Sqm	210.00	46200.00	INR Forty Six Thousand Two Hundred Only
8	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded 20mm nominal size stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick	60.00	Sqm	292.00	17520.00	INR Seventeen Thousand Five Hundred & Twenty Only

9	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m²	50.00	Sqm	706.00	35300.00	INR Thirty Five Thousand Three Hundred Only
10	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	200.00	Kg.	87.50	17500.00	INR Seventeen Thousand Five Hundred Only
Total in Figures					631000.00	INR Six Lakh Thirty One Thousand Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: **वार्ड नं0 24 वाल्मिकी स्मशान (राजीव नगर) में हॉल, टीन शेड, कलर ब्लॉक का कार्य।**

Contract No: **E NIT No 75/2021-22/05**

Name of the Bidder/ Bidding Firm / Company :						
<p style="text-align: center;"><u>PRICE SCHEDULE</u></p> <p style="text-align: center; color: red;">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m.	100.00	Cum	164.00	16400.00	INR Sixteen Thousand Four Hundred Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	100	Cum	132.00	13200.00	INR Thirteen Thousand Two Hundred Only

3	Providing and laying lean cement concrete 1:4:8 in Sub-base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	50	Cum	2300.00	115000.00	INR One Lakh Fifteen Thousand Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	3	Cum	4700.00	14100.00	INR Fourteen Thousand One Hundred Only
5	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	5	Cum	4310.00	21550.00	INR Twenty One Thousand Five Hundred & Fifty Only
6	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	25	Sqm	210.00	5250.00	INR Five Thousand Two Hundred & Fifty Only
7	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	150	Kg.	87.50	13125.00	INR Thirteen Thousand One Hundred & Twenty Five Only
8	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	100	Sqm	706.00	70600.00	INR Seventy Thousand Six Hundred Only

9	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications	500	Sqm	641.00	320500.00	INR Three Lakh Twenty Thousand Five Hundred Only
Total in Figures					589725.00	INR Five Lakh Eighty Nine Thousand Seven Hundred & Twenty Five Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: रामावत श्मशान भूमि में चार दीवारी, टीन शेड, गेट का कार्य वार्ड नं० 24

Contract No: E NIT No 75/2021-22/06

Name of the Bidder/ Bidding Firm / Company :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m.	180.00	Cum	164.00	29520.00	INR Twenty Nine Thousand Five Hundred & Twenty Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	180.00	Cum	132.00	23760.00	INR Twenty Three Thousand Seven Hundred & Sixty Only

3	Providing and laying lean cement concrete 1:4:8 in Sub-base over prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	50.00	Cum	2300.00	115000.00	INR One Lakh Fifteen Thousand Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	5.00	Cum	4700.00	23500.00	INR Twenty Three Thousand Five Hundred Only
5	Brick work with FPS bricks of class designation 75 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand).	68.80	Cum	3950.00	271760.00	INR Two Lakh Seventy One Thousand Seven Hundred & Sixty Only
6	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	105.00	Cum	4310.00	452550.00	INR Four Lakh Fifty Two Thousand Five Hundred & Fifty Only
7	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	600.00	Sqm	210.00	126000.00	INR One Lakh Twenty Six Thousand Only
8	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	300.00	Kg.	87.50	26250.00	INR Twenty Six Thousand Two Hundred & Fifty Only

9	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m²	100.00	Sqm	706.00	70600.00	INR Seventy Thousand Six Hundred Only
Total in Figures					1138940.00	INR Eleven Lakh Thirty Eight Thousand Nine Hundred & Forty Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: बंगला नगर में सेन समाज श्मशान भूमि में टीनशेड, पानी की टंकी का कार्य।

Contract No: E NIT No 75/2021-22/07

Name of the Bidder/ Bidding Firm / Company :						
<p style="text-align: center;"><u>PRICE SCHEDULE</u></p> <p style="text-align: center; color: red;">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil c.	10.00	Cum	145.00	1450.00	INR One Thousand Four Hundred & Fifty Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	10.00	Cum	132.00	1320.00	INR One Thousand Three Hundred & Twenty Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	2.00	Cum	4700.00	9400.00	INR Nine Thousand Four Hundred Only

4	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	300.00	Kg.	87.50	26250.00	INR Twenty Six Thousand Two Hundred & Fifty Only
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	50.00	Sqm	69.00	3450.00	INR Three Thousand Four Hundred & Fifty Only
6	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Per Ltr.	6.50	6500.00	INR Six Thousand Five Hundred Only
7	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	200.00	Sqm	706.00	141200.00	INR One Lakh Forty One Thousand Two Hundred Only
8	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	100.00	Sqm	210.00	21000.00	INR Twenty One Thousand Only

9	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	2.00	Cum	4310.00	8620.00	INR Eight Thousand Six Hundred & Twenty Only
Total in Figures					219190.00	INR Two Lakh Nineteen Thousand One Hundred & Ninety Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

Validate Print Help

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: बंगला नगर में भार्गव समाज श्मशान भूमि में टीन शेड, पानी की टंकी का कार्य।

Contract No: E NIT No 75/2021-22/08

Name of the Bidder/ Bidding Firm / Company :						
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil c.	10.00	Cum	145.00	1450.00	INR One Thousand Four Hundred & Fifty Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	10.00	Cum	132.00	1320.00	INR One Thousand Three Hundred & Twenty Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	2.00	Cum	4700.00	9400.00	INR Nine Thousand Four Hundred Only

4	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	200.00	Kg.	87.50	17500.00	INR Seventeen Thousand Five Hundred Only
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	50.00	Sqm	69.00	3450.00	INR Three Thousand Four Hundred & Fifty Only
6	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Per Ltr.	6.50	6500.00	INR Six Thousand Five Hundred Only
7	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	200.00	Sqm	706.00	141200.00	INR One Lakh Forty One Thousand Two Hundred Only
8	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	50.00	Sqm	210.00	10500.00	INR Ten Thousand Five Hundred Only

9	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	3.00	Cum	4310.00	12930.00	INR Twelve Thousand Nine Hundred & Thirty Only
Total in Figures					204250.00	INR Two Lakh Four Thousand Two Hundred & Fifty Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: **वार्ड नं0 23 में जाटों का श्मशान भूमि करमीसर में चार दीवारी, गेट एवं टीन शेड का कार्य।**

Contract No: **E NIT No 75/2021-22/09**

Name of the Bidder/ Bidding Firm / Company :						
<p style="text-align: center;">PRICE SCHEDULE</p> <p style="text-align: center; color: red;">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m.	100.00	Cum	164.00	16400.00	INR Sixteen Thousand Four Hundred Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	100.00	Cum	132.00	13200.00	INR Thirteen Thousand Two Hundred Only

3	Providing and laying lean cement concrete 1:4:8 in Sub- base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	20.00	Cum	2300.00	46000.00	INR Forty Six Thousand Only
4	Brick work with FPS bricks of class designation 75 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	89.96	Cum	3760.00	338249.60	INR Three Lakh Thirty Eight Thousand Two Hundred & Forty Nine and Paise Sixty Only
5	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	105.00	Cum	4310.00	452550.00	INR Four Lakh Fifty Two Thousand Five Hundred & Fifty Only
6	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	600.00	Sqm	210.00	126000.00	INR One Lakh Twenty Six Thousand Only

7	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	300.00	Kg.	87.50	26250.00	INR Twenty Six Thousand Two Hundred & Fifty Only
8	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	150.00	Sqm	706.00	105900.00	INR One Lakh Five Thousand Nine Hundred Only
9	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	8.00	Cum	4700.00	37600.00	INR Thirty Seven Thousand Six Hundred Only
Total in Figures					1162149.60	INR Eleven Lakh Sixty Two Thousand One Hundred & Forty Nine and Paise Sixty Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: सर्वोदय बस्ती वार्ड नं0 18 में नायक श्मशान भूमि में टीनशेड, फुटपाथ का कार्य।

Contract No: E NIT No 75/2021-22/10

Name of the Bidder/ Bidding Firm / Company :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m.	5.00	Cum	164.00	820.00	INR Eight Hundred & Twenty Only

2	Providing and laying lean cement concrete 1:4:8 in Sub- base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	15.00	Cum	2300.00	34500.00	INR Thirty Four Thousand Five Hundred Only
3	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimun compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications	150.00	Sqm	641.00	96150.00	INR Ninety Six Thousand One Hundred & Fifty Only

4	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.80mm thick with zinc coating not less than 275gm/m ²	50.00	Sqm	829.00	41450.00	INR Forty One Thousand Four Hundred & Fifty Only
5	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	500.00	Kg.	87.50	43750.00	INR Forty Three Thousand Seven Hundred & Fifty Only
6	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	10.00	Cum	4310.00	43100.00	INR Forty Three Thousand One Hundred Only
7	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	50.00	Sqm	210.00	10500.00	INR Ten Thousand Five Hundred Only
8	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	1000.00	Sqm	55.50	55500.00	INR Fifty Five Thousand Five Hundred Only
Total in Figures					325770.00	INR Three Lakh Twenty Five Thousand Seven Hundred & Seventy Only

Quoted Rate in Figures		Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only				

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: लाल गुफा रोड़ पर स्थित हंसावत भोजक श्मशान भूमि में टीन शेड एवं कुर्सियां, पानी टंकी इत्यादि का कार्य।

Contract No: E NIT No 75/2021-22/11

Name of the Bidder/ Bidding Firm / Company :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil c.	10.00	Cum	145.00	1450.00	INR One Thousand Four Hundred & Fifty Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	10.00	Cum	132.00	1320.00	INR One Thousand Three Hundred & Twenty Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	3.00	Cum	4700.00	14100.00	INR Fourteen Thousand One Hundred Only
4	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	500.00	Kg.	87.50	43750.00	INR Forty Three Thousand Seven Hundred & Fifty Only

5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	50.00	Sqm	69.00	3450.00	INR Three Thousand Four Hundred & Fifty Only
6	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Per Ltr.	6.50	6500.00	INR Six Thousand Five Hundred Only
7	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	30.00	Sqm	706.00	21180.00	INR Twenty One Thousand One Hundred & Eighty Only
8	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	30.00	Sqm	210.00	6300.00	INR Six Thousand Three Hundred Only
9	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	2.00	Cum	4310.00	8620.00	INR Eight Thousand Six Hundred & Twenty Only
10	Supplying, erecting and fixing in position specified precast RCC bench made of RCC grade M-30 consisting of 2 Nos. "L" shaped base support of thickness 100 mm back height 1000mm, front height 450 mm, base width 420mm and 5 Nos. RCC planks of	5.00	Each	7600.00	38000.00	INR Thirty Eight Thousand Only
Total in Figures					144670.00	INR One Lakh Forty Four Thousand Six Hundred & Seventy Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

[Validate](#)
[Print](#)
[Help](#)

Percentage BoQ

Tender Inviting Authority: Commissioner Municipal Corporation Bikaner

Name of Work: शाकद्वीपीय ब्राह्मण समाज हरोलाई हनुमान जी मंदिर के पास श्मशान भूमि में दीवार राईजिंग, ब्लॉक, टीन शेड पानी की टंकी का कार्य।

Contract No: E NIT No 75/2021-22/12

Name of the Bidder/ Bidding Firm / Company :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m.	9.45	Cum	164.00	1549.80	INR One Thousand Five Hundred & Forty Nine and Paise Eighty Only
2	Carriage of materials by manual labour including loading, unloading and stacking for lead less than 0.5 Km Sand, bazri, ballast, kankar.	9.45	Cum	132.00	1247.40	INR One Thousand Two Hundred & Forty Seven and Paise Forty Only

3	Providing and laying lean cement concrete 1:4:8 in Sub-base over aprepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, Cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and aintenance of diversion.	22.03	Cum	2300.00	50669.00	INR Fifty Thousand Six Hundred & Sixty Nine Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	5.00	Cum	4700.00	23500.00	INR Twenty Three Thousand Five Hundred Only
5	Brick masonry work in cement mortar with mechanical mixer with First class bricks (min. 10.5 Mpa) in foundation (at any level) complete as per drawing and technical specification and as per clause 1000 & 1300 of MoRT&H specification including all scaffolding material, labour, machinery but excluding pointing and plastering. In cement mortar 1:4 (1 cement : 4 coarse sand)	9.14	Cum	4310.00	39393.40	INR Thirty Nine Thousand Three Hundred & Ninety Three and Paise Forty Only
6	Brick work with FPS bricks of class designation 75 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	3.54	Cum	3760.00	13310.40	INR Thirteen Thousand Three Hundred & Ten and Paise Forty Only
7	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	93.00	Sqm	210.00	19530.00	INR Nineteen Thousand Five Hundred & Thirty Only
8	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	150.00	Sqm	55.50	8325.00	INR Eight Thousand Three Hundred & Twenty Five Only

9	Providing and laying factory made chamfered edge plastic coated Designer Cement Concrete Paver blocks of required strength, thickness & size/shape, made by table vibratory method, to attain superior smooth finish using PU or equivalent moulds, laid in required Grey/Yellow/ Red or any other colour & pattern over 50 mm thick compacted bed of coarse sand, compacting and proper embedding/laying of interlocking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with fine sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc. all complete as per manufacturer's specification & direction of Engineer-in-charge: 80 mm thick C.C. paver block of M-30 grade with approved colour design and pattern.	200.00	Sqm	666.00	133200.00	INR One Lakh Thirty Three Thousand Two Hundred Only
10	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.80mm thick with zinc coating not less than 275gm/m ²	20.00	Sqm	829.00	16580.00	INR Sixteen Thousand Five Hundred & Eighty Only
11	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	300.00	Kg.	87.50	26250.00	INR Twenty Six Thousand Two Hundred & Fifty Only
12	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Per Ltr.	6.50	6500.00	INR Six Thousand Five Hundred Only

13	Supplying, erecting and fixing in position specified precast RCC bench made of RCC grade M-30 consisting of 2 Nos. "L" shaped base support of thickness 100 mm back height 1000mm, front height 450 mm, base width 420mm and 5 Nos. RCC planks of size of 1500x100 x 50 mm and 1 Nos RCC planks of 150x200x50mm including joining all parts with galvanised nuts and bolts of suitable size. All bolts to be sealed after assembly with nice finish and appearance and level complete in all respect as per direction of engineer in charge. Every bench should have a manufacture's logo of appropriate size Engraved at suitable place.	5.00	Each	7600.00	38000.00	INR Thirty Eight Thousand Only
Total in Figures					378055.00	INR Three Lakh Seventy Eight Thousand & Fifty Five Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				