




OFFICE OF THE EXECUTIVE ENGINEER (JHOTWARA ZONE)
NAGAR NIGAM GREATER, JAIPUR

NAME OF WORK :- वार्ड नं. 51 में घनश्याम विहार, राज विहार व काली माता मन्दिर गली में सड़क निर्माण कार्य।

G-Schedule

Based on RUIDP BSR 2023

S. No	Particulars	Qty	Rate	Unit	Amount in Rs.
1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil	905.00	235.50	Cum	213127.50
2	Carriage of Materials by mechanical transport including loading, unloading and stacking ::Earth Lead 5 KM	905.00	254.76	Cum	230557.80
3	Providing and laying lean cement concrete 1:4:8 in Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with bsurface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	362.00	3070.00	Cum	1111340.00
4	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion PCC M-20.	543.00	6340.00	Cum	3442620.00
TOTAL					4997645.30


Executive Engineer (Jhotwara Zone)
Nagar Nigam Greater, Jaipur

I/We hereby accepted rates

..... % above/below as per G Schedule