


**OFFICE OF THE EXECUTIVE ENGINEER (VDZ)****NAGAR NIGAM JAIPUR GREATER****AMBABADI CIRCLE AMBABADI JAIPUR**

NAME OF WORK :- विद्याघर नगर जोन के वार्ड नं. 21 के विभिन्न स्थानों पर गली व प्लॉट नं. दर्शित स्टोन बोर्ड लगाने का कार्य एवं प्लॉट नं. 2/6, सैक्टर-2 के उत्सव गार्डन के पीछे, शिव मन्दिर पार्क के बाहर, इन्टरलॉकिंग टाईल लगाने का कार्य ।

G- Schedule					RUIDP 2023
S.NO	Particular	Qty	Rate	Per	Amount in RS.
1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301.all type of soil	90.00	235.50	Cum	21195.00
2	Carriage of Materials by mechanical transport including loading, unloading and stacking Earth upto 10km.	90.00	356.36	Cum	32072.40
3	Providing and fixing precast cement concrete M-20 grade (Using mechanical Concrete Mixer) kerb stone top and bottom width 115 and 165 mm respectively, 250 mm high on 150 mm thick PCC M-10 grade foundation as per design, including fixing at site as per clause 408 of MoRT&H Specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	360.00	326	meter	117360.00
4	Providing and laying lean cement concrete 1:4:8 in Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	36.00	2955	Cum	106380.00
5	Supplying, erecting and fixing in position specified precast RCC bench made of RCC grade M-30 consisting of 2 Nos. "L" shaped base support of thickness 100 mm back height 1000mm, front height 450 mm, base width 420mm and 5 Nos. RCC planks of size of 1500x100 x 50 mm and 1 Nos RCC planks of 150x200x50mm including joining all parts with galvanised nuts and bolts of suitable size. All bolts to be sealed after assembly with nice finish and appearance and level complete in all respect as per direction of engineer in-charge. Every bench should have a manufacturer's logo of appropriate size Engraved at suitable place.	3	8860	Each	26580.00
6	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer in-charge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications.	720.00	795	Sqm	572400.00
Total Part A					875987.40

Mowls

PART B					
II-SCHEDULE					
1	Providing & fixing in position cement cct M20 grade in foundation size 0.30*0.30*0.45 mtr for Red Stone pillar of size 0.10*0.10 mtr with total height 2.10 mtr andrectangular and any other size stone board 0.05 mtr thickness and craving of letters.shapes with colour etc including all material,labour,machinery & direction of Engineer in charge.	15.00	Rate To be QUOTED	Sqm	
			TOTAL		


 EXECUTIVE ENGINEER (VDZ)
 NAGAR NIGAM JAIPUR GREATER
M. Singh

I/We hereby accepted rates
 part A..... % above/below as per G Schedule
 part B.....Rate to be Quoted

Signature of the contractor with full postal address & contact no.