कार्यालय नगर निगम कोटा, राजस्थान

राजीव गांधी भवन, दशहरा मैदान, सी.ए.डी. सर्किल–कोटा

Email : nnksouth@gmail.com, websites : www.kotamc.org.in, Ph.: 0744-2502142

–:: तकनिकी–बिड प्रपत्र ::–

कार्य का नाम :– बन्धा धर्मपुरा स्थित गौशाला में निर्माण व अन्य मरम्मत निर्माण विकास कार्य।

फर्म का नाम एंव पूर्ण पता :– .....

मो.नं. एवं ईमेल आई.डी सहित :– .....

अनुमानित राशि :– Rs. 80.64 Lacs

Tender Cost :- Rs. 3500/- **Completion Period :- 06 Months**

Processing Fees :- Rs. 1500/-

Earnest Money :- **0.50% Rs. 40320/-**

2.00% Rs. 161280/-

Date of Sale of Tender (Website) : 20-08-2026 To 27-08-2026

Date of Tender Fee, EMD Fee, Proccessing Fees Pay Online & Upload with Technical Bid Document : 20-08-2026 To 27-08-2026

Date of submission of tender earnest money, tender fee and processing fee, original DD/Banker's Cheque/copy of deposit receipt, original stamp, copy of e-Prakoap submission, technical bid and other documents : 31-08-2026 (Evening 02:00)

Date of Opening Technical BID : 31-08-2026 (04:00 PM)

Date of Opening Financial BID : तकनिकी बिड परीक्षण के पश्चात्

क्र.सं.	तकनिकी बिड के साथ निम्न दस्तावेज जो अपलोड करने है।	दस्तावेजो का विवरण	संलग्न पेज
1	धरोहर राशि/निविदा शुल्क/प्रोसेसिंग फीस ऑन–लाईन जमा रसीद की प्रति एवं ऑफ–लाईन प्रस्तुत करने पर धरोहर राशि/निविदा शुल्क/प्रोसेसिंग फीस के डिमाण्ड ड्राफ्ट की प्रति।		
2	संवेदक या फर्म का नाम व पता हेतु आधार कार्ड/मतदाता पहचान पत्र/राशन कार्ड/ड्राईविंग लाईसेन्स मय टेलीफोन नम्बर/मोबाईल नम्बर की छायाप्रति।		
3	नगर निगम कोटा व विभिन्न अभियान्त्रिकी विभागों के "A", "AA" श्रेणी में पंजीयन/सरकारी/अर्द्धसरकारी विभागों में उपर्युक्त श्रेणी में पंजीकृत संवेदकों के पंजीयन/पंजीकरण की प्रति।		
4	संवेदक को जी.एस.टी. विभाग पंजीकृत होना आवश्यक है एवं विभाग द्वारा जारी जी.एस.टी. सर्टिफिकेट की प्रति।		
5	संवेदक को जी.एस.टी. विभाग में नवीनतम जी.एस.टी. आयकर रिर्टन प्रमाण पत्र की छाया प्रति।		
6	संवेदक या फर्म का पैन कार्ड नम्बर की छायाप्रति सलंग्न करनी होगी।		
7	संवेदक या फर्म को किसी भी राजकीय संस्था विभाग, बोर्ड, कारपोरेशन अथवा उपक्रम में वर्तमान में ब्लैक लिस्टेड/डी बार अथवा डिफाल्टर घोषित नहीं किया जाना चाहिए इस संबंध में 100 रूपये के नॉन–ज्यूडिशियल स्टाम्प पैपर पर नोटरी से प्रमाणित शपथ पत्र। **(शपथ पत्र में निविदा संख्या एवं कार्य का नाम अंकित करना होगा)**		
8	संवेदक या फर्म का ई.पी.एफ. एवं ई.एस.आई. विभाग में पंजीकृत होने पर ई.पी.एफ. एवं ई.एस.आई. के रजिस्ट्रेशन की प्रति।		
9	संवेदक को राशि 100/- के नॉन–ज्यूडिशियल स्टाम्प पैपर पर नोटरी से प्रमाणित इस आशय का शपथ पत्र प्रस्तुत करना होगा कि "ई.पी.एफ. एवं ई.एस.आई. से श्रमिको के भुगतान की ओडिट कराने एवं ई.पी.एफ. एवं ई.एस.आई.के समस्त प्रकार के दायित्वों का निवर्हन एवं नियोजित श्रमिको का ई.पी.एफ. एवं ई.एस.आई. विभाग में जमा कराने का उत्तरदायित्व स्वयं संवेदक का होगा तथा भविष्य में पी.एफ. और ई.एस.आई. विभाग के किसी प्रकार के दायित्व सृजित होते है, तो उसकी समस्त जिम्मेदारी संवेदक की होगी" का शपथ पत्र तकनिकी बिड के साथ अपलोड करना होगा तथा कार्यालय द्वारा मांगे जाने पर मूल शपथ पत्र उपलब्ध कराना होगा। **(शपथ पत्र में निविदा संख्या एवं कार्य का नाम अंकित करना होगा)**		
10	संवेदक का स्वयं या फर्म के लेटरहेड पर सहमति पत्र की प्रति मय निविदादाता के हस्ताक्षर मय सील।		
	सफल/असफल		

नोट :– उपरोक्त सभी प्रमाण पत्र स्व प्रमाणित होने चाहिये एवं उक्त दी गई सूचनाऐं मेरी जानकारी एवं विश्वास के अनुसार सही है तथा हमारी फर्म निविदा की समस्त शर्तो एवं नियमों की पालना करने के लिये सहमत है।

हस्ताक्षर निविदादाता मय सील

कार्यालय नगर निगम कोटा, राजस्थान

राजीव गांधी भवन, दशहरा मैदान, सी.ए.डी. सर्किल–कोटा

Email : nnksouth@gmail.com, websites : www.kotamc.org.in, Ph.: 0744-2502142

–:: वित्तीय–बिड प्रपत्र ::–

(NIT No. 08/2026-27) ('G' Schedule Item) (Copy No. 01)

Name of Work :- बन्धा धर्मपुरा स्थित गौशाला में निर्माण व अन्य मरम्मत निर्माण विकास कार्य।

Estimated Cost :- Rs. 80.64 Lacs

Tender Cost :- Rs. 3500/- **Completion Period :- 06 Months**

Processing Fees :- Rs. 1500/-

Earnest Money :- **0.50% Rs. 40320/-**

2.00% Rs. 161280/-

Date of Sale of Tender (Website) : 20-08-2026 To 27-08-2026

Date of Tender Fee, EMD Fee, Proccessing Fees Pay Online & Upload with Technical Bid Document : 20-08-2026 To 27-08-2026

Date of submission of tender earnest money, tender fee and processing fee, original DD/Banker's Cheque/copy of deposit receipt, original stamp, copy of e-Prakoap submission, technical bid and other documents : 31-08-2026 (Evening 02:00)

Date of Opening Technical BID : 31-08-2026 (04:00 PM)

Date of Opening Financial BID : तकनिकी बिड परीक्षण के पश्चात्

Issued

To: _____

C.R. No. _____ **Date** _____

Rate Based on RUIDP ISOR 2023

S. No.	Particulars	Qty	Unit	Rate	Amount
1	Earth work in excavation in soil unsuitable for road construction such as marshy soil including pumping out water, removal of the same and disposal with all lift and lead upto 1 km as per MoRT&H specification clause 301.	154.5	Cum	214.50	33140.25
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	77.5	Cum	5000.00	387500.00
3	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	122.50	Cum	4860.00	595350.00
4	Random rubble dry stone Kharanja (soling) under floor.	2.64	Cum	2270.00	5992.80
5	Centring and shuttering with plywood or steel sheet upto two stories (each story of height upto 3.5 metre from floor level) including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	54.0	Sqm	236.50	12771.00
6	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	10.1	Cum	6340.00	63875.50
7	Brick work with FPS bricks of class designation 75 in superstructure above plinth level upto two stories in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	18.6	Cum	6920.00	128885.00
8	Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 12 mm cement plaster of mix : 1:6 (1 cement : 6 fine/ coarse sand)	1065.0	Sqm	227.00	241755.00

9	Providing and fixing Granite stone slab mirror polished and machine edge cut in walls, pillars, steps, Shelves, Sills Counters, Floors etc. laid on 12mm (Av.) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) jointing with white cement mortar 1:2 (1white cement : 2 marble dust) with pigment to match the shade of the marble slab including grinding, rubbing and polishing complete. 27.2.1 Jhunjhunu / Jalore (Red / Choclate Colour) 27.2.1.1 Upto to 1500 Cm2 Tiles	14.8	Sqm	3025.00	44770.00

10	Reinforcement for R.C.C. work at all levels including straightening, cutting, bending, placing in position and binding all complete.	3000.0	kg	83.30	249900.00
11	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:	8125.00	kg	114.50	930312.50
12	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth	30.00	Cum	254.76	7642.80
13	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade New work (Two or more coats applied @ 1.43 ltr/ 10 sqm. over and including base coat of water proofing cement paint applied @ 2.20 kg/ 10 sqm).	250.00	Sqm	132.50	33125.00
14	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	1000.00	Sqm	159.50	159500.00
15	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Cement Concrete Grade M-15 and above and PCC blocks	7.50	Cum	678.00	5085.00
16	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Dismantling Brick / Tile work	66.00	Cum	275.50	18183.00
17	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete	100.00	Sqm	204.50	20450.00
18	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	5.00	Cum	4575.00	22875.00
19	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : **1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)**	90.00	Cum	5510.00	495900.00
20	Grading roof for water proofing treatment with water proofing compound Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	15.00	Cum	6250.00	93750.00
21	Providing and fixing 1st quality MAT finished ceramic tile size 300x300mm confirming to IS : 13755 and IS : 15622 colour such as white, grey, ivory, fume red brown, light green, light blue and other light shades in floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (including the cost of cement mortar bed 1:4).	25.00	Sqm	864.00	21600.00
22	Supply , Installation, Testing and Comissioning of site fabricated ducting made from GI sheet metal conforming to IS:277 with a zinc coating grade not less than 120 GSM (both side inclusive) & fabricated as per IS:655 and as per approved drawings & designs including the cost of hangers, supports, angle, expansion fasteners , closed cell neoprene gasket T&P etc. as required of following thickness. Test Certificate for Galavanizing with lot no. to be submitted. All as per pre approved by Engineer in-charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .	1055.00	Sqm	1421.00	1499155.00

23	Brick on edge flooring with bricks of class designation 75 including cement slurry etc. complete in cement mortar : **1:4 (1 cement : 4 coarse sand)**	650.00	Sqm	758.00	492700.00
24	Providing and laying damp-proof course with cement concrete grade M-15 (1 : 2 : 4) mortar prepared with 1% solution of water-proof compound complete as per specification . including Providing/mixing of synthetic fibers compulsorily complying with IS 16481:2022 of 06 mm/12 mm length to be mixed @ 0.25% by weight of Cement i.e. 125 gms per 50 kg Cement up to 900 gms per cum of Concrete/ mortar 50mm thick.	120.00	Sqm	445.00	53400.00
25	Hydraulic Excavator of 1 cum bucket.	120.00	Hour	930.00	111600.00
26	Galvanised wire mesh of average width of aperture 1.4 mm and nominal dia. of wire 0.63 mm.	500.00	Sqm	194.00	97000.00
27	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, ncluding getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m	68.00	Cum	229.50	15606.00
28	Random rubble dry stone Kharanja (soling) under floor.	45.32	Cum	2270.00	102876.40
29	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	22.68	Cum	4575.00	103761.00
30	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	26.80	Cum	6340.00	169912.00
31	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	28.32	Cum	5910.00	167371.20
32	Reinforcement for R.C.C. work at all levels including straightening, cutting, bending, placing in position and binding all complete. Hot rolled deformed bars	4560.00	Kg	83.30	379848.00
33	Providing and fixing 1st quality standard white, grey, ivory, fume red brown, light green, light blue and other light shades glazed tiles confirming to IS : 13753 & IS :15622 of size 200mm x 300mm in walls, floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (excluding the cost of cement plaster on walls and pillar).	72.00	Sqm	891.00	64152.00
34	Earth work in excavation in soil unsuitable for road construction such as marshy soil including pumping out water, removal of the same and disposal with all lift and lead upto 1 km as per MoRT&H specification clause 301.	43.20	Cum	214.50	9266.40
35	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	4.32	Cum	5000.00	21600.00
36	Random rubble masonry with hard stone in foundation and plinth : 25.1.1 Cement mortar 1:6 (1 cement : 6 coarse sand)	38.88	Cum	4860.00	188956.80

37	Random rubble dry stone Kharanja (soling) under floor.	15.48	Cum	2270.00	35139.60
38	Centring and shuttering with plywood or steel sheet upto two stories (each story of height upto 3.5 metre from floor level) including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	9.60	Sqm	236.50	2270.40
39	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	4.32	Cum	6340.00	27388.80
40	Brick work with FPS bricks of class designation 75 in superstructure above plinth level upto two stories in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	29.56	Cum	6920.00	204555.20
41	Centring and shuttering with plywood or steel sheet upto two stories (each story of height upto 3.5 metre from floor level) including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform.	16.20	Sqm	456.00	7387.20
42	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto two stories excluding the cost of centring, shuttering, finishing and reinforcement: including Providing /mixing of synthetic fibers compulsorily complying with IS 16481:2022 of 06 mm/12 mm length to be mixed @ 0.25% by weight of Cement i.e. 125 gms per 50 kg Cement up to 900 gms per cum of Concrete/ mortar M-20 Grade Concrete (1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size) -As per design mix)	19.80	Sqm	7660.00	151668.00
43	Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 12 mm cement plaster of mix : 1:6 (1 cement : 6 fine/ coarse sand)	288.00	Sqm	227.00	65376.00
44	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	5.40	Cum	5910.00	31914.00
45	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	480.00	Sqm	93.10	44688.00
46	Reinforcement for R.C.C. work at all levels including straightening, cutting, bending, placing in position and binding all complete.	3000.00	Kg	83.30	249900.00
47	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	200.00	Sqm	114.00	22800.00
48	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:	600.00	Kg	115.50	69300.00
49	Kota stone slab flooring 25mm thick over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : Area of each slab 900 to 2000 sqcm	36.00	Sqm	1365.00	49140.00
	H-Schedule Item				
50	Green Net (per sqft)	500.00	Sqm	107.00	53500.00
			TOTAL		**8064594.85**
			Say as		**80.64 Lacs**

Terms & Conditions:-

1. Conditional tender shall not be accepted.

2. In case of any error in rates or nomenclature, the same shall be paid as per "G" Schedule Item on RUIDP ISOR 2023.

3. आर.टी.पी.पी. एक्ट 2012 एवं आर.टी.पी.पी. 2013 के नियम एवं शर्ते निविदा में लागू होगें।

4. निविदाताओं को निविदा शुल्क/बोली प्रतिभूति एवं प्रोसेसिंग फीस आन लाईन नगर निगम कोटा की वेबसाईट http://kotamc.org.com, पर SUBMISSION DATE AND TIME से पूर्व जमा करवाकर उससे प्राप्त होने वाली रसीद को स्केन करके http://eproc.rajasthan.gov.in, पर अपलोड करने पर ही निविदा को मान्य किया जावेगा। निविदा शुल्क एवं प्रोसेसिंग फीस (Non-Refundable) वापस नही की जावेगी। निविदा शुल्क/धरोहर राशि/प्रोसेसिंग शुल्क के डी.डी. भी मान्य होंगे। (संवेदक निविदा से संबंधित निविदा शुल्क/प्रोसेसिंग शुल्क/धरोहर राशि के डी.डी. इत्यादि फर्म के नाम से बनवाये।) निविदा शुल्क एवं प्रोसेसिंग फीस के डी.डी. (Non-Refundable) वापस नही की जावेगी।

5. निविदा प्रपत्र में दिए गए निर्देशों के अनुसार प्रस्ताव उचित रूप में ऑन–लाईन प्रस्तुत किए जाने हैं।

6. ई–बोली प्रपत्र दो भागों में है। प्रथम भाग तकनिकी बिड है तथा द्वितीय भाग वित्तीय बिड है। बोली दाता द्वारा तकनिकी बिड हेतु यह प्रपत्र मय संलग्न व वांछनीय दस्तावेज के प्रत्येक पृष्ठ पर हस्ताक्षर करते हुये मय सील e-proc पोर्टल पर अपलोड करनी है। वित्तीय बिड आनलाईन BoQ में ही प्रस्तुत की जानी है। इससे भिम्न रूप मे प्रस्तुत प्रस्तावों पर विचार नहीं किया जाएगा। वित्तीय दर वाला बिड डाक्यूमेंट केवल उन्ही फर्मो का खोला जायेगा, जिन्हें कमेटी द्वारा तकनिकी बिड डाक्यूमेंट में योग्य समझा जायेगा।

7. संवेदक को किसी किसी भी राजकीय संस्था विभाग, बोर्ड, कारपोरेशन अथवा उपक्रम में वर्तमान में ब्लैक लिस्टेड/डी बार अथवा डिफाल्टर घोषित नहीं किया जाना चाहिए इस संबंध में 100 रूपये के नॉन–ज्यूडिशियल स्टाम्प पैपर पर नोटरी से प्रमाणित शपथ पत्र निविदा में तकनिकी बिड प्रपत्र के साथ सलंग्न किया जाना आवश्यक हैं। **(शपथ पत्र में निविदा संख्या एवं कार्य का नाम अंकित करना होगा)**

8. फर्म का नाम एवं पता मय टेलीफोन नम्बर फर्म की स्थिति एकाकी/पार्टनरशिप/प्रा. लि./आदि का विवरण सलंग्न करना होगा।

9. संवेदक/फर्म को निविदा में तकनिकी बिड प्रपत्र के साथ फर्म का पैन कार्ड नम्बर की छायाप्रति सलंग्न करनी होगी।

10. संवेदक/फर्म को जी.एस.टी. विभाग पंजीकृत होना आवश्यक है एवं विभाग द्वारा जारी जी.एस.टी. सर्टिफिकेट की प्रति निविदा में तकनिकी बिड प्रपत्र के साथ संलग्न करनी होगी।

11. संवेदक/फर्म को जी.एस.टी. विभाग में नवीनतम जी.एस.टी. आयकर रिर्टन प्रमाण पत्र की छाया प्रति निविदा में तकनिकी बिड प्रपत्र के साथ संलग्न करनी होगी।

12. संवेदक को निविदा के तकनिकी बिड प्रपत्र में मांगे गये दस्तावेजों की पूर्ती कर लगाया जाना आवश्यक होगा। यदि मांगे गये दस्तावेजों की पूर्ती नहीं किये जाने पर उस फर्म को उस निविदा के लिये असफल माना जावेगा।

13. स्वीकृत निविदादाता को निविदा की शर्तो की पूर्ण पालना करनी होगी। शर्तो की अवहेलना गुणवत्तापूर्वक कार्य नहीं करने पर तथा विलम्ब पर नियमानुसार कार्यवाही कर नुकसान को वसूलने का नगर निगम कोटा को पूर्ण अधिकार होगा। ऐसे मामलों में फर्म के दोषी पाये जाने पर स्वीकृति निरस्त कर पुनःनिविदा आमंत्रित की जा सकेगी। नई फर्म को निविदा द्वारा कार्यादेश दिये जाने तक नगर निगम कोटा ठेकेदार की रिस्क व कोस्ट के आधार पर किसी अन्य निविदा में भाग लेने वाली फर्म से कार्य कराया जा सकेगा,जिसकी कटौती ठेकेदार से की जावेगी।

14. किसी भी निविदा को बिना कारण बताये अस्वीकृत करने का पूर्ण अधिकार नगर निगम कोटा को होगा।

15. निविदादाता द्वारा दी जाने वाली दरें सभी कर सहित अंकित करनी होगी/BoQ में भरनी होगी।

16. फर्म के बिलो से नियमानुसार आयकर की कटौती भुगतान करते समय की जायेगी।

17. कार्य की आवश्यकता को देखते हुए दूरभाष पर भी आदेश दिये जा सकेंगे जो ठेकेदार/संवेदक को मान्य होगें।

18. सिविल विवाद की स्थिति में स्थानीय न्यायालय कोटा का ही क्षेत्राधिकार होगा।

19. राज्य सरकार व नगर निगम कोटा द्वारा समय समय पर जारी आदेश निर्देश मान्य होगें।

20. संतोषजनक कार्य नहीं होने की स्थिति में अनुबंध को किसी भी समय निरस्त किया जा सकता है तथा प्रतिभूति राशि जब्त कर ली जायेगी।

21. यदि किसी निविदा दाता द्वारा टेन्डर की राशि से कम दर भरी जाती है तो सफल निविदा दाता को निदेशालय आदेश क्रमांक प.6 (च) (431) (ई.17052) स्वी/लेखा/डिएलबी/नागौर/2020/958 दिनांक 22.10.2024 अनुसार अन्तर राशि (Additional Performance Security) 14 दिवस में BG/FDR/NSC के रूप में नगर निगम कोटा में जमा कराए जाने पर कार्यादेश जारी किया जावेगा। कार्य सन्तोषप्रद पूर्ण होने के पश्चात् वापस लौटा दी जावेगी। आदेश संलग्न है।

22. निविदादाता दरों की वैधता अवधि खोले जाने की दिनांक से 90 दिवस तक अनुमोदन हेतु मान्य होगी। तदुपरान्त नियमानुसार कार्यवाही की जावेगी।

23. न्यूनतम मजदूरी एक्ट एवं श्रम कानूनों की पालना किया जाना अनिवार्य होगा।

24. ई.पी.एफ. एवं ई.एस.आई. विभाग में पंजीकृत संवेदक को ई.पी.एफ. एवं ई.एस.आई. रजिस्ट्रेशन की प्रति तकनिकी बिड के साथ अपलोड करना होगा।

25. संवेदक को राशि 100/- के नॉन–ज्यूडिशियल स्टाम्प पैपर पर नोटरी से प्रमाणित इस आशय का शपथ पत्र प्रस्तुत करना होगा कि "ई.पी.एफ. एवं ई.एस.आई. से श्रमिको के भुगतान की ओडिट कराने एवं ई.पी.एफ. एवं ई.एस.आई.के समस्त प्रकार के दायित्त्वों का निवर्हन एवं नियोजित श्रमिको का ई.पी.एफ. एवं ई.एस.आई. विभाग में जमा कराने का उत्तरदायित्व स्वयं संवेदक का होगा तथा भविष्य में पी.एफ. और ई.एस.आई. विभाग के किसी प्रकार के दायित्व सृजित होते है, तो उसकी समस्त जिम्मेदारी संवेदक की होगी" का शपथ पत्र तकनिकी बिड के साथ अपलोड करना होगा तथा कार्यालय द्वारा मांगे जाने पर मूल शपथ पत्र उपलब्ध कराना होगा। **(शपथ पत्र में निविदा संख्या एवं कार्य का नाम अंकित करना होगा)**

26. तकनीकी प्रपत्र 24 घण्टे अपलोड होने के पश्चात् कोई आपत्ति प्राप्त होती है तो आपत्ति स्वीकार नहीं की जावेगी।

27. सशर्त निविदा मान्य नहीं होगी।

28. संवेदक कार्य प्रारम्भ करने से पूर्व एवं कार्य समाप्ति कार्य स्थल के फोटोग्राफ प्रस्तुत करने होगें एवं कार्य स्थल पर सूचना बोर्ड स्वयं के खर्चे पर लगाना होगा। कार्य प्रारम्भ करने से पूर्व संबंधित सहायक अभियन्ता/कनिष्ठ अभियन्ता सम्बन्धित वार्ड पार्षद/जन प्रतिनिधि को सूचित करेंगे एवं उनके सामने गुणवत्ता रिपोर्ट हेतु सेम्पल लिया जाना सुनिश्चित करेगें।

29. कार्य की दोष निवारण अवधि कार्य पूर्ण होने के उपरान्त एक वर्ष की होगी।

30. उक्त शर्त संख्या 30 की पालना नही करने पर सम्बन्धित संवेदक/फर्म पर ब्लैक लिस्टेड करने/डिबार करने की कार्यवाही अमल में लाई जावेगी।

31. निविदादाता विफल रहा है के मूल्य की निम्नानुसार प्रतिशत के आधार पर वसूली की जावेगी।

• विहित परिदान कालावधि की एक चौथाई कालावधि तक विलम्ब	2.50 प्रतिशत
• विहित कालावधि से एक चौथाई से अधिक किन्तु आधी से अनाधिक कालावधि तक विलम्ब	5.00 प्रतिशत
• विहित कालावधि के आधे से किन्तु तीन चौथाई तक की कालावधि का विलम्ब	7.50 प्रतिशत
• विहित कालावधि के तीन चौथाई से अधिक की कालावधि का विलम्ब	10.00 प्रतिशत
• निर्धारित नुकसान की अधिकतम रकम	10.00 प्रतिशत

32. कार्य प्रारम्भ से पूर्व संवेदक द्वारा कार्य स्थल पर स्वयं के खर्चे पर आवश्यकतानुसार कार्य की सूचना के बोर्ड लगाने अनिवार्य होगें।

33. संवेदको को निविदा की शर्तो एवं तकनिकी बिड प्रपत्र में मांगे गये दस्तावेज तकनिकी बिड के साथ संलग्न कर अपलोड करना होगा, अनावश्यक दस्तावेज संलग्न करने पर नियमानुसार कार्यवाही की जावेगी।

नोटः– तकनीकी बिड खोलने की तिथी पर किसी भी कारण वश अवकाश होने पर आगामी कार्य दिवस पर प्राप्त व खोली जावेगी।

मेरे द्वारा उपरोक्त दरो पर निविदा शर्तो के अनुसार कार्य करने हेतु उपरोक्तानुसार दर समस्त कर जी.एस.टी. सहित शामिल कर प्रस्तुत की गई है।

मैने तकनिकी बिड़ एवं सलग्ंन शर्तो का अध्ययन कर लिया है, एवं सलंग्न शर्तो एवं अनुबंध की पालना करने के लिये बाध्य है।

टेण्डर की शर्तो की भली भांति अध्ययन कर लिया है एवं उक्त शर्तो से में पूर्णतया सहमत हूँ।

I / We hereby agree to execute the work :

At the Rate _____ % Above/Below (in words)

At the Rate _____ % Above/Below (in Figures)

(हस्ताक्षर संवेदक मय सील)

–प्रारूप–

(फर्म का लेटरहेड)

सहमति–पत्र

श्रीमान अधिशाषी अभियन्ता,
नगर निगम कोटा।

विषय : अपनी निविदा हेतु सहमति के संबंध में।
प्रसंग : निविदा क्रमांक.....

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :–

(1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर है।
(2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
(3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
(4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
(5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।
(6) मैने तकनिकी बिड़ एवं सलग्न शर्तो का अध्ययन कर लिया है, एवं सलंग्न शर्तो एवं अनुबंध की पालना करने के लिये बाध्य है।
(7) मैने निविदा की शर्तो की भली भांति अध्ययन कर लिया है एवं उक्त शर्तो से में पूर्णतया सहमत हूँ।

दिनांक : ..... **(हस्ताक्षर संवेदक मय सील)**

राजस्थान सरकार
निदेशालय, स्थानीय निकाय, राज0 जयपुर
स्वायत्त शासन भवन जी-3, राजमहल रेजीडेन्सी, सिविल लाईन फाटक, जयपुर
E-mail : cmodlb@gmail.com Phone 0141 - 2223074

क्रमांक : प.6(च)(431)(E-17052)स्वी / लेखा / डीएलबी / नागौर / 2020 / 958 दिनांक 22/10/24

आयुक्त / अधिशाषी अधिकारी,
नगर निगम / परिषद / पालिकायें,
समस्त राजस्थान।

विषय : अतिरिक्त कार्य सम्पादन प्रतिभूति के सम्बन्ध में।

उपर्युक्त विषयान्तर्गत लेख है कि नगरीय निकायों द्वारा आमन्त्रित निविदाओं मे संवेदकों द्वारा प्राकलित बोली मूल्य से कम बोली के सम्बन्ध में निदेशालय में शिकायते प्राप्त हो रही है। प्राकलित बोली मूल्य से कम बोली प्राप्त होने पर कार्यो की गुणवत्ता भी प्रभावित होने की सम्भावनायें रहती है।

अतः निकायों द्वारा आमन्त्रित निविदाओं में प्राकलित बोली मूल्य से कम बोली प्राप्त होने की स्थिति में लेख है कि :-

- राजस्थान लोक उपापन मे पारदर्शिता नियम 2013 के नियम 75क में कार्यसम्पादन प्रतिभूति के अतिरिक्त, असन्तुलित बोली के मामलों में सफल बोलीदाता से अतिरिक्त कार्य सम्पादन प्रतिभूति लिये जाने का प्रावधान किया गया है।
- उक्त अतिरिक्त कार्य सम्पादन प्रतिभूति प्राकलित बोली मूल्य की 15प्रतिशत से कम बोली (Bid below more than 15% of Estimated Bid Value.)के मामलो में ली जावेगी।
- अतिरिक्त कार्य सम्पादन प्रतिभूति असन्तुलित बोली रकम के पचास प्रतिशत (Equal to fifty percent of Unblanced Bid Amount)के बराबर होगी
- अतिरिक्त कार्य सम्पादन प्रतिभूति करार के निष्पादन से पूर्व एकमुश्त जमा की जायेगी।
- प्राकलित बोली मूल्य के 85 प्रतिशत में से प्राप्त बोली रकम घटाने पर प्राप्त राशि असन्तुलित बोली है। (Unblance Bid amount means positive difference of eighty five percent of Estimated Bid Value minus Bid Amount Quoted by the bidder)

Signature valid
Digitally signed by Kumar Pal Gautam
Designation : Director
Date: 2024.10.22 11:08:15 IST
Reason: Approved

Vashistha

उदाहरण

उपापन संस्था द्वारा प्राकलित बोली मूल्य = 100

संवेदक द्वारा प्रस्तुत बोली मूल्य = 65

असन्तुलित बोली की रकम की गणना :–

प्राकलित बोली 100 का 85 प्रतिशत – प्राप्त बोली = असन्तुलित बोली

100 x 85 ÷100 =85 - 65 = 20

अतिरिक्त कार्य सम्पादन प्रतिभूति की राशि = असन्तुलित बोली रकम का पचास प्रतिशत

20 x 50 ÷100 = 10

अतः समस्त आयुक्त/अधिशाषी अधिकारियों को निर्देशित किया जाता है कि अतिरिक्त कार्य सम्पादन प्रतिभूति के समस्त प्रकरणो में राजस्थान लोक उपापन में पारदर्शिता नियम 2013 के नियम 75क की पालना सुनिश्चित की जावे।

(कुमार पाल गौतम)
निदेशक एवम् विशिष्ट सचिव

क्रमांक : प.6(च)(431)(E-17052)स्वी/लेखा/डीएलबी/नागौर/2020/958-62 दिनांक 22/10/2

प्रतिलिपि सूचनार्थ एवम् आवश्यक कार्यवाही हेतु :–

01. विशिष्ट सहायक, माननीय मंत्री महोदय, स्वायत्त शासन विभाग, राज0 जयपुर।
02. निजी सचिव, प्रमुख शासन सचिव, स्वायत्त शासन विभाग, राज0 जयपुर।
03. समस्त उप निदेशक (क्षेत्रीय), स्थानीय निकाय विभाग, राजस्थान।
04. सुरक्षित पत्रावली।

(कुमार पाल गौतम)
निदेशक व विशिष्ट सचिव

Signature valid
Digitally signed by Kumar Pal Gautam
Designation : Director
Date: 2024.10.22 11:08:15 IST
Reason: Approved

Vashistha