

# MUNICIPAL CORPORATION KOTA (NORTH) RAJASTHAN

(NIT NO. 19..../2024-25) ('G' Schedule) (Copy No. 01)

Name of work:- वार्ड नं० 31 में नाली सी.सी. एवं मरम्मत कार्य।

Estimated Cost :- 99.96 Lacs

Tender Cost:- Rs. 3500/-

Processing Fees :- Rs. 1500/-

Date & time of downloading of Bid

Date & time of online submission of Bid

Date, time and opening of Technical Bid -

Date and Time Opening of Financial Bid

Earnest Money: 49980/- (0.50%)

199920/- (2%) 06 Months

04-02-2025... to 13-02-2025

04-02-2025... to 13-02-2025

14-02-2025 upto 4:00PM

तकनीकी बिड परीक्षण के पश्चात्

Issued

To:

C.R. No.

Date :-

(Rates Based on RUIDP SOR (2023))

S.No	Particulars	Qty.	unit	Rate	Amount
1	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Cement Concrete Grade M-15 and above and PCC blocks	189.98	Cum	678.00	128806.44
2	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m	867.90	Cum	229.50	199183.05
3	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth	846.30	Cum	254.76	215603.39
4	Providing, laying and spreading of granular sub-base by providing coarse graded Material (Table 400-2), spreading in uniform layers with motor grader on prepared surface, mixing BY MIX IN PLACE METHOD with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per MoRT&H specification clause - 401 including all material, labour, machinery, lighting, guarding and maintenance of diversion. Grading - III Material	345.83	Cum	1106.00	382487.98

  
सहायक अभियन्ता  
नगर निगम कोटा उत्तर




5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	336.44	Cum	4575.00	1539213.00
6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	426.30	Cum	5910.00	2519433.00
7	Providing and fixing of precast concrete interlocking tiles of desired shape of M 30 grade manufactured from fully computerized automatic stationery hydraulic vibrio pressed machine and fully computerized automatic batching plant of class A1/A2 as per BS 6717:2001. The CC interlocking paving blocks be laid on average 50mm. thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer in-charge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications. Tensile splitting strength, abrasion and braking load etc. as per BS 6717:2001, Grey cement.80mm thick	2193.00	Sqm	792.00	1736856.00
8	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	5120.00	Kg	144.50	739840.00
9	40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement : 5 coarse sand) with joints finished flush. Red sand stone	1613.25	Sqm	783.00	1263174.75
10	Providing and fixing of reinforced Ferro-Cement drain covers designed for 'AA' class loading duly marked on cover with adequate steel reinforcement having thickness 75mm to 150mm anti corrosive bitumen painted M.S. plate , Rim and M.S. lifting hooks, Admixtures like plasticizer, bond improving compound, shrinkage, resistance compound, abrasion resistant complete as per approved design etc. Standard Size 600x800mm (75mm thick) for span 300 to 450mm	390.00	Sqm	1486.00	579540.00
11	Random rubble dry stone Kharanja (soling) under floor.	3.38	Cum	2270.00	7672.60
12	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	11.88	Cum	6340.00	75319.20
13	Reinforcement for R.C.C. work at all levels including straightening, cutting, bending, placing in position and binding all complete. Cold twisted bars	1500.00	Kg	83.30	124950.00



14	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including priming coat with cement primer.	490.00	Sqm	136.50	66885.00
15	Lettering with black Japan paint of approved brand and manufacture	12000.00	Per Letter per cm height	4.45	53400.00
16	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	9.72	Cum	4860.00	47239.20
17	Brick work with FPS bricks of class designation 75 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	24.84	Cum	6300.00	156492.00
18	Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : including Providing /mixing of synthetic fibers compulsorily complying with IS 16481:2022 of 06 mm/12 mm length to be mixed @ 0.25% by weight of Cement i.e. 125 gms per 50 kg Cement up to 900 gms per cum of Concrete/ mortar 1:6 (1 cement : 6 fine/ coarse sand)	195.00	Sqm	294.50	57427.50
19	Centring and shuttering with plywood or steel sheet upto two stories ( each story of height upto 3.5 metre from floor level) including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	432.00	Sqm	236.50	102168.00
<b>Grand Total</b>					<b>9995691.11</b>

**Terms & Conditions:-**

- 1 निविदाओं में भाग लेने वाले संवेदकों/फर्मों द्वारा जमा की जाने वाली निविदा शुल्क, प्रोसेसिंग फीस, धरोहर राशि आयुक्त नगर निगम कोटा-उत्तर की वेबसाइट [www.kotamc.org](http://www.kotamc.org), पर जाकर ऑनलाईन जमा करवानी होगी। जिसकी रसीद ऑनलाईन तकनीकी बिड में संवेदक द्वारा अपलोड करनी होगी। इसके अभाव में संवेदक को असफल कर दिया जायेगा। असफल संवेदक की सिर्फ धरोहर राशि लोटाई जावेगी। निविदा शुल्क एवं प्रोसेसिंग फीस ( **Non-Refundable**) वापस नहीं की जावेगी।
- 2 कार्य के विलम्ब की स्थिति में गुणावगुण के आधार पर अनुबन्ध में निहित अधिकतम दर तक शास्ती लगायी जा सकेगी।
- 3 अनुबन्ध करने में असमर्थ रहने अथवा कार्य करने में असमर्थ रहने पर अनुबन्ध की रारत सं0 2 व 3 के अन्तर्गत आपकी रिस्क एण्ड कास्ट पर नगर निगम को कार्य करने का/जमा योग्य अर्नेस्ट मनी की शास्ती लगाने की कार्यवाही करने का निगम को अधिकार सुरक्षित रहेगा बिड सिक्यूरिटी घोषणा पत्र के अनुसार कार्यवाही कर सकेगा।
- 4 कार्य प्रारम्भ करने से पूर्व एवं कार्य समाप्ति कार्य स्थल के फोटोग्राफ प्रस्तुत करने होंगे एवं कार्य स्थल पर सूचना बोर्ड स्वयं के खर्च पर लगाना होगा।
- 5 कार्य प्रारम्भ करने से पूर्व संबंधित सहा.अभि./कनि.अभि. संबंधित वार्ड पार्षद/जन प्रतिनिधि को सूचित करेंगे एवं उनके सामने गुणवत्ता रिपोर्ट हेतु सैम्पल लिया जाना सुनिश्चित करेंगे।
- 6 न्यूनतम मजदूरी एक्ट एवं श्रम कानूनों की पालना किया जाना अनिवार्य होगा।
- 7 कर्मचारी भविष्य निधि योजना (EPFO) के अन्तर्गत EPF & ESI पंजीयन की प्रति संलग्न करनी होगी एवं EPF & ESI के समस्त प्रकार के दायित्वों का निर्वहन संवेदक का होगा के संबंध में 100/-रु0 के स्टाम्प पर शपथ पत्र प्रस्तुत करना होगा।

  
**सहायक अभियन्ता**  
**नगर निगम कोटा उत्तर**



-प्रारूप-  
(लेटरहेड)

सहमति-पत्र

श्रीमान .....

नगर निगम कोटा उत्तर।

विषय : अपनी निविदा हेतु सहमति के संबंध में।

प्रसंग : निविदा क्रमांक.....

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- (1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर हैं।
- (2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- (3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- (4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- (5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक :



# कार्यालय नगर निगम, कोटा-उत्तर (राज0)


## तकनीकी बिड दस्तावेज चैक लिस्ट

कार्य का नाम:- नगर निगम कोटा-उत्तर के वार्ड नं0 31 में नाली, सी.सी. एवं मरम्मत कार्य।  
(कार्य संख्या-01)

क्र. सं.	तकनीकी बिड के साथ निम्न दस्तावेज जो संलग्न करने है।	दस्तावेजो का विवरण	संलग्न पेज
1	निविदाओं में भाग लेने वाले संवेदकों/फर्मों द्वारा जमा की जाने वाली निविदा शुल्क, प्रोसेगिंग फीस, धरोहर राशि आयुक्त नगर निगम कोटा-उत्तर की वेबसाइट <a href="http://www.kotamc.org">www.kotamc.org</a> , पर जाकर ऑनलाईन जमा करवानी होगी। जिसकी रसीद ऑनलाईन तकनीकी बिड में संवेदक द्वारा अपलोड करनी होगी की प्रति।		
2	कर्मचारी भविष्य निधि योजना (EPFO) के अन्तर्गत EPF & ESI पंजीयन की प्रति संलग्न करनी होगी		
3	EPF & ESI के समस्त प्रकार के दायित्वों का निवर्हन संवेदक का होगा के संबंध में 100/-रु के स्टाम्प पर शपथ पत्र प्रस्तुत करना होगा।		
4	संवेदक को किसी भी राजकीय संस्था विभाग, बोर्ड, कॉर्पोरेशन अथवा उपक्रम में गत 03 वर्षों में ब्लैक लिस्टेड/डिबार अथवा डिफाल्टर घोषित नहीं किया होना चाहिए इस संबंध में स्वप्रमाणित अपने लेटरपेड पर निविदा के साथ संलग्न किया जाना आवश्यक है।		
5	फर्म नगर निगम कोटा एवं अन्य विभाग में पंजीयन की प्रति संलग्न करनी होगी।		
6	फर्म की जीएसटी विभाग में पंजीयन की प्रति।		
7	फर्म का पेनकार्ड नं0 की छायाप्रति संलग्न करनी होगी।		
8	भविष्य में EPF&ESI से श्रमिकों के भुगतान की ओडिट कराने का 50रु के स्टाम्प पर शपथ पत्र संलग्न करेंगे।		
9	जी शिड्यूल की संवेदक द्वारा अपलोड की प्रति		
10	निविदा में संलग्न सहमति पत्र प्रारूप के अनुरूप		

नोट :- उपरोक्त सभी प्रमाण पत्र स्व प्रमाणित होने चाहिये एवं उक्त दी गई सूचनाएँ मेरी जानकारी एवं विश्वास के अनुसार सही है तथा हमारी फर्म निविदा की समस्त शर्तों एवं नियमों की पालना करने के लिये सहमत है।

हस्ताक्षर निविदादाता

  
अधिशायी अभियन्ता  
नगर निगम, कोटा-उत्तर