

MUNICIPAL CORPORATION KOTA (NORTH) RAJASTHAN

(NIT NO. 20.../2024-25) ('G' Schedule) (Copy No. 06)

Name of work:- नगर निगम कोटा उत्तर के सुभाष सर्किल पर डिवाडर मरम्मत कार्य।

Estimated Cost :- 10.25 Lacs

Tender Cost:- Rs. 1500/-

Processing Fees :- Rs. 500/-

Date & time of downloading of Bid

Date & time of online submission of Bid

Date, time and opening of Technical Bid -

Date and Time Opening of Financial Bid

Earnest Money: 5125/- (0.50%)

20500/- (2%) 02 Months

20..02..25.. to 03..03..25

20..02..25.. to 03..03..25

04..03..25... upto 4:00PM

तकनिकी बिड परीक्षण के पश्चात्

Issued

To:

C.R. No.

Date :-

(Rates Based on RUIDP SOR (2023))

S.No	Particulars	Qty.	unit	Rate	Amount
1	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Cement Concrete Grade M-15 and above and PCC blocks	10.35	Cum	678.00	7017.30
2	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Rubble stone masonry in cement mortar.	7.09	Cum	386.00	2735.78
3	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m	31.05	Cum	229.50	7125.98
4	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth	40.00	Cum	254.76	10190.40
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	5.18	Cum	4575.00	23675.63

सहायक अभियन्ता
नगर निगम कोटा उत्तर

6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	3.74	Cum	5910.00	22073.85
7	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	51.75	Cum	4860.00	251505.00
8	Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement : 6 fine/ coarse sand)	138.00	Sqm	247.00	34086.00
9	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1000.00	Kg	144.50	144500.00
10	Providing and laying damp-proof course with cement concrete grade M-15 (1 : 2 : 4) mortar prepared with 1% solution of water-proof compound complete as per specification . 50mm thick.	34.50	Sqm	445.00	15352.50
11	Supplying and stacking good earth at site of work. Note: 1) Loading, unloading and carriage to be paid extra as per actual lead. 2) Earth measured in stacks will be reduced by 20% for payment	100.00	Cum	324.50	32450.00
12	Grassing with 'Doobs' grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for moving including supplying good earth if needed. (The good earth shall be paid separately) In rows 15 cm apart in either direction	100.00	Sqm	37.30	3730.00
13	Supplying and fixing machine cut dressed 75 mm Pink sand stone (Bansi Paharpur) dasa/ coping with ornamental shape having moulding and "PAN Shape" engraving as per required pattern with engraving depth of 5 mm (average) in single piece of length 90 cm to be laid on cement mortar 1:4 (12 to 20mm thick) including pointing with admixture of pigment matching with the stone shade.	62.25	Sqm	5308.60	330460.35
14	Supply of different sized pots at site store including loading unloading & transportation etc. complete. Cement pot / Plastic pot 525 mm size	15.00	Each	936.00	14040.00
15	Supply and planting following in poly bags / earthen pots well branched, well established & free from disease of 600 mm min. height shrubs at site in 0.45 m dia holes, 0.45 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, backfilling the hole watering etc as required. Rhapsis excelsa with 3-4 suckers (Lady Palm)	30.00	Each	1251.00	37530.00
16	Agave with 10-12 leaves (Kamal Cactus)	5.00	Each	1675.00	8375.00
H-Schedule					
1	Flood Light Green	5.00	Each		40000.00
2	Flood Light Warm White	5.00	Each		40000.00



 निम्नलिखित

MUNICIPAL CORPORATION
 (M.T. No. 2024-25) (C)

Terms & Conditions:-

- 1 निविदाओं में भाग लेने वाले संवेदकों/फर्मों द्वारा जमा की जाने वाली निविदा शुल्क, प्रोसेसिंग फीस, धरोहर राशि आयुक्त नगर निगम कोटा-उत्तर की वेबसाइट www.kotamc.org, पर जाकर ऑनलाईन जमा करवानी होगी। जिसकी रसीद ऑनलाईन तकनीकी बिड में संवेदक द्वारा अपलोड करनी होगी। इसके अभाव में संवेदक को असफल कर दिया जायेगा। असफल संवेदक की सिर्फ धरोहर राशि लौटाई जावेगी। निविदा शुल्क एवं प्रोसेसिंग फीस (**Non-Refundable**) वापस नहीं की जावेगी।
- 2 कार्य के विलम्ब की स्थिति में गुणावगुण के आधार पर अनुबन्ध में निहित अधिकतम दर तक शास्ती लगायी जा सकेगी।
- 3 अनुबन्ध करने में असमर्थ रहने अथवा कार्य करने में असमर्थ रहने पर अनुबन्ध की शर्त सं0 2 व 3 के अन्तर्गत आपकी रिस्क एण्ड कास्ट पर नगर निगम को कार्य करने का/जमा योग्य अर्नेस्ट मनी की शास्ती लगाने की कार्यवाही करने का निगम को अधिकार सुरक्षित रहेगा बिड सिक्यूरिटी घोषणा पत्र के अनुसार कार्यवाही कर सकेगा।
- 4 कार्य प्रारम्भ करने से पूर्व एवं कार्य समाप्ति कार्य स्थल के फोटोग्राफ प्रस्तुत करने होंगे एवं कार्य स्थल पर सूचना बोर्ड स्वयं के खर्च पर लगाना होगा।
- 5 कार्य प्रारम्भ करने से पूर्व संबंधित सहा.अभि./कनि.अभि. संबंधित वार्ड पार्षद/जन प्रतिनिधि को सूचित करेंगे एवं उनके सामने गुणवत्ता रिपोर्ट हेतु सैम्पल लिया जाना सुनिश्चित करेंगे।
- 6 न्यूनतम मजदूरी एक्ट एवं श्रम कानूनों की पालना किया जाना अनिवार्य होगा।
- 7 कर्मचारी भविष्य निधि योजना (EPFO) के अन्तर्गत EPF & ESI पंजीयन की प्रति संलग्न करनी होगी एवं EPF & ESI के समस्त प्रकार के दायित्वों का निर्वहन संवेदक का होगा के संबंध में 100/-रु0 के स्टाम्प पर शपथ पत्र प्रस्तुत करना होगा।
- 8 कार्य संपादन प्रतिभूति/सुरक्षा निधि की वापसी अनुबंध की शर्त संख्या 37 के अनुसार होगी।
- 9 संवेदक द्वारा निष्पादित किये जाने वाले अनुबंध में संवेदक यह तथ्य भी स्पष्ट रूप से उल्लेख करेगा की PF & ESI विभाग के किसी प्रकार के दायित्व सृजित होते हैं तो उसकी समस्त जिम्मेदारी संवेदक की होगी।
- 10 वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर. टी. पी. पी. नियम 2013 **Additional Performance Security** के लिए नियम 75 । जोडा गया है। जिसके तहत कार्य आदेश जारी से पूर्व नियमानुसार राशि जमा करवानी होगी।
- 11 सुरक्षा निधि (**Performance Guarantee**) नियमानुसार प्रत्येक रनिंग बिल व अंतिम बिल से 10 प्रतिशत राशि काटी जावेगी तथा अनुबन्ध की शर्त संख्या 37 के अनुसार लौटाई जावेगी।

Signature of Contractor


 Executive Engineer
 Nagar Nigam, Kota-North

कार्यालय नगर निगम, कोटा-उत्तर (राज0)


तकनीकी बिड दस्तावेज चैक लिस्ट

कार्य का नाम:- नगर निगम कोटा-उत्तर के सुभाष सर्किल पर डिवाइडर मरम्मत कार्य।
(कार्य संख्या-06)

क्र. सं.	तकनीकी बिड के साथ निम्न दस्तावेज जो संलग्न करने है।	दस्तावेजो का विवरण	संलग्न पेज
1	निविदाओं में भाग लेने वाले संवेदकों/फर्मों द्वारा जमा की जाने वाली निविदा शुल्क, प्रोसेगिंग फीस, धरोहर राशि आयुक्त नगर निगम कोटा-उत्तर की वेबसाइट www.kotamc.org , पर जाकर ऑनलाईन जमा करवानी होगी। जिसकी रसीद ऑनलाईन तकनीकी बिड में संवेदक द्वारा अपलोड करनी होगी की प्रति।		
2	कर्मचारी भविष्य निधि योजना (EPFO) के अन्तर्गत EPF & ESI पंजीयन की प्रति संलग्न करनी होगी		
3	EPF & ESI के समस्त प्रकार के दायित्वों का निवर्हन संवेदक का होगा के संबंध में 100/-रु0 के स्टाम्प पर शपथ पत्र प्रस्तुत करना होगा।		
4	संवेदक को किसी भी राजकीय संस्था विभाग, बोर्ड, कॉर्पोरेशन अथवा उपक्रम में गत 03 वर्षों में ब्लैक लिस्टेड/डिबार अथवा डिफाल्टर घोषित नहीं किया होना चाहिए इस संबंध में स्वप्रमाणित अपने लेटरपेड पर निविदा के साथ संलग्न किया जाना आवश्यक है।		
5	फर्म नगर निगम कोटा एवं अन्य विभाग में पंजीयन की प्रति संलग्न करनी होगी।		
6	फर्म की जीएसटी विभाग में पंजीयन की प्रति।		
7	फर्म का पेनकार्ड नं0 की छायाप्रति संलग्न करनी होगी।		
8	भविष्य में EPF&ESI से श्रमिकों के भुगतान की ओडिट कराने का 50रु के स्टाम्प पर शपथ पत्र संलग्न करेंगे।		
9	शिड्यूल की संवेदक द्वारा अपलोड की प्रति		
10	निविदा में संलग्न सहमति पत्र प्रारूप के अनुरूप		

नोट :- उपरोक्त सभी प्रमाण पत्र स्व प्रमाणित होने चाहिये एवं उक्त दी गई सूचनाएँ मेरी जानकारी एवं विश्वास के अनुसार सही है तथा हमारी फर्म निविदा की समस्त शर्तों एवं नियमों की पालना करने के लिये सहमत है।

हस्ताक्षर निविदादाता


अधिशार्पी अभियन्ता
नगर निगम, कोटा-उत्तर

(लेटरहेड)

सहमति-पत्र

श्रीमान

नगर निगम कोटा उत्तर।

विषय : अपनी निविदा हेतु सहमति के संबंध में।

प्रसंग : निविदा क्रमांक.....

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- (1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर है।
- (2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- (3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- (4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- (5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक :

Signature

Signature