

MUNICIPAL CORPORATION KOTA (NORTH) RAJASTHAN

(NIT NO. 20.../2024-25) ('G' Schedule) (Copy No. 08) 07)

Name of work:- नगर निगम कोटा-उत्तर क्षेत्र के रामपुरा बाजार में पीपल के पेड़ के पास
Beautification and Fountain का कार्य।

Estimated Cost :- 07.40 Lacs

Tender Cost:- Rs. 1000/-

Processing Fees :- Rs. 500/-

Date & time of downloading of Bid

Date & time of online submission of Bid

Date, time and opening of Technical Bid -

Date and Time Opening of Financial Bid

Earnest Money: 3700/- (0.50%)

14800/- (2%) 02 Months

20-02-25 to 03-03-25

20-02-25 to 03-03-25

04-03-25 upto 4:00PM

तकनिकी बिड परीक्षण के पश्चात्

Issued

To:

C.R. No.

Date :-

(Rates Based on RUIDP SOR (2023))

S.No	Particulars	Qty.	unit	Rate	Amount
	Part-G-Schedule				
1	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Cement Concrete Grade M-15 and above and PCC blocks	10.22	Cum	678.00	6929.16
2	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth upto 10 km	10.22	Cum	356.20	3640.36
3	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:6 (1 cement : 6 fine/ coarse sand)	20.28	Sqm	294.50	5972.46
4	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	12.46	Cum	4860.00	60555.60
5	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.60	Cum	6341.00	3804.60
6	Reinforcement for R.C.C. work at all levels including straightening, cutting, bending, placing in position and binding all complete. Cold twisted bars	800.00	Kg	83.30	66640.00

Koy
कनिष्ठ अभियन्ता
नगर निगम कोटा उत्तर

7	Providing and fixing 1st quality standard white, grey, ivory, fume red brown, light green, light blue and other light shades glazed tiles confirming to IS : 13753 & IS :15622 of size 200mm x 300mm in walls, floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (excluding the cost of cement plaster on walls and pillar).	19.76	Sqm	891.00	17606.16
8	Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : including Providing /mixing of synthetic fibers compulsorily complying with IS 16481:2022 of 06 mm/12 mm length to be mixed @ 0.25% by weight of Cement i.e. 125 gms per 50 kg Cement up to 900 gms per cum of Concrete/ mortar 1:6 (1 cement : 6 fine/ coarse sand)	17.26	Sqm	294.50	5083.07
9	Supplying and fixing machine cut dressed 75 mm Pink sand stone (Bansi Paharpur) dasa/ coping with ornamental shape having moulding and "PAN Shape" engraving as per required pattern with engraving depth of 5 mm (average) in single piece of length 90 cm to be laid on cement mortar 1:4 (12 to 20mm thick) including pointing with admixture of pigment matching with the stone shade.	37.57	Sqm	5308.60	199444.10
Part-B H-Schedule Foam Jets					
1	Foam Jet -Family Fountains	4.00	Each		18000.00
2	Ball Joint Set of GM -Family Fountains	4.00	Each		3800.00
3	IP 68 Waterproof colour changing type 9x3w 27 watt Hi power LED type lights Of Aluminium body with SS top with each nozzle of 24V. Make-Family Fountains	4.00	Each		22000.00
4	1" Gate Valve	4.00	Each		2200.00
5	LED Light controller for above lights	1.00	Each		4500.00
6	Power Supply box for the required capacity 24 V for LED Light . Complete in all respect	1.00	Each		2500.00
7	Mono Submersible pump of 2 HP Three phase having inlet and outlet size respectively - Make Kirloskar/Crompton	1.00	Each		26500.00
8	3" Filter for above pump	1.00	Each		3000.00
9	Control Panel made of 16 gauge CRC sheet powder coated with Dol Starter, MCB, contactor, Overload Relay indicating light etc. Make - Family Fountains	2.00	Each		29000.00
10	Complete plumbing required for the fountain in PVC pipe & bending as per drawing including necessary control valves etc (excluding inlet and drain)	1.00	Each		10500.00
11	Complete electrical work required for the fountain including pump, transformer and light (within 10M. From water body)	1.00	Each		8500.00
12	Installing, testing, commissioning	1.00	Each		10000.00
Part-C H-Schedule Flood Light and Tube well pump					
1	Flood Light Green	2.00	Each		16000.00
2	Flood Light Warm White	2.00	Each		16000.00

Kaj


3	Wall Washer Light	16.00	Each	96000.00
4	Submersible pump of 7.5 HP Three phase having inlet and outlet size respectively - Make Kirloskar/Crompton	1.00	Each	45500.00
5	63 MM HDPE Pipe PE 80 PN 6	50.00	Mtr	13600.00
6	22 MM PP Rope	80.00	Mtr	4800.00
7	Control Panel made of 16 gauge CRC sheet powder coated with Dol Starter, MCB, contactor, Overload Relay indicating light etc. Make - Family Fountains	1.00	Each	16500.00
8	4 Sq mm X 3 Core Submersible cable flat	80.00	Mtr	11200.00
9	Installing, testing, commissioning	1.00	Each	10000.00
Grand Total				739775.52

Terms & Conditions:-

- निविदाओं में भाग लेने वाले संवेदकों/फर्मों द्वारा जमा की जाने वाली निविदा शुल्क, प्रोसेसिंग फीस, धरोहर राशि आयुक्त नगर निगम कोटा-उत्तर की वेबसाइट www.kotamc.org, पर जाकर ऑनलाईन जमा करवानी होगी। जिसकी रसीद ऑनलाईन तकनीकी बिड में संवेदक द्वारा अपलोड करनी होगी। इसके अभाव में संवेदक को असफल कर दिया जायेगा। असफल संवेदक की सिर्फ धरोहर राशि लौटाई जावेगी। निविदा शुल्क एवं प्रोसेसिंग फीस (**Non-Refundable**) वापस नहीं की जावेगी।
- कार्य के विलम्ब की स्थिति में गुणावगुण के आधार पर अनुबन्ध में निहित अधिकतम दर तक शास्ती लगायी जा सकेगी।
- अनुबन्ध करने में असमर्थ रहने अथवा कार्य करने में असमर्थ रहने पर अनुबन्ध की शर्त सं0 2 व 3 के अन्तर्गत आपकी रिस्क एण्ड कास्ट पर नगर निगम को कार्य करने का/जमा योग्य अर्नेस्ट मनी की शास्ती लगाने की कार्यवाही करने का निगम को अधिकार सुरक्षित रहेगा बिड सिक्यूरिटी घोषणा पत्र के अनुसार कार्यवाही कर सकेगा।
- कार्य प्रारम्भ करने से पूर्व एवं कार्य समाप्ति कार्य स्थल के फोटोग्राफ प्रस्तुत करने होंगे एवं कार्य स्थल पर सूचना बोर्ड स्वयं के खर्च पर लगाना होगा।
- कार्य प्रारम्भ करने से पूर्व संबंधित सहा.अभि./कनि.अभि. संबंधित वार्ड पार्षद/जन प्रतिनिधि को सूचित करेंगे एवं उनके सामने गुणवत्ता रिपोर्ट हेतु सेम्पल लिया जाना सुनिश्चित करेंगे।
- न्यूनतम मजदूरी एक्ट एवं श्रम कानूनों की पालना किया जाना अनिवार्य होगा।
- कर्मचारी भविष्य निधि योजना (EPFO) के अन्तर्गत EPF & ESI पंजीयन की प्रति संलग्न करनी होगी एवं EPF & ESI के समस्त प्रकार के दायित्वों का निर्वहन संवेदक का होगा के संबंध में 100/-रु0 के स्टाम्प पर शपथ पत्र प्रस्तुत करना होगा।
- कार्य संपादन प्रतिभूति/सुरक्षा निधि की वापसी अनुबंध की शर्त संख्या 37 के अनुसार होगी।
- संवेदक द्वारा निष्पादित किये जाने वाले अनुबंध में संवेदक यह तथ्य भी स्पष्ट रूप से उल्लेख करेगा की PF & ESI विभाग के किसी प्रकार के दायित्व सृजित होते हैं तो उसकी समस्त जिम्मेदारी संवेदक की होगी।
- वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर. टी. पी. पी. नियम 2013 **Additional Perfomance Security** के लिए नियम 75 । जोडा गया है। जिसके तहत कार्य आदेश जारी से पूर्व नियमानुसार राशि जमा करवानी होगी।
- सुरक्षा निधि (**Perfomance Gurantee**) नियमानुसार प्रत्येक रनिंग बिल व अंतिम बिल से 10 प्रतिशत राशि काटी जावेगी तथा अनुबन्ध की शर्त संख्या 37 के अनुसार लौटाई जावेगी।

Signature of Contractor


 Executive Engineer
 Nagar Nigam, Kota-North


 अभियन्ता
 कोटा उत्तर

कार्यालय नगर निगम, कोटा-उत्तर (राज0)


तकनीकी बिड दस्तावेज चैक लिस्ट

कार्य का नाम:- नगर निगम कोटा-उत्तर क्षेत्र के रामपुरा बाजार में पीपल के पेड़ के पास Beautification and Fountain का कार्य। (कार्य संख्या-~~08~~07)

क्र. सं.	तकनीकी बिड के साथ निम्न दस्तावेज जो संलग्न करने है।	दस्तावेजो का विवरण	संलग्न पेज
1	निविदाओं में भाग लेने वाले संवेदकों/फर्मों द्वारा जमा की जाने वाली निविदा शुल्क, प्रोसेगिंग फीस, धरोहर राशि आयुक्त नगर निगम कोटा-उत्तर की वेबसाइट www.kotamc.org , पर जाकर ऑनलाईन जमा करवानी होगी। जिसकी रसीद ऑनलाईन तकनीकी बिड में संवेदक द्वारा अपलोड करनी होगी की प्रति।		
2	कर्मचारी भविष्य निधि योजना (EPFO) के अन्तर्गत EPF & ESI पंजीयन की प्रति संलग्न करनी होगी		
3	EPF & ESI के समस्त प्रकार के दायित्वों का निवर्हन संवेदक का होगा के संबंध में 100/-रु0 के स्टाम्प पर शपथ पत्र प्रस्तुत करना होगा।		
4	संवेदक को किसी भी राजकीय संस्था विभाग, बोर्ड, कॉर्पोरेशन अथवा उपक्रम में गत 03 वर्षों में ब्लैक लिस्टेड/डिबार अथवा डिफाल्टर घोषित नहीं किया होना चाहिए इस संबंध में स्वप्रमाणित अपने लेटरपेड पर निविदा के साथ संलग्न किया जाना आवश्यक है।		
5	फर्म नगर निगम कोटा एवं अन्य विभाग में पंजीयन की प्रति संलग्न करनी होगी।		
6	फर्म की जीएसटी विभाग में पंजीयन की प्रति।		
7	फर्म का पेनकार्ड नं0 की छायाप्रति संलग्न करनी होगी।		
8	भविष्य में EPF&ESI से श्रमिकों के भुगतान की ओडिट कराने का 50रु के स्टाम्प पर शपथ पत्र संलग्न करेंगे।		
9	शिड्यूल की संवेदक द्वारा अपलोड की प्रति		
10	निविदा में संलग्न सहमति पत्र प्रारूप के अनुरूप		

नोट :- उपरोक्त सभी प्रमाण पत्र स्व प्रमाणित होने चाहिये एवं उक्त दी गई सूचनाएँ मेरी जानकारी एवं विश्वास के अनुसार सही है तथा हमारी फर्म निविदा की समस्त शर्तों एवं नियमों की पालना करने के लिये सहमत है।

हस्ताक्षर निविदादाता


अधिशाषी अभियन्ता
नगर निगम, कोटा-उत्तर

00.0000			-प्रारूप-	
			(लेटरहेड)	
00.0000			00.1	
00.0000			00.2	
00.0000			सहमति-पत्र	
00.0000			00.3	
00.0000			00.4	
00.0000			00.5	
00.0000			00.6	
00.0000			00.7	
00.0000			00.8	
00.0000			00.9	
00.0000			00.10	

श्रीमान
नगर निगम कोटा उत्तर।

विषय : अपनी निविदा हेतु सहमति के संबंध में।

प्रसंग : निविदा क्रमांक.....

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- (1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर हैं।
- (2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- (3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- (4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- (5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक :

(Signature)
Resident Engineer
Nagar Nigam, Kota-North

(Signature)
Contractor

(Signature)
Nagar Nigam, Kota-North