

# MUNICIPAL CORPORATION KOTA (NORTH) RAJASTHAN

(NIT NO. 14/2024-25) ('G' Schedule) (Copy No. 01)

Name of work:- वार्ड नं. 69 नगर निगम कोटा उत्तर में सी सी रोड, नाले, आर सी.सी. नाला व इन्टरलॉकिंग का कार्य। (पुनः निर्माण)

Estimated Cost :- 213.50

Tender Cost:- Rs. 6000/-

Processing Fees :- Rs. 2000/-

Date & time of downloading of Bid

Date & time of online submission of Bid

Date, time and opening of Technical Bid -

Date and Time Opening of Financial Bid

Earnest Money: 106750/- (0.50%)

427000/- (2%) 08 Months

18-11-2024 to 09-12-2024

18-11-2024 to 09-12-2024

10-12-2024 upto 4:00PM

तकनीकी बिड परीक्षण के पश्चात्

Issued

To:

C.R. No.

Date :-

(Rates Based on RUIDP SOR (2023))

| S.No | Particulars  | Qty.    | unit | Rate    | Amount     |
|------|--|---------|------|---------|------------|
| 1    | Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc.   | 4342.00 | cum  | 229.50  | 996489.00  |
| 2    | Providing, laying and spreading of granular sub-base by providing coarse graded Material (Table 400-2), spreading in uniform layers with motor grader on prepared surface, mixing BY MIX IN PLACE METHOD with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per MoRT&H specification clause - 401 including all material, labour, machinery, lighting, guarding and maintenance of diversion.<br><b>Grading - II Material</b> | 198.00  | cum  | 1103.00 | 218394.00  |
| 3    | Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).  | 612.50  | cum  | 4575.00 | 2802187.50 |
| 4    | Carriage of Materials by mechanical transport including loading, unloading and stacking ::Earth  | 3907.80 | cum  | 254.76  | 995551.13  |
| 5    | Random rubble masonry with hard stone in foundation and plinth :Cement mortar 1:6 (1 cement : 6 coarse sand)   | 1667.25 | cum  | 4860.00 | 8102835.00 |
| 6    | Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).  | 300.00  |      | 5910.00 | 1773000.00 |

|    |   |         |     |         |            |
|----|---|---------|-----|---------|------------|
| 7  | 40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 ( 1cement : 5 coarse sand) with joints finished flush. <b>Red sand stone</b>   | 1540.00 | sqm | 783.00  | 1205820.00 |
| 8  | Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 12 mm cement plaster of mix : including Providing /mixing of synthetic fibers compulsorily complying with IS 16481:2022 of 06 mm/12 mm length to be mixed @ 0.25% by weight of Cement i.e. 125 gms per 50 kg Cement up to 900 gms per cum of Concrete/ mortar <b>1:6 (1 cement : 6 fine/ coarse sand)</b>  | 3969.00 | sqm | 213.50  | 847381.50  |
| 9  | Providing and laying damp-proof course with cement concrete grade M-15 (1 : 2 : 4) mortar prepared with 1% solution of water-proof compound complete as per specification . including Providing/mixing of synthetic fibers compulsorily complying with IS 16481:2022 of 06 mm/12 mm length to be mixed @ 0.25% by weight of Cement i.e. 125 gms per 50 kg Cement up to 900 gms per cum of Concrete/ mortar <b>50mm thick.</b>   | 2614.50 | sqm | 445.00  | 1163452.50 |
| 10 | Centring and shuttering with plywood or steel sheet upto two stories ( each story of height upto 3.5 metre from floor level) including strutting, propping etc. and removal of form for : <b>Foundations, footings, bases of columns, etc. for mass concrete.</b>   | 438.00  | sqm | 236.50  | 103587.00  |
| 11 | Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : <b>1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)</b>   | 109.80  | Cum | 6340.00 | 696132.00  |
| 12 | Reinforcement for R.C.C. work at all levels including straightening, cutting, bending, placing in position and binding all complete. <b>Hot rolled deformed bars</b>  | 8620.69 | kg  | 83.30   | 718103.23  |
| 13 | Providing and fixing of precast concrete interlocking tiles of desired shape of M 30 grade manufactured from fully computerized automatic stationery hydraulic vibrio pressed machine and fully computerized automatic batching plant of class A1/A2 as per BS 6717:2001. The CC interlocking paving blocks be laid on average 50mm. thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer in-charge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications. Tensile splitting strength, abrasion and braking load etc. as per BS 6717:2001, Grey cement. <b>80mm thick</b> | 1600.00 | sqm | 792.00  | 1267200.00 |

|    |  |         |     |         |           |
|----|--|---------|-----|---------|-----------|
| 14 | Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. <b>Providing &amp; Fixing in position, MS fabrication work using angles, sqr tubes, c channels etc for various partition frame as per Design &amp; Instructions &amp; Complete in all aspects . including all materials labour, finishing etc complete</b>                 | 2000.00 | kg  | 114.50  | 229000.00 |
| 15 | Providing and fixing of reinforced Ferro-Cement drain covers designed for 'AA' class loading duly marked on cover with adequate steel reinforcement having thickness 75mm to 150mm anti corrosive bitumen painted M.S. plate , Rim and M.S. lifting hooks, Admixtures like plasticizer, bond improving compound, shrinkage, resistance compound, abrasion resistant complete as per approved design etc. <b>Standard Size 1000x800mm (100mm thick) for span 451 to 700mm</b> | 80.00   | sqm | 2885.00 | 230800.00 |


**Total** **21349932.86**

says **213.50**

**Terms & Conditions:-**

- निविदाओं में भाग लेने वाले संवेदकों/फर्मों द्वारा जमा की जाने वाली निविदा शुल्क, प्रोसेसिंग फीस, धरोहर राशि आयुक्त नगर निगम कोटा-उत्तर की वेबसाइट [www.kotamc.org](http://www.kotamc.org), पर जाकर ऑनलाईन जमा करवानी होगी। जिसकी रसीद ऑनलाईन तकनीकी बिड में संवेदक द्वारा अपलोड करनी होगी। इसके अभाव में संवेदक को असफल कर दिया जायेगा। असफल संवेदक की सिर्फ धरोहर राशि लौटाई जावेगी। निविदा शुल्क एवं प्रोसेसिंग फीस (**Non-Refundable**) वापस नहीं की जावेगी।
- कार्य के विलम्ब की स्थिति में गुणावगुण के आधार पर अनुबन्ध में निहित अधिकतम दर तक शास्ती लगायी जा सकेगी
- अनुबन्ध करने में असमर्थ रहने अथवा कार्य करने में असमर्थ रहने पर अनुबन्ध की शर्त सं० 2 व 3 के अन्तर्गत आपकी रिस्क एण्ड कास्ट पर नगर निगम को कार्य करने का/जमा योग्य अर्नेस्ट मनी की शास्ती लगाने की कार्यवाही करने का निगम को अधिकार सुरक्षित रहेगा बिड सिक्यूरिटी घोषणा पत्र के अनुसार कार्यवाही कर सकेगा।
- कार्य प्रारम्भ करने से पूर्व एवं कार्य समाप्ति कार्य स्थल के फोटोग्राफ प्रस्तुत करने होंगे एवं कार्य स्थल पर सूचना बोर्ड स्वयं के खर्च पर लगाना होगा।
- कार्य प्रारम्भ करने से पूर्व संबंधित सहा.अभि./कनि.अभि. संबंधित वार्ड पार्श्वद/जन प्रतिनिधि को सूचित करेग एवं उनके सामने गुणवत्ता रिपोर्ट हेतु सम्पल लिया जाना सुनिश्चित करेगें।
- न्यूनतम मजदूरी एक्ट एवं श्रम कानूनों की पालना किया जाना अनिवार्य होगा।
- निर्माण कार्यों में नियोजित श्रमिकों का कर्मचारी भविष्य निधि योजना के अन्तर्गत पंजीयन करना तथा **PF & ESI** करा कर संबंधित विभाग (**EPFO**) से अदेयता प्रमाण पत्र कार्य के अन्तिम बिल के साथ प्रस्तुत करना होगा।
- कार्य संपादन प्रतिभूति/सुरक्षा निधि की वापसी अनुबंध की शर्त संख्या 37 के अनुसार होगी।
- संवेदक द्वारा निष्पादित किये जाने वाले अनुबंध में संवेदक यह तथ्य भी स्पष्ट रूप से उल्लेख करेगा की **PF & ESI** विभाग के किसी प्रकार के दायित्त सृजित होते हैं तो उसकी समस्त जिम्मेदारी संवेदक की होगी।
- वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर. टी. पी. पी. नियम 2013 **Additional Performance Security** के लिए नियम 75 । जोडा गया है। जिसके तहत कार्य आदेश जारी से पूर्व नियमानुसार राशि जमा करवानी होगी।
- सुरक्षा निधि (**Performance Gurantee**) नियमानुसार प्रत्येक रनिंग बिल व अंतिम बिल से 10 प्रतिशत राशि काटी जावेगी तथा अनुबन्ध की शर्त संख्या 37 के अनुसार लौटाई जावेगी।

Signature of Contractor

  
**राशिशाही अभियन्ता**  
**Executive Engineer**  
**नगर निगम कोटा उत्तर**  
**Nagar Nigam Kota North**

-प्रारूप-  
(लेटरहेड)

सहमति-पत्र

श्रीमान अधिशाषी अभियन्ता,  
नगर निगम कोटा उत्तर।

विषय : अपनी निविदा हेतु सहमति के संबंध में।

प्रसंग : निविदा क्रमांक.....

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- (1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर हैं।
- (2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- (3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- (4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- (5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक :